

Pesticide Risk Assessment for Pollinators
Proceedings from a SETAC Pellston Workshop

January 15 – 21, 2011
Pensacola, Florida, USA

[PAGE * MERGEFORMAT]

32	Table of Contents
33	[TOC \o "1-3" \h \z \u]
34	
35	
36	
37	
38	
39	
40	
41	
42	

CHAPTER 1 INTRODUCTION

Worldwide declines in managed and non-managed pollinators have led to an increased global dialogue and focus concerning the potential factors that may be causing these declines. Although a number of factors have been hypothesized as potential contributors to pollinator declines, at this time, no single factor has been identified as the cause. The available science suggests that pollinator declines are a result of multiple factors which may be acting in various combinations. Research is being directed at identifying the individual and combined stressors that are most strongly associated with pollinator declines. Pesticide use is one of the factors under consideration.

In an effort to further the global dialogue, the Society of Environmental Toxicology and Chemistry (SETAC) held a Pellston Workshop¹ to explore the state of the science on pesticide risk assessment for pollinators. The proposal for this SETAC Workshop was developed by a steering committee (hereafter referred to as the Steering Committee) comprised of members from government and non-governmental organizations who were interested in advancing the science to understand the effect of pesticides on non-target insects. Workshop participants were tasked to advance the current state of the science of pesticide risk assessment by more thoroughly vetting quantitative and qualitative measures of exposure and effects on the individual bee, and where appropriate, on the colony. In doing so, the Workshop aimed to synthesize the global understanding and work that has, thus far, taken place, and to move toward a harmonized process for evaluating and quantitatively characterizing risk to pollinators from exposure to pesticides; and, to identify the data needed to inform that process. The Workshop focused on four major topics:

1. design/identify testing protocols to estimate potential exposure of bees to pesticide residues in pollen and nectar, as well as exposure through other routes;
2. design/identify testing protocols to measure effects of pesticides on developing brood and adult honey bees at both the individual and colony level;

¹ The first Pellston Workshop was held in 1977 to address the needs and means for assessing the hazards of chemicals to aquatic life. Since then, many workshops have been held to evaluate current and prospective environmental issues. Each has focused on a relevant environmental topic, and the proceedings of each have been published as a peer-reviewed or informal report. These documents have been widely distributed and are valued by environmental scientists, engineers, regulators, and managers because of their technical basis and their comprehensive, state-of-the-science reviews. The first four Pellston workshops were initiated before the Society of Environmental Toxicology and Chemistry (SETAC) was effectively functioning. Beginning with the 1982 workshop, however, SETAC has been the primary organizer and SETAC members (on a volunteer basis) have been instrumental in planning, conducting, and disseminating workshop results. Taken from: <http://www.setac.org/node/104>

3. propose a tiered approach for characterizing the potential risk of pesticides to pollinators; and
4. explore the applicability of testing protocols, used for honey bees (*Apis* bees), to measure effects of pesticides and pesticide risk to other non-*Apis* bee species.

Although the term “pollinators” encompasses a broad number of taxa, for the purposes of this SETAC Workshop and its proceedings, the term “pollinators” refers specifically to subspecies and strains of *Apis mellifera* that originated in Europe (i.e., the honey bee) and other (non-*Apis mellifera*) bees, e.g., bumble bees, solitary bees and stingless bees. The Workshop built upon the numerous efforts of different organizations, regulatory authorities, and individuals, both nationally and internationally, aiming to better understand the role and effect(s) of pesticide products on honey bees² and other bee species.

Workshop Balance and Composition

Similar to other timely and relevant scientific issues addressed by SETAC Pellston Workshops, the issue of pollinator protection is of high interest to scientists employed by governments, business, academia and non-governmental organizations. For this reason, SETAC requires that its workshops be similarly balanced. The Workshop on Pesticide Risk Assessment for Pollinators represented an exceptionally diverse composition by both sector (employer) and geography. The forty eight participants (35 panelists and 13 Steering Committee members) included individuals from industry, non-governmental organizations, federal and state governments, the beekeeping community, and academia and represented five continents (South America, Europe, Australia, North America, and Africa) (see Acknowledgments).

This Proceedings of the Workshop on Pesticide Risk Assessment for Pollinators has several sections:

² USDA Technical Working Group Report on Honey Bee Toxicity Testing, July 8 and 9, 2009;[

HYPERLINK

"http://www.aphis.usda.gov/plant_health/plant_pest_info/honey_bees/downloads/twg_report_july_2010.pdf"]

International Commission for Plant-Bee Relationships 10th International Symposium, 2009;[HYPERLINK "http://www.uoguelph.ca/icpbr/pubs/2008%20ICPBR%20symposium%20archives%20Pesticides.pdf"]

- Chapters 2 through 6 provide background and overview of key elements such as bee biology, ecological risk assessment, and protection goals.
- Chapters 7 through 10 capture recommendations by the Workshop on the elements of exposure assessment, effects assessment (laboratory and field testing), and risk assessment.
- Chapters 11 through 14 capture discussion around statistical analysis, modeling, risk management, and research needs.

Pollinators, and the honey bee in particular, have been identified as a valued group of organisms because of the services they provide to agriculture and to ecosystem biodiversity. While both managed and unmanaged (*Apis* and non-*Apis*) bees contribute to crop pollination, most of the current knowledge of the side-effects of agricultural pesticides on pollinators is in relation to the honey bee. Since it is not possible to test all species, regulatory authorities rely on one or several surrogate species to represent a wider range of species within a taxon. Unlike the North American process that uses the honey bee as a surrogate for other terrestrial invertebrates, the European process includes testing requirements for honey bees specifically (representing pollinating insects), and includes other surrogate test species for non-target arthropods in general. The proposed process discussed herein relies mainly on the honey bee, but includes other species, such as bumble bees for example, to represent the many different species of bees. Therefore, it is important to understand the ecology and biology of the *Apis* bee as a test organism, as well as that of non-*Apis* bees.

CHAPTER 2 OVERVIEW OF THE HONEY BEE

Pettis, J.

A key goal of regulatory authorities is to protect non-target organisms from potential adverse effects of pesticides. As it is not possible to test all species, the pesticide risk assessment framework relies on surrogate species to represent major taxa, including insect pollinators. The European honey bee (*Apis mellifera*), among the many different bee species, is a desirable surrogate test species in that it is both commercially valued and is also adaptable to laboratory research. In many countries, such as Canada, and United States, the honey bee is used as a surrogate for insect pollinators and many other non-target terrestrial insects. While honey bees may be subject to collateral effects from the use of pesticides in crop production, they are also the beneficiaries of pesticide applications, as beekeepers routinely employ registered pesticides to manage pest problems that occur in managed hives. The in-hive use of pesticides by beekeepers and the potential exposure of honey bees to environmental mixtures of pesticides used in agriculture coupled with the complex social organization/biology of honey bees can complicate pesticide risk assessment. While these are major challenges facing risk assessment, their resolution will require additional research efforts and so they are beyond the scope of this document and are not addressed further herein (see Chapter 13, Recommendations for Future Research in Pesticide Risk Assessment for Pollinators).

Overview of Honey Bee Biology

From a risk assessment perspective, there are several aspects of honey bee biology which are important to consider as they potentially influence the toxicity studies required as well as the approach for evaluating potential risks. Colony growth and survival are dependent on the collective actions of individuals that perform various critical tasks; therefore, honey bee colonies act collectively as a "superorganism". The different castes of bees within the hive structure have different functions which can result in differential exposure in terms of route, duration, magnitude and mode (direct versus indirect, secondary exposure). The survival of an individual bee may be of little consequence as colonies typically have a 10-30% reserve of workers, which reflects and accommodates the high turn-over rate (of the individual) and

flexibility of the colony to adapt to its environment. An examination of the roles of various castes within the hive and the implication for risk assessments follows.

A honey bee colony is made up of one queen, several drones, thousands of workers and many immature bees in various stages of development (eggs, larvae, pupae). Worker bees are sexually undeveloped females and constitute the vast majority of the adults in a colony. All work, inside and outside the colony, is done by worker bees. Older workers forage outside the hive for pollen and nectar and thus are potentially more exposed to pesticides via contact during foraging (e.g. by direct overspray or by contact with pesticide residues on treated plant surfaces), as well as dietary exposure during collection/ingestion of pollen and nectar. Workers also are a medium by which environmental contaminants come back to the hive. Young workers clean cells and attend brood whereas middle-aged workers do a variety of tasks mainly within the hive. Both young and middle-aged workers can be exposed to pesticides through contaminated food brought back to the hive. Each colony has a single queen. Once she mates with drones, the queen returns to the hive to begin the task of egg-laying; she will lay up to 1200 eggs per day for several years. The queen performs no other work in the hive and continues to be fed royal jelly throughout her lifespan. Drones are male bees whose sole function in the hive is to serve as sperm donors for new queens. Like younger and middle-aged workers, queens and drones can also be exposed to pesticides through contaminated food brought back to the hive or intentionally used in the colony by beekeepers.

Inputs by worker bees into the colony include pollen, nectar, water, and plant exudates (*e.g.*, sap) used to make propolis. Pollen is used as the source of protein. It may be consumed directly, consumed and used to produce brood food or royal jelly, or stored and consumed later as bee bread. While larval bees may consume small quantities of raw pollen directly, they as well as the queen depend on processed secretions (brood food and royal jelly) produced by nurse bees. Availability and quality of pollen can have a great influence on the health status of the colony. Nectar is used as a source of carbohydrates, it may be consumed directly or stored inside the hive converted to honey and consumed later.

From a risk assessment perspective, the large forage area of honey bees complicates the task of estimating potential exposure. Honey bees typically forage in the middle of the day for food within 1-2 miles (2 - 3 km) of the hive, but may forage 5 miles (7 km) or more if food of suitable quality is lacking nearby. The large forage range increases the potential that the

189 pollen and nectar collected by the honey bee may contain pesticide residue(s) used in the
190 foraging vicinity. The time of day when foraging occurs in relation to pesticide application
191 may also influence exposure and therefore the risk assessment. As will be discussed in the
192 following chapters, numerous other factors should be considered in light of bee biology that
193 can impact the design or interpretation of data intended to inform pesticide risk assessment
194 with these organisms.

195

CHAPTER 3 OVERVIEW OF NON-*APIS* BEES

Vaughan, M., Vaissière, B.E., Maynard, G., Kasina, M., Nocelli, R.C.F., Scott-Dupree, C.,
Johansen, E., Brittain, C., Coulson, M., and Dinter, A.

Introduction

Honey bees (*Apis mellifera* L.) can be employed in pesticide toxicity testing either as a the
representative species (i.e., surrogate) for pollinating insects (such as in the EU) or in other
cases to represent other non-target terrestrial invertebrates (such as in North America). As
with many surrogate test organisms, there are considerations and/or limitations to using *Apis*
mellifera as a representative species for pollinators/terrestrial invertebrates in general. For
example, field tests with honey bees can be challenging because of their very long foraging
range, the variability of their foraging area and the forage resources they utilize (Visscher &
Seeley 1982). In semi-field tests, honey bees do not respond well to being kept in cages or
indoor environments for a long period.

Uncertainties exist regarding the extent to which pesticide toxicity data for honey bees can be
considered protective for non-*Apis* bees. Studies have demonstrated variable and inconsistent
toxicity among various bee groups (Torchio 1973, Johansen et al. 1983, Malaspina & Stort
1983, Macieira & Hebling-Beraldo 1989, Peach et al. 1994, Malone et al. 2000, Moraes et al.
2000, Scott-Dupree et al. 2009, Roessink et al. 2011). This variability results, in part, from
the basic biological differences between the highly social honey bees and other non-eusocial
species, as well as intrinsic differences in physiology, life cycle, and behavior between any
two insect species (Thompson and Hunt 1999).

The need to thoroughly explore pesticide risk assessment for non-*Apis* pollinators is more
important now than in the past as many areas around the world are seeing an increasing
demand for insect pollination, but a decreasing availability of pollinating species and the
consequential rising costs for honey bee pollination services to satisfy the needs of
agriculture (Aizen and Harder 2009). As a result, across the globe many farmers are looking
to other managed or wild (unmanaged) non-*Apis* bee species, and scientists are documenting
that many crops are pollinated to a significant level by non-*Apis* bees. For example, managed
bumble bees (*Bombus* spp.) are increasingly being used to support agricultural/horticultural
production. Over 1 million bumble bee colonies of different species were sold worldwide in
2006, primarily for greenhouse fruit and vegetable production (e.g., tomato *Lycopersicon*

esculentum), but also increasingly for commercial orchards and seed production (Velthuis & Doorn 2006).

In the U.S., many growers of alfalfa seed (*Medicago sativa*), almond (*Prunus dulcis*), apple (*Malus domestica*), blueberry (*Vaccinium* spp.), and sweet cherry (*Prunus avium*) are using managed solitary bees such as wood-nesting alfalfa leafcutting bees (*Megachile rotundata*), and blue orchard bees (*Osmia lignaria*), and ground-nesting alkali bees (*Nomia melanderi*). In some places, the use of these non-*Apis* pollinators is already widespread or is becoming more common (Bosch and Kemp 2001). For example, in the U.S. approximately 35,000 tons of alfalfa seed are produced annually with pollination provided by alfalfa leafcutting bees from Canada (Pitts-Singer 2008, Stephen 2003, Mayer and Johansen 2003, James 2011, Pitts-Singer pers. comm. Dec 9, 2011). In Japan, the hornfaced bee (*Osmia cornifrons*) is managed to pollinate orchards of apple and pear (*Pyrus communis*) (Matsumoto et al. 2009), and in Brazil, the carpenter bee *Xylocopa frontalis* can be managed to pollinate the passion fruit (*Passiflora edulis*; Freitas & Oliveira Filho 2003). In Kenya, solitary bees have not yet been commercialized for pollination purposes, but efforts are underway to develop management protocols for solitary bees such as *Xylocopa calens*, *X. incostans*, and *X. flavorufa* for high-value greenhouse crops (Kasina, pers. comm. Oct 5, 2011).

In the tropics, efforts are also underway to develop meliponiculture (stingless beekeeping) as a source of revenue from honey production, other hive products, and rentals for crop pollination. Meliponiculture is well established in countries such as Brazil and Mexico (Nogueira-Neto 1997, Villanueva-Gutiérrez et al. 2005). In Africa there are ongoing efforts to improve the management and expand the use of regionally native stingless bees, for example in Ghana (Kwapong et al. 2010) and in Kenya (Kasina pers. comm. 2011).

At the same time, across the world, there is a growing emphasis on the role of unmanaged or wild bees in agro-ecosystems among agriculture and conservation agencies. For example, in the U.S. this includes national-level ecosystem restoration efforts by the U.S. Department of Agriculture's Natural Resources Conservation Service (USDA-NRCS), mandated under the *Food, Conservation and Energy Act of 2008* (Vaughan and Skinner 2009). These conservation efforts are based upon general trends demonstrating declines in populations of wild bees in agricultural landscapes (Kremen et al. 2004, Biesmeijer et al. 2006, National Research Council 2007), as well as the increasingly large body of research demonstrating the significant role that unmanaged non-*Apis* bees may play in crop pollination (Kremen et al.

Pesticide RA for Pollinators 4-13-13

2002, Kremen et al. 2004, Njoroge et al. 2004, Winfree et al. 2007, Campos 2008, Winfree et al. 2008, Kasina et al. 2009, Isaacs & Kirk 2010, Vieira et al. 2010, Carvalheiro et al. 2011). Furthermore, recent research highlights the importance of a diverse pollinator guild for optimal pollination (Klein et al. 2003, Höhn et al. 2008), as well as the benefits of the interaction between honey bees and wild bees to enhance the pollination effectiveness of honey bees (Greenleaf and Kremen 2006, Carvalheiro et al. 2011).

Non-*Apis* bees are often specialized for foraging on particular flower taxa, such as squash, berries, forage legumes, or orchard crops (e.g. Tepedino 1981, Bosch and Kemp 2001, Javorek et al. 2002, Brunet and Stewart 2010). This specialization is usually associated with more efficient pollination on an individual bee visit basis, which can lead to production of larger and more abundant fruit or seed from certain crops (Greenleaf and Kremen 2006, Klein et al. 2007, but see also Rader et al. 2009). In one study, researchers estimated that non-managed bees contribute an estimated US\$3 billion worth of crop pollination annually to the U.S. economy (Losey and Vaughan 2006). More recently, researchers estimated that in California alone, unmanaged non-*Apis* bees pollinated US\$937 million to US\$2.4 billion worth of crops (Chaplin-Kramer et al. 2011). In addition to their impact on agroecosystems, non-*Apis* pollinators are crucial to native flora. More than 85% of flowering plants benefit from animal pollinators (Ollerton et al. 2011), most of which are insects and the most important of which are bees (Apiformes). To develop appropriate toxicity tests and risk assessment protocols for non-*Apis* bees, however, it is important to understand more about non-*Apis* bees and the unique exposure pathways relevant for them.

Non-*Apis* Bee Biology and Diversity

Worldwide, there are over 20,000 recorded species of bees (Michener 2007, Ascher and Pickering 2011). They range in size from approximately 2 mm (1/12 inch) to more than 25 mm (1 inch), exhibit a wide variety of foraging and nesting strategies, vary from solitary to highly social, and exhibit other diverse life histories.

Bees use nectar mainly as a carbohydrate source and pollen as a source of protein, fatty acids, minerals, and vitamins. Some species also use other plant resources such as resins, leaves, plant hairs, oil, and fragrances to feed their larvae, build and protect nests, or attract mates (Michener 2007). Because they use plant products during all life cycle stages, they are vulnerable to plant protection products that are present or expressed in pollen and nectar, or that are found in or on other plant resources.

During their life cycle, bees undergo a complete metamorphosis where they develop through egg, larval, pupal, and adult stages. It is only the last of these stages, the adult, which most people see and recognize as a bee. During the first three stages, the bee is inside a brood cell of the nest. The length of each stage varies widely between species and is often defined by whether the bee is solitary or social (O'Toole and Raw 1999). In the case of solitary bees, each female works alone to create a brood cell, place a mixture of pollen and nectar into it, and then lay an egg on (or more rarely in) the food. Solitary bees may take a year to complete metamorphosis, although it can happen faster *i.e.*, 4 to 6 weeks in those species that have 2 or 3 generations per year. Social bees, on the other hand, take only a few weeks to complete growth and emerge as adults.

The quantity of food provided at the time of egg-laying depends on whether the larvae are mass-provisioned (*i.e.*, all of the bee's food is supplied in the cell at one time), or if the larvae are progressively fed (*i.e.*, the food is delivered in small amounts over time). Most solitary bees mass-provision their brood cells, as do most stingless bees, whereas honey bees and most bumble bees feed their brood progressively.

Female bees of most species have special morphological structures that enable them to carry pollen back to their nests. For example, the tibiae on the hind legs of honey bees, bumble bees, and stingless bees are modified into corbiculae (a flattened, shallowly depressed area margined with a narrow band of stiff hairs) into which the bee accumulates pollen wetted with nectar and packed into place. Other bee species have scopae to transport pollen. Scopae are fringes, tufts, or brushes of hair on their legs, their thorax, or the undersurface of the abdomen. Scopae are used to transport large amounts of pollen, usually in a dry state.

The wide range of life history traits of bees has implications for their exposure to pesticides (Brittain and Potts 2011) and so relevant aspects of their natural history is describe below.

Generalist and Specialist Foragers

Bee species have several dispositions for pollen collection. Certain species are considered generalist foragers (polylectic). Generalist foragers include species such as honey bees, stingless bees, and bumble bee species, which gather pollen from a wide range of flower species. Other species are considered specialist foragers, (oligolectic) that gather pollen from a narrow range of plant species that are usually related taxonomically. Specialist foragers

however, may gather nectar from a wider range of plants than from which they gather pollen. Examples of oligolectic bees include squash bees (*Xenoglossa* or *Peponapis* spp.), *Macropis* spp., and *Leioproctus* spp., which collect pollen from cucurbits (*Cucurbita* spp.), yellow loosestrife (*Lysimachia* spp.), and geebung (*Persoonia* spp.). A third category of pollen collectors, of which there are very few species, are those bees which are monoleactic. Monolectic foragers are those which feed on pollen from only a single species of plant. (e.g. *Hesperapis araria* which only visits flowers of the plant *Balduina angustifolia* (Asteraceae) in the coastal islands of the northern Gulf of Mexico). (Cane et. al. 1996)... ~~need examples of monolactic species)~~ Monolectic foragers are those which feed on pollen from only a single species of plant. The life cycle of specialists (oligolectic and monolactic) are normally closely tied to their host plants, with the adult female bees emerging from their brood cells when their main pollen sources are flowering (O'Toole and Raw 1999).

Formatted: Kern at 14 pt, Not Highlight

Formatted: Kern at 14 pt, Not Highlight

Formatted: Font: Italic, Kern at 14 pt

Formatted: Kern at 14 pt, Not Highlight

Formatted: Kern at 14 pt, Not Highlight

Social and Solitary Behavior

Bees exhibit a wide range of social behaviors, but depending on their interdependency, bees can be broadly divided into two groups, social or solitary.

Social Bees

Social bees typically live as a colony in a nest with one queen (but occasionally can have more than one queen). The labor of building the nest, caring for offspring, protecting the colony, and foraging for resources is shared among female offspring with greatly reduced reproductive capacity. Only a few species of bees demonstrate highly social (eusocial) behavior. These eusocial species include all species of honey bees in the genus *Apis*, and approximately 400 stingless bee species in the tribe Meliponini. Eusocial bees are found primarily in the tropics and subtropics, with two species, *Apis mellifera* and *Apis cerana*, living in temperate areas. Primitively social (or facultatively eusocial) bees exhibit lesser degrees of eusocial behavior (Michener 2007), where colonies are initiated by queens or dominant females on an annual basis (e.g., Halictidae (sweat bees). Most remaining bee species, the vast majority, are solitary and while sometimes nest together in great numbers, these gregarious bees do not cooperate (Michener 2007, Cane 2008). For these solitary species, the labor of nest construction and provisioning, foraging and egg-laying is all done by single, fertile female bees.

In the world's temperate zones, bumble bees are the best known non-*Apis* social bees.

Bumble bees live in colonies, share the work of foraging and nest construction, and produce

many overlapping generations throughout the year; and thus, they are eusocial. However, unlike honey bees, bumble bee colonies are seasonal. At the end of the summer, most of the bees in the colony die, leaving only a few fertilized queens to [REDACTED] [REDACTED] (usually underground) through the winter. In the spring, each surviving queen will start a new nest, which may eventually grow to include dozens to hundreds of workers, depending on the species. Apart from honey bees, bumble bees are often the first bees active in late winter (foraging at lower temperatures than honey bees) and the last bees active in the autumn (Kearns and Thomson 2001, Goulson 2003).

Most bumble bees are generalist foragers, visiting a wide diversity of flowers. Bumble bees can gather pollen by “buzzing” flowers — holding them tightly and vibrating their flight muscles (with an audible buzz), causing the poricidal anthers to release their pollen. Buzz pollinators are important for ensuring pollination in crops with poricidal anthers such as blueberries, cranberries, and other *Vaccinium* spp., as well as solanaceous plants including tomatoes and eggplants (*Solanum melongena*), but also others such as peppers (*Capsicum annuum*) and strawberry (*Fragaria x ananassa*).

Bumble bees need a suitable cavity in which to nest. Sometimes they build nests aboveground, under a tussock of grass or in hollow trees or walls, but generally they nest underground (Kearns and Thomson 2001). Abandoned rodent burrows are common nest sites, as this space is easily warmed and likely contains nesting and insulating materials, such as fur or dried grass. In this cavity, the queen creates the first few pot-like brood cells from wax secreted by her wax glands, lays eggs, and then forages to provide her brood with pollen and nectar (Goulson 2003). It will take about a month for her to raise this first brood. When this first brood emerges, these bees become workers. They take on the task of foraging and help the queen tend the growing number of brood cells through the summer. At the end of summer, new queens and drones emerge and mate. When the cooler weather of autumn arrives, most of the bees, including the old queen, will die, leaving only the new, mated queens to find appropriate sites in which to hibernate through the winter (Kearns and Thomson 2001).

Bumble bees mainly occur in temperate areas. However, as the pollination demand for greenhouse crops grows, there have been attempts to introduce bumble bee colonies in other non-native temperate zones. The threats of such introduction may include inbreeding with local bumble bee species, competition with the native bees for food resources, and transfer of

pathogens (Oldroyd 1999, Thomson 2004, Stout and Morales 2009), which may result in a decline in the abundance and/or diversity of the native bee community (Dafni et al. 2010) and disruption to the pollination of native plants. In temperate countries, the approach of winter controls the population of these bees through the death of all caste members except newly mated queens. In warmer climates, weather may be more favorable year round and these bees may not diapause, increasing their numbers tremendously within a short duration of their introduction (Beekman et al. 1999, Dafni et al. 2010). Bumble bees therefore, may not be appropriate for providing pollination services in the tropics and thus there is a need to study locally or regionally native stingless bees to provide pollination service for greenhouse crops in the tropics (Slaa et al. 2000, Del Sarto et al. 2005).

Social, Stingless Bees

Stingless bees live in the tropical and southern subtropical areas (Michener, 2007). They live in colonies that number from a few dozen individuals to more than 25,000, and they are active year-round. The colony size and nest architecture are characteristic for each different species. Numerous species can be found in Central and South America. In the Yucatan Peninsula for example, farming of stingless bees for honey and wax was so extensive that European honey bees were not introduced until the 19th century (Crane 1992, Vit et al. 1994, Javier et al. 2001).

Stingless bees are generalist foragers, visiting a broad variety of flowers. However, individual colonies or populations may demonstrate a tendency to visit particular types of flowers or exhibit a temporary fidelity to specific plant species (Ramalho et al. 1994, 1998, 2007). They are known to visit at least 90 crop species and are used to enhance pollination in some crops on a commercial to semi-commercial basis (Heard & Dollin 1998a, Heard 1999).

Most stingless bees nest in a cavity. Typically, these cavities are in trees or hollow logs; however, a few species will move into termite mounds, building walls, or even cavities underground. Nests are often located 2 to 30 m aboveground (Kajobe 2007). Stingless bees line their nest cavity with an envelope of batuman, a tough mixture of wax produced by the bees combined with resins, gums, plant material, and sometimes mud collected from around the nest. The nests are composed of many storage pots of honey and pollen and smaller brood cells. The pots (both storage and brood) are made of cerumen, a mixture of wax and plant resins.

Within the nest, each brood pot is mass provisioned with hypopharyngeal gland secretions, pollen, and honey. An egg is laid on top of these provisions and then the pot is sealed. The nests can have one to several queens depending on the species. Most species of stingless bees have brood cells of two different sizes; the large cells produce gynes (queens) while the small ones produce males and workers (Michener 1974). Caste determination is usually through food provisioning, with the quantity, not the quality, of food determining the caste. Thus gyne cells are provisioned with more food compared to the worker and male brood cells. This is in contrast to the honey bee caste determination where both quantity and quality of brood food are important.

New nests are initiated on a progressive basis. A virgin queen moves into a new cavity with some workers over a period of several weeks. They take materials from the old nest to create the new nest. Hence stingless bees are not capable of long distance migration (Roubik 2006). However, with domestication, new colonies can be established through methods similar to splitting honey bee colonies. Young gynes are moved together with brood, workers, and males to another hive to establish a new colony (Nogueira-Neto 1997, Arzaluz et al. 2002, Villanueva-Gutiérrez et al. 2005, Kwapong et al. 2010).

Solitary bees

The majority of bee species in the world are solitary. A female solitary bee may lay twenty or thirty eggs in her life. For solitary species having one generation per year, one to three weeks after an egg is laid, it hatches and the larva emerges to feed on the combination of pollen and nectar ("bee bread") previously provided by the adult female. The larva grows rapidly for six to eight weeks before pupating. The dormant prepupal or pupal stage typically lasts eight or nine months in temperate climates. When it emerges, the adult bee is fully grown and then needs food (primarily nectar) for egg maturation and energy. Most solitary bees have only one generation per year and have a fairly short season of adult activity. Some solitary species, such as some sweat bees in the genera *Halictus* and *Lasioglossum*, have two or three generations each year and so are present over a longer period of time.

Adult solitary bees are typically active for three to six weeks. Males usually emerge first from the nest, after which they typically loiter around a nesting area or a foraging site in search of a female to mate with. After a female bee emerges, she mates and then spends her time

building and provisioning a nest in which to lay eggs (O'Toole and Raw 1999, Michener 2007, Cane 2008). The adults of a species emerge at roughly the same time each year: for example, early spring in the case of blue orchard bees (*Osmia lignaria*) or midsummer in the case of squash bees (*Peponapis pruinosa*). This emergence normally coincides with the flowering of forage plants, particularly if the bee is a specialist.

About 30% of solitary bee species are twig, or wood-nesting. Most species use hollow stems or abandoned beetle burrows or other tunnels in dead or dying standing trees, but some can chew out a nesting tunnel in the soft central pith of stems and twigs, or in a few cases they may bore their own tunnel in wood (Michener 2007). The other 70% nest in the ground, digging tunnels in bare or partially vegetated, well-drained soil (Potts et al. 2005). Each solitary bee nest will have one or more separate cells in which the female places all the provisions (pollen and nectar) required for the full development of her larvae. While some nests may have only a single cell, most have five or more. In the case of ground-nesting bees, females create a range of underground architectures, from simple tunnels to complex, branching systems with cells usually located 10 cm to 2 m underground. Wood-nesting bees on the other hand, usually stack cells in a single line inside their nest tunnels.

Most wood-nesting species separate individual brood cells with materials they collect, such as leaf pieces, leaf pulp, plant hairs, tree resin, or mud. For example, leafcutting bees (genus *Megachile*) use pieces of leaf or petal to create self-contained brood cells. Using their mandibles, they cut particular sizes and shapes to fit different parts of the brood cell, lining the entire cell. Most other wood-nesting bees, however, do not line the entire cell, but simply build dividing walls across the nesting tunnel, segmenting it into separate brood cells. Blue orchard bees (genus *Osmia*) make these walls with mud or leaf pulp. Large carpenter bees (genus *Xylocopa*) and small carpenter bees (genus *Ceratina*) use wood fibers scraped from the walls of the tunnel to form dividers of compacted sawdust. These bees seal the nest entrance when it is finished with the same materials they use to construct the inner partitions.

Rather than collecting materials from outside the nest with which to line their brood cells, many ground-nesting bee species smoothe the cell walls with their abdomens and then apply a waxy or oily substance produced from special glands near their mouths or on their abdomens to line the cells, thus stabilizing the soil and protecting their brood. The substance lining the cell usually soaks into the soil, making it look shiny and helping to exclude water and control microbes. Plasterer or polyester bees (genus *Colletes*), yellow-faced bees (genus

Pesticide RA for Pollinators 4-13-13

Hylaeus), and other bees from the family Colletidae line each cell with a cellophane-like substance secreted from special glands to create a complete waterproof lining for their underground cells. A few species, such as tiny *Perdita* bees living in the southwestern deserts of the United States, leave their underground cells unlined.

Opportunities for non-*Apis* bees to inform pollinator risk assessment

Some of the life history traits of non-*Apis* bees described here lend themselves to providing useful information for risk assessors. For example, solitary non-*Apis* bees, such as *Osmia* and *Megachile* spp., have a more restricted foraging area than honey bees and use of these species in field testing scenarios may provide more confidence that the test bees are foraging (receiving exposure) from the treated (test) crops (Maccagnani et al. 2003, Zurbuchen et al. 2010). In field test scenarios, typically it is only feasible to apply the product to a small area (e.g., ≤ 2 ha.) of a bee-attractive crop, but honey bees can forage over much larger areas (Visscher & Seeley 1982, Steffan-Dewenter & Kuhn 2003). The extended forage range of honey bees may be a variable in test scenarios. The more limited forage range of many non-*Apis* bees reduces this potential variability, and provides more precise data on pesticide exposure in a field test scenario (Maccagnani et al. 2003, Zurbuchen et al. 2010) (check to see this ref. is added to endnotes). Non-*Apis* bees, especially managed species of social (i.e., bumble bees and stingless bees) and solitary bees, also lend themselves to semi-field experiments as they may be less stressed than honey bees in enclosed cage or greenhouse settings, and thus behave more “naturally.” Table 3-1 provides a list of species that are available for toxicity testing. Further research on the use of these species would inform the use of *Apis mellifera* as a surrogate for other non-*Apis* bees. Table 10-5 also lists available laboratory, semi-field, and field studies with representative groups of solitary and social non-*Apis* bee species.

Conclusions

It is clear that non-*Apis* bees play an important role in supporting diverse plant communities, and an increasingly important role in agriculture. They differ from honey bees in their biological characteristics, which consequently may make them subject to unique exposure routes. At the same time, these characteristics – such as their more limited foraging ranges and relatively unaffected foraging in enclosed areas – could be used to better assess the risks of pesticide applications for pollinators, including honey bees. For several reasons,

Workshop attendees believed it important to consider non-*Apis* bees among its discussions on pesticide risk assessment for pollinators, including: (i) the increased understanding of the value of non-*Apis* bees in commercial agriculture; (ii) the critical role they play in natural ecosystems; (iii) increased research being conducted with them; and, (iv) the potential value they may add to the understanding of potential risks from pesticides to these taxa. For these reasons the Participants of the Workshop considered when and how non-*Apis* bee species may be incorporated and considered in a pesticide risk assessment for pollinators.

Reference

- Abbott VA, Nadeau JL, Higo HA, Winston ML. 2008. Lethal and sublethal effects of imidacloprid on *Osmia lignaria* and clothianidin on *Megachile rotundata* (Hymenoptera: Megachilidae). *Journal of Economic Entomology*. 101(3):784-796.
- Aizen MA, Harder LD. 2009. The global stock for domesticated honey bees is growing slower than agricultural demand for pollination. *Current Biology*. 19:915-918.
- Arzaluz A, Obregón F, Jones R. 2002. Optimum brood size for artificial propagation of the stingless bee *Scaptotrigona mexicana*. *Journal of Apicultural Research*. 41:62-63.
- Ascher JS, Pickering J. 2011. Discover Life bee species guide and world checklist (Hymenoptera: Apoidea: Anthophila). [HYPERLINK "http://www.discoverlife.org/mp/20q?guide=Apoidea_species"] [Accessed on January 5, 2012]
- Babendreier D, Karlberger N, Romes J, Fluri P, Bigler F. 2004. Pollen consumption in honey bee larvae: a step forward in risk assessment of transgenic plants. *Apidologie*. 35:293-300.
- Beekman M, van Stratum P, Veerman A. 1999. Selection for non-diapause in the bumblebee *Bombus terrestris*, with notes on the effect of inbreeding. *Entomologia Experimentalis et Applicata*. 93:69-75.
- Beekman M, Ratnieks FLW. 2000. Long-range foraging by the honey-bee, *Apis mellifera* L. *Functional Ecology* 14 :490-496.
- Biesmeijer JC, Roberts SPM, Reemer M, Ohlemüller R, Edwards M, Peeters T, Schaffers AP, Potts SG, Kleukers R, Thomas CD, Settele J, Kunin WE. 2006. Parallel declines in pollinators and insect-pollinated plants in Britain and the Netherlands. *Science*. 313:351-354.
- Biliński M, Teper D. 2004. Rearing and utilization of the red mason bee - *Osmia rufa* L. (Hymenoptera, Megachilidae) for orchard pollination. *Journal of Apicultural Research*. 48:69-74.
- Bosch J, Kemp W. 2001. *How to Manage the Blue Orchard Bee as an Orchard Pollinator*. Sustainable Agriculture Network. Beltsville, MD. 88 pp.
- Brittain C, Potts SG. 2011. The potential impacts of insecticides on the life-history traits of bees and the consequences for pollination. *Basic and Applied Ecology*. 12(4):321-331.
- Brunet J, Stewart C. 2010. Impact of bee species and plant density on alfalfa pollination and potential for gene flow. *Psyche*. doi:10.1155/2010/201858

- 594 Campos MJO. 2008. Landscape management and pollinator richness in tomato (*Lycopersicum esculentum* Mill,
595 Solanaceae) crops in southeastern Brazil. In: *Pollinator Management in Brazil*. Ministry of Environment.
596 pp 26-29.
597
- 598 Cane J. 2008. Bees (Hymenoptera: Apoidea: Apiformes). *Encyclopedia of Entomology*. Springer Verlag. 2:419-
599 434.
600
- 601 JH Cane, RR Snelling, and LJ Kerwin. 1996. A new monolectic coastal bee, *Hesperapis oraria* Snelling and
602 Stage (Hymenoptera: Melittidae), with a review of desert and neotropical disjunctives in the southeastern U.S.,
603 *Journal of the Kansas Entomological Society*. 69(4):238-247.
604
- 605
- 606 Carvalheiro LG, Veldtman R, Shenkute AG, Tesfay GB, Pirk CWW, Donaldson JS, Nicolson SW. 2011.
607 Natural and within-farmland biodiversity enhances crop productivity. *Ecol. Lett.* 14:251-259.
608
- 609 Chaplin-Kramer R, Tuxen-Bettman K, Kremen C. 2011. Value of wildland habitat for supplying pollination
610 services to California agriculture. *Rangelands*. 34(3):33-41.
611
- 612 Crane E. 1992. The past and present status of beekeeping with stingless bees. *Bee World*. 73:29-42.
613
- 614 Dafni A, Kevan P, Gross CL, Goka K. 2010. *Bombus terrestris*, pollinator, invasive and pest: An assessment of
615 problems associated with its widespread introductions for commercial purposes. *Applied Entomology and*
616 *Zoology*. 45(1):101-113.
617
- 618 de Oliveira Cruz D, Magalhães Freitas B, da Silva LA, Sarmento da Silva EM, Abrahão Bomfim IG. 2005.
619 Pollination efficiency of the stingless bee *Melipona subnitida* on greenhouse sweet pepper. *Pesquisa*
620 *Agropecuária Brasileira*. 40(12):1197-1201.
621
- 622 Del Sarto MCL, Peruquetti RC, Campos LAO. 2005. Evaluation of the neotropical stingless bee *Melipona*
623 *quadrifasciata* (Hymenoptera: Apidae) as pollinator of greenhouse tomatoes. *Journal of Economic*
624 *Entomology*. 98: 260-266.
625
- 626 Freitas BM. 2004. *Solitary Bees: Conservation, Rearing and Management for Pollination*. Imprensa
627 Universitaria. Fortaleza, CE - Brazil. 285 pp.
628
- 629 Evans E, Burns I, Spivak M. 2007. *Befriending Bumble Bees: A Practical Guide to Raising Local Bumble Bees*.
630 University of Minnesota Extension. Publication 08484. St Paul, MN. 65 pp.
631
- 632 Freitas BM, Oliveira Filho JH. 2001. Criação racional de mamangavas para polinização em áreas agrícolas.
633 Fortaleza: Banco do Nordeste. 96 pp.
634
- 635 Freitas BM, Oliveira Filho JH. 2003. Ninhos racionais para mamangava (*Xylocopa frontalis*) na polinização do
636 maracujá-amarelo (*Passiflora edulis*). *Ciência Rural*. 33:1135-1139.
637
- 638 Gels JA, Held DW, Potter DA. 2002. Hazards of insecticides to the bumble bees *Bombus impatiens*
639 (Hymenoptera : Apidae) foraging on flowering white clover in turf. *Journal of Economic Entomology*.
640 95:722-728.
641
- 642 George DA, Rinker CM. 1982. Residues of commercially used insecticides in the environment of *Megachile*
643 *rotundata*. *Journal of Economic Entomology*. 75:319-323.
644
- 645 González AJ, Medellín MS. 1991a. La división artificial de la abeja Xunan Kab. Revista YIK'EL-KAB A.C.
646
- 647 González AJ, Medellín MS. 1991b. Manual práctico para criar abejas indígenas sin aguijón. YIK'EL-KAB.
648
- 649 Goulson D. 2003. *Bumblebees: Their Behaviour and Ecology*. Oxford University Press. Oxford, U.K. 235 pp.
650
- 651 González AJ, de Araujo Freitas JC. 2005. *Manual de Meliponicultura Mexicana*. Universidad Autónoma de
652 Yucatán/Fundación Produce Guerrero. 46 pp. Edición de Impresos Gramma.
653
- 654 Gradish AE, Scott-Dupree CD, Cutler GC. 2011a. Susceptibility of *Megachile rotundata* to insecticides used in
655 wild blueberry production in Atlantic Canada. *Journal of Pest Science*. Submitted August 2011.
- Pesticide RA for Pollinators 4-13-13

Formatted: Font: 10 pt

Formatted: Indent: Left: 0", First line: 0"

- Gradish AE, Scott-Dupree CD, Frewin AJ, Cutler GC. 2011b. Lethal and sub-lethal effects of some insecticides recommended for wild blueberry on the pollinator *Bombus impatiens*. *Canadian Entomologist*. Accepted July 2011.
- Gradish AE, Scott-Dupree C D, Shipp L, Harris CR, Ferguson G. 2010. Effect of reduced risk pesticides for use in greenhouse vegetable production on *Bombus impatiens* (Hymenoptera: Apidae). *Pest Management Science*. 66(2):142-146.
- Greco MK, Spooner-Hart RN, Beattie GAC, Barchia I, Holford P. 2011. Stocking rates of *Trigona carbonaria* for the pollination of greenhouse capsicums. *Journal of Apicultural Research*. 50(4):299-305.
- Greenleaf S, Kremen C. 2006a. Wild bees enhance honey bees' pollination of hybrid sunflower. *Proceedings of the National Academy of Sciences USA*. 103:13890-13895.
- Greenleaf S, Kremen C. 2006b. Wild bee species increase tomato production and respond differently to surrounding land use in Northern California. *Biological Conservation*. 133:81-87.
- Greenleaf S, Williams NM, Winfree R, Kremen C. 2007. Bee foraging ranges and their relationship to body size. *Oecologia*. 153:589-596
- Heard TA. 1998. Propagation of hives of the stingless bee *Trigona carbonaria*. *Journal of the Australian Entomological Society*. 27:303-304.
- Heard TA. 1999. The role of stingless bees in crop pollination. *Annual Review of Entomology* 44:183-206.
- Heard TA, Dollin A. 1998a. Crop pollination with native stingless bees. *Native bees of Australia Series, Booklet 6*. Australian Native Bee Research Centre: Sydney.
- Heard TA, Dollin A. 1998b. Keeping Australian stingless bees in a log or box. In: *Native bees of Australia Series, Booklet 5*. Australian Native Bee Research Centre: Sydney. pp 1-14.
- Hogdson EW, Pitts-Singer TL, Barbour JD. 2011. Effects of the insect growth regulator, novaluron on immature alfalfa leafcutting bees, *Megachile rotundata*. *Journal of Insect Science*. 11:43.
- Hogendoorn K, Gross CL, Sedgely M, Keller MA. 2006. Increased tomato yield through pollination by native Australian blue-banded bees (*Amegilla chlorocyanea* Cockerell). *Journal of Economic Entomology*. 99:828-833.
- Höhn P, Tschamtké T, Tylianakis JM, Steffan-Dewenter I. 2008. Functional group diversity of bee pollinators increases crop yield. *Proceedings of the Royal Society B-Biological Sciences*. 275:2283-2291.
- Huntzinger C, James RR, Bosch J, Kemp W P. 2008. Fungicide tests on adult alfalfa leafcutting bees *Megachile rotundata* (F.) (Hymenoptera: Megachilidae). *Journal of Economic Entomology*. 101:1088-1094.
- Isaacs R, Kirk AK. 2010. Pollination services provided to small and large highbush blueberry fields by wild and managed bees. *Journal of Applied Ecology*. 47:841-849.
- James R. 2011. Bee Importation, Bee Price Data, and Chalkbrood. *Proceedings of the Western Alfalfa Seed Growers Association (WASGA)*. Las Vegas, NV. January 23-25, 2011.
- Javier J, Quezada-Euan JG, May-Itza WJ, Gonzalez-Acereto JA. 2001. Meliponiculture in Mexico: problems and perspective for development. *Bee World*. 82:160-167.
- Javorek S K, Mackenzie KE, Vander Kloet SP. 2002. Comparative pollination effectiveness among bees (Hymenoptera: Apoidea) on lowbush blueberry (Ericaceae: *Vaccinium angustifolium*). *Annals of the Entomological Society of America*. 95:345-351.
- Johansen CA, Mayer DF. 1990. *Pollinator Protection: A Bee and Pesticide Handbook*. Wicwas. Cheshire, CT. 212 pp.

- Johansen CA, Mayer DF, Eves JD, Kious CW. 1983. Pesticides and bees. *Environmental Entomology*. 12:1513-1518.
- Johansen CA, Rincker CM, George DA, Mayer DF, Kious CW. 1984. Effects of aldicarb and its biologically-active metabolites on bees. *Environmental Entomology*. 13:1386-1398.
- Kajobe R. 2007. Nesting biology of equatorial Afrotropical stingless bees (Apidae; Meliponini) in Bwindi Impenetrable National Park, Uganda. *Journal of Apicultural Research*. 46: 245-255.
- Kasina, Muo. October 5, 2011. Personal Communication. Principal Entomologist, Kenya Agricultural Research Institute, NARL P.O. Box 14733-00800, Nairobi, Kenya.
- Kasina M, Mburu J, Kraemer M, Holm-Müller K. 2009. Economic benefit of crop pollination by bees: A case of Kakamega small-holder farming in western Kenya. *Journal of Economic Entomology*. 102(2):467-473
- Kearns CA, Thompson JD. 2001. *The Natural History of Bumblebees. A Sourcebook for Investigations*. Boulder: University Press of Colorado. 130 pp.
- Kim J, Williams N, Kremen C. 2006. Effects of cultivation and proximity to natural habitat on ground-nesting native bees in California sunflower fields. *Journal of the Kansas Entomological Society*. 79:309-320.
- Klein AM, Vaissiere BD, Cane JH, Steffan-Dewenter I, Cunningham SA, Kremen C, T. Tschamtkke. 2007. Importance of pollinators in changing landscapes for world crops. *Proceedings of the Royal Society B-Biological Sciences*. 274:303-313.
- Klein AM, Steffan-Dewenter I, Tschamtkke T. 2003. Fruit set of highland coffee increases with the diversity of pollinating bees. *Proceedings of the Royal Society B-Biological Sciences*. 270:955-961.
- Konrad R, Ferry N, Gatehouse A, Babendreier D. 2008. Potential effects of oilseed rape expressing oryzacystatin-1 (OC-1) and of purified insecticidal proteins on larvae of the solitary bee *Osmia bicornis*. *PLoS ONE*. 3(7):e2664. doi:10.1371/journal.pone.0002664.
- Kremen C, Williams NM, Thorp RW. 2002. Crop pollination from native bees at risk from agricultural intensification. *Proceedings of the National Academy of Sciences USA*. 99:16812-16816.
- Kremen C, Williams NM, Bugg RL, Fay JP, Thorp RW. 2004. The area requirements of an ecosystem service: crop pollination by native bee communities in California. *Ecology Letters*. 7:1109-1119.
- Krischik, Vera. 2011. Personal Communication. Associate Professor. 219 Hodson Hall, 1980 Folwell Ave., University of Minnesota. St. Paul, MN 55108.
- Krunic M, Pinzauti M, Felicioli A, Stanisavljevic LJ. 1995. Further observations on *Osmia cornuta* Latr. and *O. rufa* L. as alternative fruits pollinators, domestication and utilization. *Archives of Biological Sciences Belgrade*. 47:59-66.
- Kwapong P, Aidoo K, Combey R, Karikari A. 2010. *Stingless Bees: Importance, management and utilization. A Training Manual for Stingless Beekeeping*. Unimax Macmillan Ltd, Ghana.
- Ladurner E, Bosch J, Kemp WP, Maini S. 2005. Assessing delayed and acute toxicity of five formulated fungicides to *Osmia lignaria* Say and *Apis mellifera*. *Apidologie*. 36:449-460.
- Ladurner E, Bosch J, Kemp WP, Maini S. 2008. Foraging and nesting behavior of *Osmia lignaria* (Hymenoptera: Megachilidae) in the presence of fungicides: cage studies. *Journal of Economic Entomology*. 101:647-653.
- Laurent FM, Rathahao E. 2003. Distribution of [C14] imidacloprid in sunflowers (*Helianthus annuus* L.) following seed treatment. *Journal of Agricultural and Food Chemistry*. 51:8005-8010.
- Losey JE, Vaughan M. 2006. The economic value of ecological services provided by insects. *Bioscience*. 56:311-323.

- Maccagnani B, Ladurner E, Santi F, Burgio G. 2003. *Osmia cornuta* (Hymenoptera, Megachilidae) as a pollinator of pear (*Pyrus communis*): fruit- and seed-set. *Apidologie*. 34:207-216.
- Macieira OJD, Hebling-Beraldo MJA. 1989. Laboratory toxicity of insecticides to workers of *Trigona spinipes* (F. 1793) (Hymenoptera: Apidae). *Journal of Apicultural Research*. 28:3-6.
- Mader E, Spivak M, Evans E. 2010. *Managing Alternative Pollinators: A Handbook for Beekeepers, Growers, and Conservationists*. Beltsville, MD. USDA Sustainable Agriculture Research and Education (SARE). SARE Handbook 11. 162 pp.
- Malaspina O, Stört AC. 1983. Estudo da tolerância ao DDT e relação com outros caracteres em abelhas sociais. *Revista Brasileira de Biologia*. 43:327-330.
- Malone L, Burgess E, Stefanovic D, Gatehouse H. 2000. Effects of four protease inhibitors on the survival of worker bumblebees, *Bombus terrestris* L. *Apidologie*. 31:25-38.
- Matsumoto S, Abe A, Maejima T. 2009. Foraging behavior of *Osmia cornifrons* in an apple orchard. *Scientia Horticulturae*. 121:73-79.
- Mayer D, Johansen C. 2003. The rise and decline of *Nomia melanderi* (Hymenoptera: Halictidae) as a commercial pollinator for alfalfa seed. *For Nonnative Crops, Whence Pollinators of the Future*. Entomological Society of America. Lanham, MD. Pp. 139-149.
- Mayer DF, Kovacs G, Lunden JD. 1998. Field and laboratory tests on the effects of cyhalothrin on adults of *Apis mellifera*, *Megachile rotundata* and *Nomia melanderi*. *Journal of Apicultural Research*. 37:33-37.
- Mayer DF, Lunden JD. 1999. Field and laboratory tests of the effects of fipronil on adult female bees of *Apis mellifera*, *Megachile rotundata* and *Nomia melanderi*. *Journal of Apicultural Research*. 38:191-197.
- Michener CD. 1974. *The Social Behaviour of Bees: A Comparative Study*. The Belknap press of Harvard University Press. Cambridge, Massachusetts. 404 pp.
- Michener CD. 2007. *The Bees of the World*. 2nd edition. John Hopkins University Press. Baltimore, MD. 992 pp.
- Moraes SS, Bautista AR, Viana BF. 2000. Avaliação da toxicidade aguda (DL50 e CL50) de inseticidas para *Scaptotrigona tubida* (Smith) (Hymenoptera: Apidae): via de contacto. *Anais da Sociedade Entomológica do Brasil*. 29:31-37.
- Morandin LA, Winston ML, Franklin MT, Abbott VA. 2005. Lethal and sub-lethal effects of spinosad on bumble bees (*Bombus impatiens* Cresson). *Pest Management Science*. 61:619-626.
- National Research Council – Committee on Status of Pollinators in North America. 2007. *Status of Pollinators in North America*. Washington, D.C.: The National Academies Press.
- Njoroge GN, Gemmill B, Bussmann R, Newton LE, Ngum VW. 2004. Pollination ecology of *Citrullus lanatus* at Yatta, Kenya. *International Journal of Tropical Insect Science*. 24(1):73-77.
- Nogueira-Neto P. 1997. Vida e criação de abelhas indígenas sem ferrão. 1st ed. São Paulo: Nogueirapis.
- OEDC (Organization for Economic Co-operation and Development). 1998. Guidelines for the testing of chemicals. Honey Bees, Acute Oral and Contact Toxicity Test, n.213, n.214.
- Oldroyd BP. 1999. Coevolution while you wait: *Varroa jacobsoni*, a new parasite of western honey bees. *Trends in Ecology & Evolution*. 14:312-315.
- Ollerton J, Winfree R, Tarrant S. 2011. How many plants are pollinated by animals? *Oikos*. 120:321-326.
- O'Toole C, Raw A. 1999. *Bees of the World*. London: Blandford. 192 pp.
- Peach ML, Alston DG, Tepedino VJ. 1995. Sublethal effects of carbaryl bran bait on nesting performance, parental investment, and offspring size and sex ratio of the alfalfa leafcutting bee (Hymenoptera: Megachilidae). *Environmental Entomology*. 24:34-39.

Pesticide RA for Pollinators 4-13-13

- Pereboom JJM. 2000. The composition of larval food and the significance of exocrine secretions in the bumblebee *Bombus terrestris*. *Insectes Sociaux*. 47:11–20.
- Pitts-Singer T. 2008. Past and present management of alfalfa bees. *Bee Pollination in Agricultural Ecosystems*. Pittsinger, T.L. and R. James, eds. Oxford Press. New York, NY. Pp. 105-123.
- Pitts-Singer, Theresa. December 9, 2011. Personal Communication. Research Entomologist, USDA ARS Bee Biology & Systematics Laboratory, Utah State University, Logan, Utah 84322.
- Potts SG, Vulliamy B, Roberts S, O'Toole C, Dafni A, Ne'eman G, Willmer PG. 2005. Role of nesting resources in organizing diverse bee communities in a Mediterranean landscape. *Ecological Entomology*. 30:78-85.
- Quezada Euán JJG. 2005. Biología y uso del las abejas nativas sin aguijón de la península de Yucatán, Mexico (Hymenoptera: Meliponini) Tratados 16, ediciones de la Universidad Autónoma de Yucatán).
- Quezada Euán JJG. 2009. Potencial de las abejes nativas en la polinización de cultivos. *Acta boil. Colomb*. 14:169-172.
- Rader R, Howlett BG, Cunningham SA, Westcott DA, Newstrom-Lloyd LE, Walker MK, Teulon DAJ, Edwards W. 2009. Alternative pollinator taxa are equally efficient but not as effective as the honeybee in a mass flowering crop. *Journal of Applied Ecology*. 46 : 1080-1087.
- Ramalho M, Giannini TC, Malagodi-Braga KS, Imperatriz-Fonseca VL. 1994. Pollen harvest by stingless bees foragers (Hymenoptera, Apidae, Meliponinae). *Grana*. 33:239-244.
- Ramalho M, Imperatriz-Fonseca VL, Giannini TC. 1998. Within-colony size variation of foragers and pollen load capacity in the stingless bee *Melipona quadrisfasciata anthidioides* Lepeletier (Apidae, Hymenoptera). *Apidologie*. 29:221-228.
- Ramalho M, Silva MD, Carvalho CAL. 2007. Dinâmica de uso de fontes de pólen por *Melipona scutellaris* Latreille (Hymenoptera: Apidae): uma análise comparativa com *Apis mellifera* L. (Hymenoptera: Apidae), no Dominio Tropical Atlântico. *Neotropical Entomology*. 36(1):38-45.
- Riedl H, Johansen E, Brewer L, Barbour J. 2006. *How to Reduce Bee Poisoning from Pesticides*. Oregon State University. Corvallis, OR. 25 pp.
([HYPERLINK "http://extension.oregonstate.edu/catalog/pdf/pnw/pnw591.pdf"] accessed 2011 Aug. 30)
- Roessink I, van der Steen JJM, Kasina M, Gikungu M, Nocelli RCF. 2011. Is the European honey bee (*Apis mellifera mellifera*) a good representative for other pollinator species? SETAC Europe 21st Annual Meeting: Ecosystem Protection in a Sustainable World: a Challenge for Science and Regulation. Milan, Italy, 15-19 May 2011.
- Roubik DW. 2006. Stingless bee nesting biology. *Apidologie*. 37:124-137.
- Sampson BJ, Knight PR, Cane JH, Spiers JM. 2007. Foraging behavior, pollinator effectiveness, and management potential of the new world squash bees *Peponapis pruinosa* and *Xenoglossa strenua* (Apidae: Eucerini). *HortScience*. 42:459.
- Scott-Dupree CD, Conroy L, Harris CR. 2009. Impact of currently used or potentially useful insecticides for canola agroecosystems on *Bombus impatiens* (Hymenoptera: Apidae), *Megachile rotundata* (Hymenoptera: Megachilidae), and *Osmia lignaria* (Hymenoptera: Megachilidae). *Journal of Economic Entomology*. 102(1):177-182.
- Sekita N, Yamada M. 1993. Use of *Osmia cornifrons* for pollination of apples in Aomori Prefecture, Japan. *Japan Agricultural Research Quarterly*. 26(4):264-270.
- Shuler RE, Roulston TH, Farris GE. 2005. Farming practices influence wild pollinator populations on squash and pumpkin. *Journal of Economic Entomology*. 98:790-795.
- Pesticide RA for Pollinators 4-13-13

- 902 Slaa JE, Sanchez LA, Sandi M, Salazar W. 2000. A scientific note on the use of stingless bees for commercial
903 pollination in enclosures. *Apidologie*.31:141-142.
- 904
- 905 Steffan-Dewenter I, Kuhn A. 2003. Honeybee foraging in differentially structured landscapes. *Proceedings of*
906 *the Royal Society B-Biological Sciences*. 270:569-575.
- 907
- 908 Stephen WP. 2003. Solitary bees in North American agriculture: A perspective. *For Nonnative Crops, Whence*
909 *Pollinators of the Future*. Entomological Society of America. Lanham, MD. Pp. 41-66.
- 910
- 911 Stout J, Morales C. 2009. Ecological impacts of invasive alien species on bees. *Apidologie*. 40:388-409.
- 912
- 913 Taséi JN. 2002. Impact of agrochemicals on non-*Apis* bees. pp.101-131 in J. Devillers & M.H. Pham-Delègue
914 (eds.) *Honey Bees: Estimating the Environmental Impact of Chemicals*. Taylor & Francis. London, UK. 332
915 pp.
- 916
- 917 Taséi JN, Carre S, Moscatelli B, Grondeau C. 1988. Recherche de la D.L. 50 de la deltamethrine (Decis) chez
918 *Megachile rotundata* F. Abeille pollinistatrice de la luzerne (*Medicago sativa* L.) et des effets de doses
919 infralethales sur les adultes et les larves. *Apidologie*. 19(3):291-306.
- 920
- 921 Taséi JN, Ripault G, Rivault E. 2001. Hazards of imidacloprid seed coating to *Bombus terrestris* (Hymenoptera:
922 Apidae) when applied to sunflower. *Journal of Economic Entomology*. 94:623-627.
- 923
- 924 Tepedino VJ. 1981. The pollination efficiency of the squash bee (*Peponapis pruinosa*) and the honey bee (*Apis*
925 *mellifera*) on summer squash (*Cucurbita pepo*). *Journal of the Kansas Entomological Society* 54:359-377.
- 926
- 927 Tew JE. 1997. *Protecting Honey Bees from Pesticides*. The Ohio State University, Horticulture and Crop
928 Science, Factsheet HYG-2161-97. Wooster, OH. [<http://ohioline.osu.edu/hyg-fact/2000/2161.html> accessed
929 4 January 2012].
- 930
- 931 Thompson HM, Hunt LV. 1999. Extrapolating from honeybees to bumblebees in pesticide risk assessment.
932 *Ecotoxicology*. 8:147-166.
- 933
- 934 Thompson HM. 2001. Assessing the exposure and toxicity of pesticides to bumblebees (*Bombus* sp.).
935 *Apidologie*. 32:305-321.
- 936
- 937 Thomson D. 2004. Competitive interactions between the invasive European honey bee and native bumble bees.
938 *Ecology*. 85:458-470.
- 939
- 940 Torchio P. 1983. The effects of field applications of naled and trichlorfon on the alfalfa leafcutting bee,
941 *Megachile rotundata* (Fabricius). *Journal of the Kansas Entomological Society*. 56:62-68.
- 942
- 943 Tuell JK, Isaacs R. 2010. Community and species-specific responses of wild bees to insect pest control
944 programs applied to a pollinator-dependent crop. *Journal of Economic Entomology*. 103:668-675.
- 945
- 946 Vaissière BE, Merritt SJ, Keim DL. 1985. *Melissodes thelypodii* Cockerell (Hymenoptera: Anthophoridae), an
947 effective pollinator of hybrid cotton on the Texas High Plains. p. 398-399 in J.M. Brown (ed.) *Proceedings*
948 *of the Beltwide Cotton Production Research Conference*. National Cotton Council of America. Memphis,
949 TN.
- 950
- 951 Valdovinos-Núñez GR, Quezada-Euán JJG, Ancona-Xiu P, Moo-Valle H, Carmona A, Sánchez ER. 2009.
952 Comparative toxicity of pesticides to stingless bees (Hymenoptera: Apidae: Meliponini). *Journal of*
953 *Economic Entomology*. 102(5):1737-1742.
- 954
- 955 van der Steen JJM. 1994. Method development for the determination of the contact LD50 of pesticides to
956 bumblebees (*Bombus terrestris* L.). *Apidologie*. 25:463-465.
- 957
- 958 van der Steen JJM, Bortolotti L, Chauzat MP. 2008. Can pesticide acute toxicity for bumblebees be derived
959 from honeybee LD50 values? *Hazards of pesticides to bees – 10th International Symposium of the ICP-BR*
960 *Bee Protection Group*. October 8-10, Bucharest (Romania).
- 961
- 962 Vaughan M, Skinner M. 2009. *Using Farm Bill programs for pollinator conservation*. United States Department
963 of Agriculture Natural Resources Conservation Service. Pollinator Technical Note No: 78.

Pesticide RA for Pollinators 4-13-13

964
965 Velthuis HHW, van Doorn A. 2006. A century of advances in bumblebee domestication and the economic and
966 environmental aspects of its commercialization for pollination. *Apidologie*. 37:421-451.
967
968 Vieira PFSP, Cruz DO, Gomes MFM, Campos LAO, Lima JE. 2010. Valor econômico da polinização por
969 abelhas mamangavas no cultivo do maracujá-amarelo. *Revista de la rede Iberoamericana de Economía*
970 *Ecológica*. 15:43-53.
971
972 Villanueva-Gutiérrez R, Buchmann S, Donovan AJ, Roubik D. 2005. *Crianza y Manejo de la Abeja Xunan Cab*
973 *en la Península Yucatán*. ECOSUR-University of Arizona, USA. 35 pp.
974
975 Visscher PK, Seeley TD. 1982. Foraging strategy of honey bee colonies in a temperate deciduous forest.
976 *Ecology*. 63:1790-1801.
977
978 Vit P, d'Albore R. 1994. Melissopalynology of stingless bees (Apidae: Meliponinae) from Venezuela. *Journal*
979 *of Apicultural Research*. 33: 145-154.
980
981 Waller G. 1969. Susceptibility of an alfalfa leafcutting bee to residues of insecticides on foliage. *Journal of*
982 *Economic Entomology*. 62:189-192.
983
984 Wilson RL, Abel CA. 1996. Storage conditions for maintaining *Osmia cornifrons* (Hymenoptera: Megachilidae)
985 for use in germplasm pollination. *Journal of the Kansas Entomological Society*. 69(3):270-271.
986
987 White J, Youngsoo S, Park Y. 2009. Temperature-Dependent Emergence of *Osmia cornifrons* (Hymenoptera:
988 Megachilidae) Adults. *Journal of Economic Entomology*. 102(6):2026-2032.
989
990 Winfree R, Williams NM, Dushoff J, Kremen C. 2007. Native bees provide insurance against ongoing honey
991 bee losses. *Ecology Letters*. 10:1105-1113.
992
993 Winfree R, Williams NM, Gaines H, Ascher JS, Kremen C. 2008. Wild bee pollinators provide the majority of
994 crop visitation across land-use gradients in New Jersey and Pennsylvania, USA. *Journal of Applied*
995 *Ecology*. 45:793-802.
996
997 Winston ML. 1987. *The Biology of the Honey Bee*. Harvard Univ. Press. Cambridge, MA. 294 pp.
998
999 Zurbuchen A, Landert L, Klaiber J, Müller A, Hein S, Dorn S. 2010. Maximum foraging ranges in solitary bees:
1000 only few individuals have the capability to cover long foraging distances. *Biological Conservation*.
1001 143:669-676.
1002
1003
1004

1005 Table 3-1. Potential Non-*Apis* Bee Species for Use in Laboratory, Semi-field or Field Tests*

Species (common name)	Sociality	Region	References on management
<i>Megachile rotundata</i> (Alfalfa leafcutting)	Solitary	Temperate North America, Asia	Mader et al. 2010
<i>Osmia lignaria</i> (Blue orchard bee)	Solitary	Temperate North America	Bosch & Kemp 2001, Mader et al. 2010
<i>Osmia cornifrons</i> (Japanese orchard bee)	Solitary	Temperate Asia, Europe	Sekita & Yamada 1993, Wilson & Abel 1996, White et al. 2009, Mader et al. 2010
<i>Osmia rufa</i> (Red orchard bee)	Solitary	Temperate Europe	Krunic et al. 1995, Bilinski & Teper 2004
<i>Osmia cornuta</i> (Hornfaced bee)	Solitary	Southern and Central Europe	Krunic et al. 1995, Maccagnani et al. 2003
<i>Amegilla chlorocyanea</i> (Blue-banded bee)	Solitary	Australia	Hogendoorn et al. 2006
<i>Xylocopa</i> spp. (Carpenter bees)	Solitary	Tropical (Brazil)	Freitas & Oliveira-Filho 2001, Freitas 2004
<i>Bombus impatiens</i> (Eastern bumble bee)	Social	Temperate (North America)	Readily available commercially. See also Evans et al. 2007, Mader et al. 2010
<i>Bombus terrestris</i> (European bumble bee)	Social	Temperate (Europe)	Readily available commercially. See also Evans et al. 2007, Mader et al. 2010
<i>Melipona beecheii</i> (stingless bee)	Social	Tropical (Central America)	Gonzalez & De Araujo Freitas 2005, Villanueva-Gutiérrez et al. 2005, Quezada Euán 2005, Quezada Euán & José Javier 2009
<i>Trigona nigra</i> (stingless bee)	Social	Tropical (Central America)	González & Medellín 1991a, 1991b
<i>Nannotrigona perilampoides</i> (stingless bee)	Social	Tropical (Central America)	González & Medellín 1991a, 1991b
<i>Trigona carbonaria</i> (stingless bee)	Social	Tropical (Australia)	Heard 1998, Heard & Dollin 1998b, Greco et al. 2011
<i>Melipona subnitida</i> (stingless bee)	Social	Tropical (Brazil)	De Oliveira Cruz et al. 2005
Meliponini tribe (stingless bees)	Social	Tropical (Brazil)	Nogueira-Neto 1997
Trigonini tribe (stingless bees)	Social	Tropical (Brazil)	Nogueira-Neto 1997

Pesticide RA for Pollinators 4-13-13

<i>Meliponula bocandei</i> (stingless bee)	Social	Tropical (Africa, Kenya)	Kwapong et al. 2010
<i>Meliponula ferruginea</i> (stingless bee)	Social	Tropical (Africa, Kenya)	Kwapong et al. 2010

1006
1007
1008
1009
1010
1011
1012
1013

* All of these species are either commercially available and/or they can be managed for crop pollination in various parts of the world. Analysis of data generated with these species would inform whether or which species may be an appropriate surrogate, and whether their use in pesticide risk assessment would be sufficient to support regulatory decisions and attendant protection goals.

CHAPTER 4 OVERVIEW OF PROTECTION GOALS FOR POLLINATORS

Moriarty, T., Alix, A., and Miles, M.

Introduction

Management of cropping systems has evolved over the past decades in a response to higher demands for food and other products (*e.g.*, fiber, fuel, etc.). Along with this has come an increased need to control pest populations and diseases. Pesticides have become an integral part of commercial production. Regulatory authorities serve a critical function in assessing and balancing the benefits of pesticides with other potential consequences of their use in order to maximize overall benefits to the societies they serve. Authorities articulate the objectives of their efforts in broad terms, such as “protecting human health and the environment” as a guide to their efforts (EFSA, 2010a). At this level, multiple considerations in addition to estimated risk are considered when guiding the actions of a regulatory authority and may include economic, legal, or political considerations. Together, all the variables are considered and balanced in a way that produces an assessment that is consistent with the protection goals of a regulatory authority.

Regulatory authorities base their interest in assessing the potential impact of pesticides to a specific organism or taxon in different factors such as:

- the market value or the role an organism (or taxon) plays in ecosystem services, both in natural and cultivated systems
- the estimation (*e.g.*, estimated exposure values) or knowledge (*e.g.*, test data or monitoring data) of actual or potential exposure of the species to pesticides;
- information on actual or potential impacts of pesticides on a taxon (*e.g.*, incident reports or survey efforts); and
- the relevance of the species or taxon to a regulatory authority’s protection goals.

Protection goals therefore reflect a certain level of information and certain values of a society. Regulatory authorities, in turn, use risk assessment tools to determine whether the use of a pesticide is consistent with its general goal, such as protecting human health and the environment. A risk assessment process must be designed to provide clear information for the risk assessor and risk manager to determine whether the proposed use of a pesticide

Pesticide RA for Pollinators 4-13-13

Formatted: Font: Italic

product would or would not be consistent with the protection goals of a regulatory authority. General protection goals however, do not necessarily inform or provide adequate guidance at the risk assessment level. Therefore, more specific protection goal(s) may need to be considered which would be more appropriate for use at the risk assessment level. Specific protection goals, however, must be is linked to the general protection goals. In this way, protection goals of a risk assessment (e.g., for a particular taxon or non-target species) are consistent with and support the general protection goal of “protecting human health and the environment.” Over time, entities such as the Organization for Economic Co-operation and Development (OECD), the US Environmental Protection Agency (EPA) and the European and Mediterranean Plant Protection Organisation (EPPO) have developed a number of documents to guide the risk assessment processes in support of decision-making with respect to registering pesticides.

The participants came to the Workshop with an understanding of the value of honey bees and of the current science on potential exposure and effects of pesticides on bees. Participants spent time discussing specific protection goals for pollinators such that a pesticide risk assessment process for pollinators would be supportive of general protection goals of regulatory authorities.

From this discussion developed surrogate protection goals that served the Workshop participants as they developed recommendations for a pesticide risk assessment process, and for the data to inform that process. However, the participants of the Workshop were aware that, since protection goals reflect a range of considerations (including legal, societal, and resource considerations) that are specific to a government or authority, it was not within the scope of this effort to define the protection goal of any one country or protection authority.

Elements and Proposed Protection Goals

During the Workshop, participants discussed the longstanding global importance of *Apis* and non-*Apis* bees in terms of both commercial and ecological significance. Participants of the Workshop agreed that a critical ecological service of pollinators (bees in particular) that needs to be protected is the maintainance of the pollinating function of these organisms. The goal would be to ensure adequate pollination (sufficient frequency of floral visits) to support healthy crop survival and yield. While such a protection goal is relevant for commercial agricultural production, it may not be relevant at a larger scale, *i.e.* the landscape, where the

1084 role of non-*Apis* species is more relevant as these species pollinate adjacent cropland or the
 1085 non-cropped landscape. For this to be taken into account, non-*Apis* (*i.e.*, non-managed)
 1086 pollinating insect species would need to be considered with their interactions in the larger
 1087 landscape. While pollination remains the critical function of these species which ensures a
 1088 healthy and ecologically diverse landscape, consideration of non-*Apis* species and their
 1089 contribution to landscape ecology reflects the role that ecological diversity plays in
 1090 supporting a health environment. Protection of the pollinator community at the landscape
 1091 level ensures pollination services and also contributes to the diversity of the species
 1092 associated with pollination services within that landscape. Finally, participants identified
 1093 honey and other hive products as potentially both a specific goal to be protected as well as a
 1094 measure of honey bee health. Model (surrogate) protection goals upon which to build a risk
 1095 assessment framework were then defined as:

Formatted: Font: Italic

- 1096 (i) protection of pollination services provided by both *Apis* and non-*Apis* species;
- 1097 (ii) protection of pollinator biodiversity, (*i.e.*, protection of adequate number and
 1098 diversity of bee species that contribute to the health of the environment); and,
- 1099 (iii) protection of honey production and other hive products.

1100
 1101

1102 **Linking Protection Goals with Assessment Endpoints**

1103

1104 With possible protection goal(s) defined, they then had to be linked to risk assessment
 1105 endpoints, and further linked to specific endpoints measured in either exposure or effects
 1106 studies (*i.e.*, measurement endpoints). Assessment endpoints are attributes of an entity (*e.g.*,
 1107 an organism or environmental component) that are essential for its continued survival. In
 1108 ecological risk assessments for wildlife, assessment endpoints have traditionally been defined
 1109 as the growth, reproduction and survival of an organism. These same assessments can be
 1110 applied to the honey bee, but it must be recognized that the honey bee functions as a
 1111 superorganism and therefore the attributes of growth, reproduction and survival, apply to the
 1112 colony, not the individual bee.

Formatted: Font: Italic

1113
 1114 A risk assessment (*e.g.*, for a particular taxon) is based upon data from a one or several
 1115 studies that provide sufficient information for the risk assessor to determine whether the
 1116 intended use of a pesticide will have a significant adverse effect on one or more of the
 1117 assessment endpoint(s). Data provided by specific studies should inform one or more of the

Formatted: Font: Italic

assessment endpoints in either a direct fashion (*e.g.*, treatment related mortality) or an indirect fashion (*e.g.*, reduced foraging activity). Both exposure studies and effects studies produce measurement endpoints (*e.g.*, pesticide residue levels in pollen, body length, adult bee longevity, or mortality of different castes or stages) informing the risk assessor whether the intended use of a pesticide results in a significant exposure and/or reduction in an organisms ability to either grow, reproduce, and/or survive. When measurement endpoints are appropriately linked to assessment endpoints and specific protection goals, they then support generic protection goals. Below, Figure 4-1 shows the relationship between measurement endpoints, assessment endpoints, specific protection goals, and generic protection goals (Table 10-1 also gives more specific examples of protection goals, assessment endpoints and measurement endpoints).

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

General Protection Goals of a Regulatory Authority

General Protection goals are overarching supported the when specific protection goals



Specific Protection Goals for Risk Assessment

Specific protection goals are consistent with, and support generic protection goals; knowledge of whether a specific protection goal(s) is met is based upon whether the assessment endpoints are met.



Assessment Endpoints

Assessment endpoints are attributes of an entity that are sufficient to support a specific protection goal. Measurement endpoints individually or collectively contribute to one or more assessment endpoint.



Measurement Endpoints

Measurement endpoints are collected through studies and are indicative of, or provide information on one or more assessment endpoint.

Figure 4-1. Relationship between measurement endpoints to generic protection goals, used in assessing ecological risks

Protection Goals and Monitoring

The risk assessment process proposed by the participants of the Workshop is designed to support the protection goals articulated at the Workshop. The process also provides an avenue for additional feedback information to continue to inform the assessment of risk. Confirmatory information, such as incident or monitoring data, provides direct feedback on whether the regulatory decisions are effective, and whether specific and generic and protection goals are being achieved. However, field monitoring studies can be complex since they often reflect natural events/scenarios that impact bees, such as disease, predation and competition. Thus, it is important that when defining protection goals, consideration is given to the risk assessment parameters and potential monitoring parameters in a way that makes the relationship between them clear. Figure 4-2 illustrates the relationship between risk assessment, risk mitigation techniques (*i.e.*, risk management) and post registration monitoring. The process described in Figure 4-2 would provide information on exposure, effects, or the effectiveness of mitigation measures




Figure 4-2. Post registration monitoring studies in a risk assessment framework

Conclusion

Well defined protection goals guide a risk assessment by providing criteria for decisions within the paradigm of risk assessment (study design and interpretation), risk mitigation, and/or post-registration monitoring actions to determine whether protection goals are met. Protection goals must be achievable and sustainable through appropriate scientific analysis and decisions (*i.e.*, studies, management, and/or monitoring). During the Workshop, participants discussed the longstanding global importance of *Apis* and non-*Apis* bees in terms of both commercial and ecological realms. Participants developed model (or surrogate) protection goals suitable as the basis for a risk assessment framework. It was noted that both risk assessment and risk management are complementary options to meet protection goals. Therefore, suitable protection goals were defined as:

- protection of pollination services provided by *Apis* and non-*Apis* species,
- protection of honey production and other hive products
- protection of pollinator biodiversity, that is, protection of adequate number and diversity of bee species that contribute to the health of the environment (primarily non-*Apis* bees); and,

References

- EC, 2010. Directive 91/414/EEC, Council Directive of 15 July 1991 concerning the placing of plant protection products on the market (91/414/EEC), Official Journal L 0414: 01.08.2006.
- EC, 2009. Regulation (EC) No 1107/2009 of the European parliament and of the council concerning the placing of plant protection products on the market and repealing Council Directives 79/117/EEC and 91/414/EEC. Official Journal L 309.1: 24.11.2009.
- EFSA Panel on Plant Protection Products and their Residues (PPR), 2010a. Scientific Opinion on the development of specific protection goal options for environmental risk assessment of pesticides, in particular in relation to the revision of the Guidance Documents on Aquatic and Terrestrial Ecotoxicology (SANCO/3268/2001 and SANCO/10329/2002). EFSA Journal 2010;8(10):1821. [55 pp.] doi:10.2903/j.efsa.2010.1821. Available online: [[HYPERLINK](http://www.efsa.europa.eu/efsajournal.htm) "http://www.efsa.europa.eu/efsajournal.htm"]
- EPPO, 2010a. Environmental risk assessment scheme for plant protection products, Chapter 10. Risk assessment to honey bees, PP 3/10 (3), OEPP/EPPO, Bulletin OEPP/EPPO Bulletin 40, 1–9.

1230
1231
1232 EPPO, 2003. EPPO Environmental risk assessment scheme for plant protection products, PP 3/10(2), Chapter
1233 10: Honeybees. Bull OEPP/EPPO Bull 33: 99-101.
1234
1235 FIFRA, 2008. Federal Insecticide, Fungicide, and Rodenticide Act.
1236
1237 Kluser S, Peduzzi P, (2007), "Global Pollinator Decline: A Literature Review", UNEP/GRIDEurope. UNEP
1238 2007.
1239
1240 Neumann P. and Carreck N.L., 2010. Honey bee colony losses. Journal of Apicultural Research 49(1): 1-6
1241 (2010).
1242
1243 OECD, 2007. Guidance Document 75: Guidance document on the honey bee (*Apis mellifera* L.) brood test
1244 under semi-field conditions. Series on testing and assessment, Number 75. ENV/JM/MONO(2007)22.
1245
1246 SANCO/10329/2002 rev 2 final, Working Document Guidance Document on Terrestrial Ecotoxicology Under
1247 Council Directive 91/414/EEC, (2002).
1248
1249

CHAPTER 5 OVERVIEW OF THE PESTICIDE RISK ASSESSMENT AND THE REGULATORY PROCESS

Lee-Steere, C., and Steeger, T.

Introduction

As discussed earlier, regulatory authorities have the responsibility to evaluate pesticides and the potential risks associated with their use. They have developed tools and methods to do this in a consistent manner with respect to different taxon. However, with the introduction of new plant protection products, changes in agricultural practices, and advances in the understanding of honey bee health and ecology, the ability to accurately characterize potential risks to insect pollinators with the existing tool set has been seen as a challenge. While many countries share the same broad risk-based environmental assessment approach, differences between approaches exist that account for national conditions, such as policies, legal requirements, or preferences.

The Workshop considered a generic, tiered risk assessment methodology, and worked to develop a process that included three phases: (1) problem formulation, (2) exposure and (3) effects assessment, risk characterization. In Phase 1; (*i.e., problem formulation*), measurement endpoints, derived from studies, are selected with an understanding of how they relate to assessment endpoints (and ultimately specific protection goals and generic protection goals); a conceptual model is prepared that describes a risk hypothesis; and an analysis plan to test that hypothesis is described. In Phase 2; (*i.e., analysis*), measures of exposure and effects are evaluated. In Phase 3; (*i.e., risk characterization*), measures of exposure and measures of effect are integrated to develop risk estimates, and uncertainties are discussed.

Analysis is carried out in a tiered manner, where a tier 1 analysis is intended to be a conservative screen that efficiently separates compounds that are not anticipated to present a potential risk from those compounds that may. Higher tiers are intended to refine the estimates or measures of potential exposure, effects, and the resulting characterization of risk. Risk assessors and risk managers proceed through the risk assessment process (*i.e., ascending through higher tiers of analysis*) to determine whether the intended use of a compound is

Pesticide RA for Pollinators 4-13-13

Formatted: Font: Italic, Underline

Formatted: Font: Not Italic

consistent with defined protection goals. If the estimate of risk indicates that proposed use is not consistent with the protection goals, then risk mitigation techniques may be implemented proactively to resolve concerns. During the Workshop, risk mitigation was briefly discussed as it is a component of the overall regulatory management of plant protection products (see Chapter 13 on Risk Mitigation).

Current Approach for Assessing Effects of Pesticide Products to Pollinators

In the United States, the first tier of toxicity testing with honey bees consists of an acute contact toxicity test (USEPA 2012a)³ with adult honey bees that provides a median Lethal Dose (LD₅₀), *i.e.*, the dose that causes death to 50% of the exposed organisms from a single dose of the test compound, along with any sublethal effects that may have occurred as a result of chemical exposure. The acute LD₅₀ is assessed after 24 and 48 hours, but depending upon the outcome of the test, its duration can be extended up to a maximum of 96 hrs, if necessary. Based upon the outcome of the acute LD₅₀ toxicity test, pesticides are classified as practically non-toxic, moderately toxic, or highly toxic to bees on an acute exposure basis. If the LD₅₀ is less than 11 µg/bee, additional testing may be required in the form of a foliar residue study (USEPA 2012b)⁴ to determine the duration over which field-weathered foliar residues remain toxic to honey bees. On a case-by-case basis, additional higher-tiered studies such as field pollinator studies with honey bees (USEPA 2012c)⁵ (*i.e.*, hive studies) may be necessary if the data from toxicity studies indicate potential chronic effects or adverse effects on colonies.

In the European Union (EU), risk to honey bees from exposure to pesticides is based on the European and Mediterranean Plant Protection Organization (EPPO) process and includes a three-tiered progression of testing OECD 2007, EPPO 2001 and 2010a, 2010b, 2010c, 2010d, 2010e, 2010f, 2010g, 2010h, 2010i, 2010j, 2010k, 2010l, 2010m, 2010n, 2010o, 2010p, 2010q, 2010r, 2010s, 2010t, 2010u, 2010v, 2010w, 2010x, 2010y, 2010z, 2011a, 2011b, 2011c, 2011d, 2011e, 2011f, 2011g, 2011h, 2011i, 2011j, 2011k, 2011l, 2011m, 2011n, 2011o, 2011p, 2011q, 2011r, 2011s, 2011t, 2011u, 2011v, 2011w, 2011x, 2011y, 2011z, 2012a, 2012b, 2012c, 2012d, 2012e, 2012f, 2012g, 2012h, 2012i, 2012j, 2012k, 2012l, 2012m, 2012n, 2012o, 2012p, 2012q, 2012r, 2012s, 2012t, 2012u, 2012v, 2012w, 2012x, 2012y, 2012z, 2013a, 2013b, 2013c, 2013d, 2013e, 2013f, 2013g, 2013h, 2013i, 2013j, 2013k, 2013l, 2013m, 2013n, 2013o, 2013p, 2013q, 2013r, 2013s, 2013t, 2013u, 2013v, 2013w, 2013x, 2013y, 2013z, 2014a, 2014b, 2014c, 2014d, 2014e, 2014f, 2014g, 2014h, 2014i, 2014j, 2014k, 2014l, 2014m, 2014n, 2014o, 2014p, 2014q, 2014r, 2014s, 2014t, 2014u, 2014v, 2014w, 2014x, 2014y, 2014z, 2015a, 2015b, 2015c, 2015d, 2015e, 2015f, 2015g, 2015h, 2015i, 2015j, 2015k, 2015l, 2015m, 2015n, 2015o, 2015p, 2015q, 2015r, 2015s, 2015t, 2015u, 2015v, 2015w, 2015x, 2015y, 2015z, 2016a, 2016b, 2016c, 2016d, 2016e, 2016f, 2016g, 2016h, 2016i, 2016j, 2016k, 2016l, 2016m, 2016n, 2016o, 2016p, 2016q, 2016r, 2016s, 2016t, 2016u, 2016v, 2016w, 2016x, 2016y, 2016z, 2017a, 2017b, 2017c, 2017d, 2017e, 2017f, 2017g, 2017h, 2017i, 2017j, 2017k, 2017l, 2017m, 2017n, 2017o, 2017p, 2017q, 2017r, 2017s, 2017t, 2017u, 2017v, 2017w, 2017x, 2017y, 2017z, 2018a, 2018b, 2018c, 2018d, 2018e, 2018f, 2018g, 2018h, 2018i, 2018j, 2018k, 2018l, 2018m, 2018n, 2018o, 2018p, 2018q, 2018r, 2018s, 2018t, 2018u, 2018v, 2018w, 2018x, 2018y, 2018z, 2019a, 2019b, 2019c, 2019d, 2019e, 2019f, 2019g, 2019h, 2019i, 2019j, 2019k, 2019l, 2019m, 2019n, 2019o, 2019p, 2019q, 2019r, 2019s, 2019t, 2019u, 2019v, 2019w, 2019x, 2019y, 2019z, 2020a, 2020b, 2020c, 2020d, 2020e, 2020f, 2020g, 2020h, 2020i, 2020j, 2020k, 2020l, 2020m, 2020n, 2020o, 2020p, 2020q, 2020r, 2020s, 2020t, 2020u, 2020v, 2020w, 2020x, 2020y, 2020z, 2021a, 2021b, 2021c, 2021d, 2021e, 2021f, 2021g, 2021h, 2021i, 2021j, 2021k, 2021l, 2021m, 2021n, 2021o, 2021p, 2021q, 2021r, 2021s, 2021t, 2021u, 2021v, 2021w, 2021x, 2021y, 2021z, 2022a, 2022b, 2022c, 2022d, 2022e, 2022f, 2022g, 2022h, 2022i, 2022j, 2022k, 2022l, 2022m, 2022n, 2022o, 2022p, 2022q, 2022r, 2022s, 2022t, 2022u, 2022v, 2022w, 2022x, 2022y, 2022z, 2023a, 2023b, 2023c, 2023d, 2023e, 2023f, 2023g, 2023h, 2023i, 2023j, 2023k, 2023l, 2023m, 2023n, 2023o, 2023p, 2023q, 2023r, 2023s, 2023t, 2023u, 2023v, 2023w, 2023x, 2023y, 2023z, 2024a, 2024b, 2024c, 2024d, 2024e, 2024f, 2024g, 2024h, 2024i, 2024j, 2024k, 2024l, 2024m, 2024n, 2024o, 2024p, 2024q, 2024r, 2024s, 2024t, 2024u, 2024v, 2024w, 2024x, 2024y, 2024z, 2025a, 2025b, 2025c, 2025d, 2025e, 2025f, 2025g, 2025h, 2025i, 2025j, 2025k, 2025l, 2025m, 2025n, 2025o, 2025p, 2025q, 2025r, 2025s, 2025t, 2025u, 2025v, 2025w, 2025x, 2025y, 2025z, 2026a, 2026b, 2026c, 2026d, 2026e, 2026f, 2026g, 2026h, 2026i, 2026j, 2026k, 2026l, 2026m, 2026n, 2026o, 2026p, 2026q, 2026r, 2026s, 2026t, 2026u, 2026v, 2026w, 2026x, 2026y, 2026z, 2027a, 2027b, 2027c, 2027d, 2027e, 2027f, 2027g, 2027h, 2027i, 2027j, 2027k, 2027l, 2027m, 2027n, 2027o, 2027p, 2027q, 2027r, 2027s, 2027t, 2027u, 2027v, 2027w, 2027x, 2027y, 2027z, 2028a, 2028b, 2028c, 2028d, 2028e, 2028f, 2028g, 2028h, 2028i, 2028j, 2028k, 2028l, 2028m, 2028n, 2028o, 2028p, 2028q, 2028r, 2028s, 2028t, 2028u, 2028v, 2028w, 2028x, 2028y, 2028z, 2029a, 2029b, 2029c, 2029d, 2029e, 2029f, 2029g, 2029h, 2029i, 2029j, 2029k, 2029l, 2029m, 2029n, 2029o, 2029p, 2029q, 2029r, 2029s, 2029t, 2029u, 2029v, 2029w, 2029x, 2029y, 2029z, 2030a, 2030b, 2030c, 2030d, 2030e, 2030f, 2030g, 2030h, 2030i, 2030j, 2030k, 2030l, 2030m, 2030n, 2030o, 2030p, 2030q, 2030r, 2030s, 2030t, 2030u, 2030v, 2030w, 2030x, 2030y, 2030z, 2031a, 2031b, 2031c, 2031d, 2031e, 2031f, 2031g, 2031h, 2031i, 2031j, 2031k, 2031l, 2031m, 2031n, 2031o, 2031p, 2031q, 2031r, 2031s, 2031t, 2031u, 2031v, 2031w, 2031x, 2031y, 2031z, 2032a, 2032b, 2032c, 2032d, 2032e, 2032f, 2032g, 2032h, 2032i, 2032j, 2032k, 2032l, 2032m, 2032n, 2032o, 2032p, 2032q, 2032r, 2032s, 2032t, 2032u, 2032v, 2032w, 2032x, 2032y, 2032z, 2033a, 2033b, 2033c, 2033d, 2033e, 2033f, 2033g, 2033h, 2033i, 2033j, 2033k, 2033l, 2033m, 2033n, 2033o, 2033p, 2033q, 2033r, 2033s, 2033t, 2033u, 2033v, 2033w, 2033x, 2033y, 2033z, 2034a, 2034b, 2034c, 2034d, 2034e, 2034f, 2034g, 2034h, 2034i, 2034j, 2034k, 2034l, 2034m, 2034n, 2034o, 2034p, 2034q, 2034r, 2034s, 2034t, 2034u, 2034v, 2034w, 2034x, 2034y, 2034z, 2035a, 2035b, 2035c, 2035d, 2035e, 2035f, 2035g, 2035h, 2035i, 2035j, 2035k, 2035l, 2035m, 2035n, 2035o, 2035p, 2035q, 2035r, 2035s, 2035t, 2035u, 2035v, 2035w, 2035x, 2035y, 2035z, 2036a, 2036b, 2036c, 2036d, 2036e, 2036f, 2036g, 2036h, 2036i, 2036j, 2036k, 2036l, 2036m, 2036n, 2036o, 2036p, 2036q, 2036r, 2036s, 2036t, 2036u, 2036v, 2036w, 2036x, 2036y, 2036z, 2037a, 2037b, 2037c, 2037d, 2037e, 2037f, 2037g, 2037h, 2037i, 2037j, 2037k, 2037l, 2037m, 2037n, 2037o, 2037p, 2037q, 2037r, 2037s, 2037t, 2037u, 2037v, 2037w, 2037x, 2037y, 2037z, 2038a, 2038b, 2038c, 2038d, 2038e, 2038f, 2038g, 2038h, 2038i, 2038j, 2038k, 2038l, 2038m, 2038n, 2038o, 2038p, 2038q, 2038r, 2038s, 2038t, 2038u, 2038v, 2038w, 2038x, 2038y, 2038z, 2039a, 2039b, 2039c, 2039d, 2039e, 2039f, 2039g, 2039h, 2039i, 2039j, 2039k, 2039l, 2039m, 2039n, 2039o, 2039p, 2039q, 2039r, 2039s, 2039t, 2039u, 2039v, 2039w, 2039x, 2039y, 2039z, 2040a, 2040b, 2040c, 2040d, 2040e, 2040f, 2040g, 2040h, 2040i, 2040j, 2040k, 2040l, 2040m, 2040n, 2040o, 2040p, 2040q, 2040r, 2040s, 2040t, 2040u, 2040v, 2040w, 2040x, 2040y, 2040z, 2041a, 2041b, 2041c, 2041d, 2041e, 2041f, 2041g, 2041h, 2041i, 2041j, 2041k, 2041l, 2041m, 2041n, 2041o, 2041p, 2041q, 2041r, 2041s, 2041t, 2041u, 2041v, 2041w, 2041x, 2041y, 2041z, 2042a, 2042b, 2042c, 2042d, 2042e, 2042f, 2042g, 2042h, 2042i, 2042j, 2042k, 2042l, 2042m, 2042n, 2042o, 2042p, 2042q, 2042r, 2042s, 2042t, 2042u, 2042v, 2042w, 2042x, 2042y, 2042z, 2043a, 2043b, 2043c, 2043d, 2043e, 2043f, 2043g, 2043h, 2043i, 2043j, 2043k, 2043l, 2043m, 2043n, 2043o, 2043p, 2043q, 2043r, 2043s, 2043t, 2043u, 2043v, 2043w, 2043x, 2043y, 2043z, 2044a, 2044b, 2044c, 2044d, 2044e, 2044f, 2044g, 2044h, 2044i, 2044j, 2044k, 2044l, 2044m, 2044n, 2044o, 2044p, 2044q, 2044r, 2044s, 2044t, 2044u, 2044v, 2044w, 2044x, 2044y, 2044z, 2045a, 2045b, 2045c, 2045d, 2045e, 2045f, 2045g, 2045h, 2045i, 2045j, 2045k, 2045l, 2045m, 2045n, 2045o, 2045p, 2045q, 2045r, 2045s, 2045t, 2045u, 2045v, 2045w, 2045x, 2045y, 2045z, 2046a, 2046b, 2046c, 2046d, 2046e, 2046f, 2046g, 2046h, 2046i, 2046j, 2046k, 2046l, 2046m, 2046n, 2046o, 2046p, 2046q, 2046r, 2046s, 2046t, 2046u, 2046v, 2046w, 2046x, 2046y, 2046z, 2047a, 2047b, 2047c, 2047d, 2047e, 2047f, 2047g, 2047h, 2047i, 2047j, 2047k, 2047l, 2047m, 2047n, 2047o, 2047p, 2047q, 2047r, 2047s, 2047t, 2047u, 2047v, 2047w, 2047x, 2047y, 2047z, 2048a, 2048b, 2048c, 2048d, 2048e, 2048f, 2048g, 2048h, 2048i, 2048j, 2048k, 2048l, 2048m, 2048n, 2048o, 2048p, 2048q, 2048r, 2048s, 2048t, 2048u, 2048v, 2048w, 2048x, 2048y, 2048z, 2049a, 2049b, 2049c, 2049d, 2049e, 2049f, 2049g, 2049h, 2049i, 2049j, 2049k, 2049l, 2049m, 2049n, 2049o, 2049p, 2049q, 2049r, 2049s, 2049t, 2049u, 2049v, 2049w, 2049x, 2049y, 2049z, 2050a, 2050b, 2050c, 2050d, 2050e, 2050f, 2050g, 2050h, 2050i, 2050j, 2050k, 2050l, 2050m, 2050n, 2050o, 2050p, 2050q, 2050r, 2050s, 2050t, 2050u, 2050v, 2050w, 2050x, 2050y, 2050z, 2051a, 2051b, 2051c, 2051d, 2051e, 2051f, 2051g, 2051h, 2051i, 2051j, 2051k, 2051l, 2051m, 2051n, 2051o, 2051p, 2051q, 2051r, 2051s, 2051t, 2051u, 2051v, 2051w, 2051x, 2051y, 2051z, 2052a, 2052b, 2052c, 2052d, 2052e, 2052f, 2052g, 2052h, 2052i, 2052j, 2052k, 2052l, 2052m, 2052n, 2052o, 2052p, 2052q, 2052r, 2052s, 2052t, 2052u, 2052v, 2052w, 2052x, 2052y, 2052z, 2053a, 2053b, 2053c, 2053d, 2053e, 2053f, 2053g, 2053h, 2053i, 2053j, 2053k, 2053l, 2053m, 2053n, 2053o, 2053p, 2053q, 2053r, 2053s, 2053t, 2053u, 2053v, 2053w, 2053x, 2053y, 2053z, 2054a, 2054b, 2054c, 2054d, 2054e, 2054f, 2054g, 2054h, 2054i, 2054j, 2054k, 2054l, 2054m, 2054n, 2054o, 2054p, 2054q, 2054r, 2054s, 2054t, 2054u, 2054v, 2054w, 2054x, 2054y, 2054z, 2055a, 2055b, 2055c, 2055d, 2055e, 2055f, 2055g, 2055h, 2055i, 2055j, 2055k, 2055l, 2055m, 2055n, 2055o, 2055p, 2055q, 2055r, 2055s, 2055t, 2055u, 2055v, 2055w, 2055x, 2055y, 2055z, 2056a, 2056b, 2056c, 2056d, 2056e, 2056f, 2056g, 2056h, 2056i, 2056j, 2056k, 2056l, 2056m, 2056n, 2056o, 2056p, 2056q, 2056r, 2056s, 2056t, 2056u, 2056v, 2056w, 2056x, 2056y, 2056z, 2057a, 2057b, 2057c, 2057d, 2057e, 2057f, 2057g, 2057h, 2057i, 2057j, 2057k, 2057l, 2057m, 2057n, 2057o, 2057p, 2057q, 2057r, 2057s, 2057t, 2057u, 2057v, 2057w, 2057x, 2057y, 2057z, 2058a, 2058b, 2058c, 2058d, 2058e, 2058f, 2058g, 2058h, 2058i, 2058j, 2058k, 2058l, 2058m, 2058n, 2058o, 2058p, 2058q, 2058r, 2058s, 2058t, 2058u, 2058v, 2058w, 2058x, 2058y, 2058z, 2059a, 2059b, 2059c, 2059d, 2059e, 2059f, 2059g, 2059h, 2059i, 2059j, 2059k, 2059l, 2059m, 2059n, 2059o, 2059p, 2059q, 2059r, 2059s, 2059t, 2059u, 2059v, 2059w, 2059x, 2059y, 2059z, 2060a, 2060b, 2060c, 2060d, 2060e, 2060f, 2060g, 2060h, 2060i, 2060j, 2060k, 2060l, 2060m, 2060n, 2060o, 2060p, 2060q, 2060r, 2060s, 2060t, 2060u, 2060v, 2060w, 2060x, 2060y, 2060z, 2061a, 2061b, 2061c, 2061d, 2061e, 2061f, 2061g, 2061h, 2061i, 2061j, 2061k, 2061l, 2061m, 2061n, 2061o, 2061p, 2061q, 2061r, 2061s, 2061t, 2061u, 2061v, 2061w, 2061x, 2061y, 2061z, 2062a, 2062b, 2062c, 2062d, 2062e, 2062f, 2062g, 2062h, 2062i, 2062j, 2062k, 2062l, 2062m, 2062n, 2062o, 2062p, 2062q, 2062r, 2062s, 2062t, 2062u, 2062v, 2062w, 2062x, 2062y, 2062z, 2063a, 2063b, 2063c, 2063d, 2063e, 2063f, 2063g, 2063h, 2063i, 2063j, 2063k, 2063l, 2063m, 2063n, 2063o, 2063p, 2063q, 2063r, 2063s, 2063t, 2063u, 2063v, 2063w, 2063x, 2063y, 2063z, 2064a, 2064b, 2064c, 2064d, 2064e, 2064f, 2064g, 2064h, 2064i, 2064j, 2064k, 2064l, 2064m, 2064n, 2064o, 2064p, 2064q, 2064r, 2064s, 2064t, 2064u, 2064v, 2064w, 2064x, 2064y, 2064z, 2065a, 2065b, 2065c, 2065d, 2065e, 2065f, 2065g, 2065h, 2065i, 2065j, 2065k, 2065l, 2065m, 2065n, 2065o, 2065p, 2065q, 2065r, 2065s, 2065t, 2065u, 2065v, 2065w, 2065x, 2065y, 2065z, 2066a, 2066b, 2066c, 2066d, 2066e, 2066f, 2066g, 2066h, 2066i, 2066j, 2066k, 2066l, 2066m, 2066n, 2066o, 2066p, 2066q, 2066r, 2066s, 2066t, 2066u, 2066v, 2066w, 2066x, 2066y, 2066z, 2067a, 2067b, 2067c, 2067d, 2067e, 2067f, 2067g, 2067h, 2067i, 2067j, 2067k, 2067l, 2067m, 2067n, 2067o, 2067p, 2067q, 2067r, 2067s, 2067t, 2067u, 2067v, 2067w, 2067x, 2067y, 2067z, 2068a, 2068b, 2068c, 2068d, 2068e, 2068f, 2068g, 2068h, 2068i, 2068j, 2068k, 2068l, 2068m, 2068n, 2068o, 2068p, 2068q, 2068r, 2068s, 2068t, 2068u, 2068v, 2068w, 2068x, 2068y, 2068z, 2069a, 2069b, 2069c, 2069d, 2069e, 2069f, 2069g, 2069h, 2069i, 2069j, 2069k, 2069l, 2069m, 2069n, 2069o, 2069p, 2069q, 2069r, 2069s, 2069t, 2069u, 2069v, 2069w, 2069x, 2069y, 2069z, 2070a, 2070b, 2070c, 2070d, 2070e, 2070f, 2070g, 2070h, 2070i, 2070j, 2070k, 2070l, 2070m, 2070n, 2070o, 2070p, 2070q, 2070r, 2070s, 2070t, 2070u, 2070v, 2070w, 2070x, 2070y, 2070z, 2071a, 2071b, 2071c, 2071d, 2071e, 2071f, 2071g, 2071h, 2071i, 2071j, 2071k, 2071l, 2071m, 2071n, 2071o, 2071p, 2071q, 2071r, 2071s, 2071t, 2071u, 2071v, 2071w, 2071x, 2071y, 2071z, 2072a, 2072b, 2072c, 2072d, 2072e, 2072f, 2072g, 2072h, 2072i, 2072j, 2072k, 2072l, 2072m, 2072n, 2072o, 2072p, 2072q, 2072r, 2072s, 2072t, 2072u, 2072v, 2072w, 2072x, 2072y, 2072z, 2073a, 2073b, 2073c, 2073d, 2073e, 2073f, 2073g, 2073h, 2073i, 2073j, 2073k, 2073l, 2073m, 2073n, 2073o, 2073p, 2073q, 2073r, 2073s, 2073t, 2073u, 2073v, 2073w, 2073x, 2073y, 2073z, 2074a, 2074b, 2074c, 2074d, 2074e, 2074f, 2074g, 2074h, 2074i, 2074j, 2074k,

approach, where laboratory studies are considered tier 1 tests, and semi-field and field tests are considered higher tiers. In contrast to the U.S., the EU and Canada require the acute oral toxicity (LD₅₀) on adult workers (OECD 1998a) in addition to the acute contact toxicity (OECD 1998b). In the EU, it is also standard practice to conduct both acute oral and acute contact LD₅₀ studies on formulated end-use products, in cases where either exposure to the end use product itself is possible, or in the case where products have more than one active component, as well as the technical grade (relatively pure) active substance.

In addition to guideline toxicity test requirements, regulatory authorities around the world also make use of published open literature and dedicated studies for non-target arthropods to evaluate the potential effects of pesticides on terrestrial invertebrates, or as a line of evidence to require higher tiered testing. Along with guideline and open literature studies, adverse effect (*e.g.* bee kill incident) reports, and monitoring studies are considered in order to gauge the effects of pesticides on non-target organisms.

Risk Assessment for Systemic Compounds

Many who are familiar with pesticide risk assessment recognize that the methodology and assessment schemes employed for foliar application products (where exposure may be primarily through surface contact) are not well adapted to assess potential risk from compounds with systemic properties. With better understanding of the ability of these chemicals to be present in pollen and nectar during flowering, there has followed a better understanding of how systemic compounds present potential for both oral and contact exposure and, therefore, need to be considered.

The EPPO has recently put forward a risk assessment scheme (Alix *et al.* 2009) for systemic compounds that includes the same tiered testing system, but replaces the hazard quotient (HQ) calculation with a Toxicity Exposure Ratio (TER), where $TER = PNEC/PEC$. The PNEC is the Predicted No Effect Concentration, while the PEC is the Predicted Exposure Concentration. The PEC is determined from estimated or measured residue concentrations in the whole plant, flowers, pollen and/or nectar. The dose that individual bees might ingest is then calculated for different categories of honey bees (*e.g.*, larvae, queen, foragers) depending on the amount of contaminated pollen and nectar they may consume. PNECs are derived from acute, sublethal, and chronic toxicity data and may also include a factor to account for uncertainty. These factors range from 1 to 10 depending on whether the toxicity

Pesticide RA for Pollinators 4-13-13

endpoint is assessed in a laboratory (Tier 1) or in a semi-field or field test, *i.e.*, uncertainty decreases as toxicity data become more representative of how the pesticide will be used.

Trigger Criterion and Levels of Concern

A “trigger criterion” is a value, a threshold, used to define the limit of risk that is consistent with protection goals. A trigger criterion or level of concern (LOC) is compared to a quantitative risk estimate (*e.g.*, hazard quotient (HQ) employed in Europe, or a risk quotient (RQ) employed in North America (USEPA 1998)) to determine if the estimated risk is acceptable or not. If the comparison between a level of concern and an estimated risk indicates that the use of a compound is inconsistent with defined protection goals, then it may be appropriate to either further refine the risk with additional data, or seek action to mitigate potential risk. (In Europe for example, when assessing a spray formula, the trigger criterion at the screening level is where $HQ \geq 50$; such that when $HQ \geq 50$, either higher tier data, or risk mitigation may be sought, (EPPO 2010*b*; Alix *et al.* 2009). In the US, estimates of risk (*i.e.*, the risk quotient or RQ) is compared against the level of concern (LOC) to determine whether further refinement is needed. Participants of the Workshop noted that while levels of concern promote efficiency in decision-making, risk assessment is an iterative process between risk assessors and risk managers, and is composed of multiple lines of evidence in order to determine whether the use of a compound on a specific crop is consistent with a protection goal(s). Ultimately, trigger criterion and levels of concern are policy tools and, as such, they are outside the purview of the SETAC Pellston Workshop and remain the right and responsibility of respective regulatory authorities to define.

Formatted: Font: Italic

References

- Alix, A., M. P. Chauzat, S. Duchard, G. Lewis, C. Maus, M. J. Miles, E. Pilling, H. M. Thompson, K. Wallner. 2009. Environmental Risk Assessment Scheme for Plant Protection Products – Chapter 10: Honey bees – Proposed Scheme. Pages 27 - 33 in P. A. Oomen and H. M. Thompson (editors) International Commission for Plant-Bee Relationships Bee Protection Group 10th International Symposium Hazards of Pesticides to Bees, Buscharest (Romania). October 8 – 10, 2008. Julius –Kühn Archiv
- EPPO, 2003. EPPO Environmental risk assessment scheme for plant protection products, PP 3/10(2), Chapter 10: Honey bees. Bull OEPP/EPPO Bull 33: 99-101.
- EPPO. 2010a. Efficacy Evaluation of Plant Protection Products: Side-effects on Honey bees. PP 1/170 (4). OEPP/EPPO Bulletin 40: 313–319

1390 EPPO. 2010b. Environmental risk assessment scheme for plant protection products: Chapter 10, Honey bees.
1391 European and Mediterranean Plant Protection Organization (EPPO). Bulletin OEPP/EPPO Bulletin 40, 323–331.
1392
1393 OECD. 1998a. OECD Guidelines for the Testing of Chemicals. Test Number 213: Honey bees, Acute Oral
1394 Toxicity Test. [HYPERLINK "http://www.oecd-ilibrary.org/environment/test-no-213-
1395 honeybees-acute-oral-toxicity-test_9789264070165-en;jsessionid=5p2ngklfmv8p4.epsilon"]
1396
1397 OECD. 1998b. OECD Guidelines for the Testing of Chemicals. Test Number 214, Acute Contact Toxicity Test.
1398 [HYPERLINK "http://www.oecd-ilibrary.org/environment/test-no-214-honeybees-acute-
1399 contact-toxicity-test_9789264070189-en;jsessionid=43gvto47wnue9.delta"]
1400
1401 OECD. 2007. Guidance document on the honey bee (*Apis mellifera*) brood test under semi-field conditions.
1402 OECD Environment, Health and Safety Publications. Series on Testing and Assessment No. 75.
1403 ENV/JM/MONO (2007) 22.
1404
1405 USEPA. 1998. Guidelines for Ecological Risk Assessment. Published on May 14, 1998, Federal Register
1406 63(93): 26846 – 26924. [HYPERLINK
1407 "http://www.epa.gov/raf/publications/pdfs/ECOTXTBX.PDF"]
1408
1409 USEPA. 2012a. Ecological Effects Test Guidelines. OCSPP 850.3020 Honey Bee Acute Contact Toxicity. EPA
1410 712-C-019. January 2012. [HYPERLINK "http://www.regulations.gov/" \l
1411 "!documentDetail;D=EPA-HQ-OPPT-2009-0154-0016"]
1412
1413 USEPA. 2012b. Ecological Effects Test Guidelines OCSPP 850.3030 Honey Bee Toxicity of Residues on
1414 Foliage. EPA 712-C-018. January 2012. [HYPERLINK "http://www.regulations.gov/" \l
1415 "!documentDetail;D=EPA-HQ-OPPT-2009-0154-0017"]
1416
1417 USEPA. 2012c. Ecological Effects Test Guidelines OCSPP 850.3040. Field Testing for Pollinators. EPA 712-
1418 C-017. January 2012 [HYPERLINK "http://www.regulations.gov/" \l
1419 "!documentDetail;D=EPA-HQ-OPPT-2009-0154-0018"]
1420
1421
1422

CHAPTER 6 PROBLEM FORMULATION FOR AN ASSESSMENT OF RISK TO HONEY BEES FROM APPLICATIONS OF PLANT PROTECTION PRODUCTS TO AGRICULTURAL CROPS

Fischer, D., Alix, A., Coulson, M., Delorme, P., Moriarty, T., Pettis, J., Steeger, T., and
Wisk, J.D.

As mentioned in Chapter 5, Phase 1 of the risk assessment process is problem formulation⁷, (PF), where measurement endpoints are selected; a conceptual model is prepared that describes a risk hypothesis; and an analysis plan that articulates what data is needed and how it will be used to test the stated hypothesis is described. The problem formulation is intended to provide a foundation for the risk assessment, by articulating the purpose of the assessment, defining the nature of the problem (*i.e.*, potential for adverse effects given the nature of the chemical stressor and its existing and/or proposed use), and establishing the plan for analyzing available data and characterizing risk. Participants of the Workshop discussed the generic principles of problem formulation and developed PFs for the assessment of risk of honey bees for two types of pesticide use scenarios: (1) application of a systemic chemical to the soil or seeds planted into the soil, and (2) application of a non-systemic chemical as a foliar spray. It should be noted that there are other possible scenarios such as foliar spray application of a systemic chemical, which may require a separate PF because both contact and oral exposure routes may be important. Likewise, some modification of the PF examples presented herein by the Workshop will likely be needed to apply them to non-*Apis* species in order to account for differences in behavior and life history. The goal here is to illustrate the process for developing a PF for assessment of pesticide risk to honey bees and other insect pollinators by providing some relevant examples.

What is a Problem Formulation?

Problem formulation is the first step of an ecological risk assessment (**Figure 6-1**). The objective of problem formulation is to develop a working risk hypothesis regarding the potential exposure to and resulting effects of a stressor (*e.g.*, a pesticide) on ecological receptors of concern (*e.g.*, honey bees). During problem formulation, objectives of the

⁷ Problem Formulation is a widely utilized generic process for framing and developing an ecological risk assessment. This process is not necessarily employed by all regulatory authorities, nor employed in the same manner by those regulatory authorities that do employ the Problem Formulation process.
Pesticide RA for Pollinators 4-13-13

anticipated risk assessment are identified and underlying uncertainties and assumptions (constraints) regarding data are described. During problem formulation, initial scoping and integration of available information begins, and data/information gaps are identified. Within the context of a pesticide active ingredient being identified as a stressor, the problem formulation considers use information (which may include label information, formulations, application parameters (rates, methods, ~~timing and timing~~), crop types, or information on target pests) (see Text Box below).

Problem Formulation Questions: Assessing Available Information

Source and Stressor Characteristics

- What is the source of the stressor (anthropogenic, natural, point source, *etc.*)?
- What type of stressor is it (chemical, physical, or biological)?
- What is the intensity of the stressor (the dose or concentration, the magnitude, or extent of the disruptions)?
- What is the mode of action? How does the stressor act on organisms or ecosystem functions?

Formatted: Font: Italic

Problem Formulation Questions: Assessing Available Information (continued)

Exposure Characteristics

- With what frequency does the stressor event occur (is it isolated, episodic, continuous)?
- What is the duration of the exposure? How long does it persist in the environment? (half-life, does it bioaccumulate, does it alter habitat, does it reproduce, or proliferate)
- What is the timing of exposure? When does it occur in relation to critical organism life cycle(s) or ecosystem events?
- What is the spatial scale of exposure? Is the extent or influence of the stressor local, regional, global, habitat-specific or ecosystem-wide?
- What is the distribution? How does the stressor move through the environment?

Ecosystems Potentially at Risk

- In what habitats is the stressor present?
- How do these characteristics influence the susceptibility (sensitivity and likelihood of exposure) of the ecosystem to the stressor(s)?
- Are there unique features that are particularly valued (*i.e.*, the last representative of an ecosystem type)?
- What is the landscape context within which the ecosystem occurs?
- What are the geographic boundaries of the endpoint? How do they relate to the functional characteristics of the ecosystem/endpoint?
- What are the key abiotic factor(s) influencing the endpoint (*e.g.*, climatic, geology, hydrology)?
- Where and how are functional characteristics driving the ecosystem?
- What are the structural characteristics of the ecosystem (*e.g.*, species number and abundance, trophic relationships)?

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Ecological Effects

- What are the type and extent of available ecological effects information (*e.g.*, field surveys, laboratory tests, or structure-activity relationships)?
- Given the nature of the stressor (if known), which effects are expected to be elicited by the stressor?
- Under what circumstances will effects occur?

Formatted: Font: Italic

1499




Figure 6-1 [SEQ Figure * ARABIC]. Scheme depicting problem formulation phase of the ecological risk assessment process. (taken from USEPA, 1998)

Problem formulation has three deliverables (see middle box of **Figure 6-1**):

- (1) risk assessment endpoints that reflect management/ protection goals, and the ecosystem they represent;
- (2) conceptual models that describe key relationships between a stressor and assessment endpoint; and,
- (3) an analysis plan.

A critical component of problem formulation is planning dialog (left box of **Figure 1**) where risk assessors and risk managers identify and agree on management objectives and identify issues associated with the chemical. Problem formulation is intended to be iterative and is informed by existing data (including open literature, existing data, or incident information). As more data become available, the risk hypothesis may change to reflect a more refined understanding of potential risks. The problem formulation identifies available data and information gaps and enables risk managers to convey potential limitations to registrants (chemical manufacturers who support labels) who may be able to provide information to address uncertainties.

Components of problem formulations include:

- 1) A description of the nature of the chemical stressor (typically a single technical grade active ingredient, but may include formulations, inert ingredients or degradates of the active ingredient based on the availability of data);
- 2) A broad overview of pesticide existing/proposed uses;

- 3) A description of assessment endpoints, *i.e.*, valued entities (biological receptors) and their attributes, *i.e.*, characteristics to be protected (survival, growth and reproduction), which are relevant to management/ protection goals;
- 4) A conceptual model which identifies the relationship between ecological entities and the chemical stressor under consideration. The conceptual model has two components, *i.e.*, the risk hypothesis and conceptual diagram.
 - a. The risk hypothesis describes the predicted relationships among the chemical stressor, exposure and assessment endpoint responses along with a rationale to support the hypothesis.
 - b. The conceptual model diagram illustrates the relationships presented in the risk hypothesis and is typically represented by a flow diagram depicting the source (use), stressor, receptor and change in [endpoint] attribute.
- 5) An analysis plan is then presented to identify how the risk hypothesis will be assessed; it identifies data needs and methods for conducting the assessment and what measurements, *e.g.*, model-estimated environmental concentrations, no-observed adverse effect concentrations (NOAEC) and attribute changes, *e.g.*, foraging behavior, will be used.

Selecting Assessment Endpoints

Assessment endpoints are explicit expressions of the actual environmental value that is to be protected. Selection of assessment endpoints begins to structure the assessment toward addressing management concerns. Assessment endpoints must be measurable ecosystem characteristics that represent protection goals. Selection of ecological characteristics to protect becomes then, the basis for defining assessment endpoints, which connects broad protection goals with specific measures in risk assessment.

The element or characteristic of an ecosystem to be valued or protected must:

- (1) have ecological relevance;
- (2) be susceptible to known or potential stressors; and,
- (3) be relevant to protection goals and societal values.

Ecological Relevance

Ecologically-relevant endpoints reflect important characteristics of the system and may be defined at any level of organization (*e.g.*, individual, community, population, ecosystem, landscape). Ecologically relevant endpoints often help sustain the natural structure, function, and biodiversity of a system or its components.

Ecologically-valuable endpoints are those that, when changed, cause multiple or widespread effects (*i.e.*, are upstream of other effects in the ecosystem).

Susceptibility to Known or Potential Stressors

An ecological resource is susceptible when it is sensitive to a stressor, *i.e.*, it is affected by the stressor such as through a mode of action. The sensitivity of an ecological resource may be relative to timing, *i.e.*, a life stage of an organism (or system), or may be affected by the presence of other stressors or natural disturbances. Measures of sensitivity may include mortality, behavioral abnormalities, loss of offspring, habitat alteration, community structural change, and/or other factors. Susceptibility (of an ecological resource) requires exposure such as through co-occurrence or contact. Typically, the amount and conditions of exposure directly influence how an ecological resource will respond to a stressor. Thus, timing of exposure, timing of effects, presence or absence of other stressors, and other variables add complexity to evaluations of sensitivity and/or susceptibility.

Defining, and Relation of Assessment Endpoints to Protection Goals

As noted earlier, measurement endpoints, assessment endpoints, specific protection goals and generic protection goals must all be related. Protection goals must be appropriately scaled in order to be represented by assessment endpoints. Assessment endpoints should remain neutral and specific, whereas protection goals represent a desired achievement (*i.e.*, a goal). As such, assessment endpoints do not contain words like “protect,” “maintain,” or “restore,” or indicate a direction for change such as “loss,” or “increase.” Instead, assessment endpoints are ecological values defined for specific entities and their measurable attribute, providing a framework for measuring stress-response relationships.

Risk assessors and risk managers should share their professional judgment when selecting and defining potential endpoints. Assessment endpoints themselves must be: (i) scientifically valid, (ii) important to the public, and (iii) valued by risk managers (*i.e.*, reflect statutory

obligations) in order for them to be relevant. Once ecological values are selected as potential endpoints (attribute changes), they must then be operationally defined. Two elements are required for operational definition:

- (1) identification of the specific valued ecological entity, such as a species, or a functional group of species, or a community or ecosystem or specific habitat or unique place; and,
- (2) the characteristics (attributes) of the entity that is important to protect.

For practical reasons, it may be helpful to use assessment endpoints that have well-developed test methods, field measurement techniques, and predictive models. However, this is not necessary, since appropriate measures for an assessment endpoint are identified during the development of the conceptual model and further specified in the analysis plan. The number and type of measurement endpoints depend upon the specificity of the question(s) being asked through the risk assessment and the complexity of the ecological entity being examined. Final assessment endpoint selection is an important risk manager-assessor checkpoint during problem formulation. Risk assessors and risk managers should agree that selected assessment endpoints effectively represent the protection goals.

Common problems in selecting assessment endpoints are:

- the endpoint is a goal
- the endpoint is vague
- the ecological entity is better suited as a measure rather than an endpoint
- the ecological entity may not be sensitive to the stressor
- the ecological entity is irrelevant to the assessment
- the attribute is not sufficiently sensitive for detecting important effects (*e.g.*, survival compared with recruitment for endangered species).

Conceptual Models

Conceptual model(s) provide a written and visual representation of predictive relationships between ecological entities and the stressor(s) and may describe primary, secondary or tertiary exposure pathways, co-occurrences, ecological effects, or ecological receptors that are reflective of valued attribute changes in these receptors. Multiple conceptual models may be developed to address several issues in a given risk assessment. When conceptual models

are used to describe pathways of individual stressors and assessment endpoints and the interaction of multiple and diverse stressors and endpoints, more complex models and sub-models will often be needed.

Conceptual models are flexible and can be modified to accommodate new or additional data. For example, conceptual models can start out as broad and identify as many potential relationships as possible, then narrow as information is acquired. The complexity of a risk hypothesis is commensurate with the complexity of the risk assessment.

Conceptual models consist of two principal components:

- (1) a set of risk hypotheses that describe predicted relationships among stressor, exposure, and endpoint response; and,
- (2) a diagram that illustrates the relationship(s) presented in the risk hypotheses.

Diagrams are typically flow diagrams with boxes and arrows. Elements considered for inclusion in the diagram include: the number of relationships depicted; the comprehensiveness of the information; data abundance or scarcity; or the relative certainty of the pathway(s). Several smaller diagrams may be more effective than a single diagram that contains too much detail. Diagrams should reflect/document a risk assessor's level of knowledge and degree of certainty regarding its components and should be discussed with risk managers to ensure that they reflect and communicate the manager's concerns prior to analysis.

Case 1: PF for a Systemic Chemical Applied to the Soil, or as a Seed-dressing

Stressor description

Participants of the Workshop developed a risk assessment process through two case examples that were representative of two general types of pesticide delivery modes, i.e., systemic and foliar. Briefly outlined below is an example of a Problem Formulation for the pesticide risk assessment for pollinators first for a systemic compound, and then for a foliar applied compound.

The stressor of concern is a systemic plant protection product (insecticide or acaricide) applied to the soil of field and orchard crops such as cotton, maize, oil-seed rape, wheat,

barley, potatoes, sugar beets, cucurbits (*e.g.*, melons), citrus and pome fruit, or as a coating on seeds of field crops (cotton, maize, oil-seed rape, wheat, barley). Crop plants absorb the chemical through the roots and translocate it into aboveground tissues of the plant. Magnitude of residue studies demonstrate that the parent compound, *per se*, comprises the residues found in treated plants. Use of the product provides effective control of several economically important chewing and sucking pest insects such as aphids, psyllids and whiteflies. Application timing is at planting or during transplant of field crops and after flowering of orchard crops.

The above paragraph covers the first two components of a PF, which were listed as (1) a description of the nature of the chemical stressor, and (2) a broad overview of pesticide existing/proposed uses. The third component of a PF is a description of assessment endpoints, *i.e.*, valued entities (biological receptors) and their attributes, *i.e.* characteristics to be protected (*e.g.*, survival, growth and reproduction), which are relevant to protection goals.

Protection goals

As discussed, protection goals are policy decisions that are set by government agencies and other organizations that represent the interests of the societies they serve. In the absence of specific protection goals, the participants used those developed during the workshop, which included:

- Protection of pollination services provided by *Apis* and non-*Apis* species'
- Protection of honey production and other hive products; and,
- Protection of pollinator biodiversity,

The first and third of these goals is applicable to pollinators in general (*Apis* and non-*Apis*). The second statement is applicable to managed pollinators (*Apis*).

Assessment endpoints

For honey bees, logical assessment endpoints are colony strength (population size and demographics), and colony survival (persistence). Bumble bees too can be measured against colony strength (larval ejection, number of offspring, or colony weight) and colony survival (persistence). Since a colony loss simply represents the situation when colony strength is

minimal, it could be argued that *colony survival* is not needed as a separate assessment endpoint. Various measures of colony strength are often made when beehives are rented and placed at agricultural crops. Rental fees are greater for strong colonies than weak colonies because colony strength is expected to be related to the quality of pollination service provided by the colony. Colony strength will likely be significantly impacted if queen viability, brood development, or general worker bee health is adversely affected for an extended period of time. There are many known cases where pesticide exposure has caused effects on colony strength, which meets the criteria for an assessment endpoint which includes:

1. the effected organism has ecological relevance;
2. the effected organism is sensitive, or susceptible to known or potential stressors; and,
3. the effected organism is relevant to the management/ protection goals and societal values associated with maintenance of pollination services.

For solitary bees, possible assessment endpoints may include adult survival, adult fecundity, larval survival and larval development time. Populations will be significantly impacted by decreased adult or larval survival and adult fecundity. Increased time for larval development for example, could impact (be delaing) individual bee emergence time and reduce the number of generations per year in multi-voltine species, or cause bees to enter diapauses too late which could ultimately relate to fecundity.

Conceptual Model

The fourth component of PF is the conceptual model which identifies the relationship between ecological entities and the chemical stressor under consideration. The conceptual model has two components: the risk hypothesis, and the conceptual diagram.

Risk Hypothesis

For a systemic pesticide applied to the soil or as a seed dressing, the risk hypothesis may involve the following steps describing how exposure most likely occurs and results in effects on an assessment endpoint (*e.g.*, colony strength). The hypothesis is:

- 1) the use of the systemic plant protection product results in concentrations in nectar, pollen or other parts of plants visited by honey bees;
- 2) forager honey bees collect the contaminated nectar and pollen and transport it back to the hive where it is incorporated into the food stores of the colony;

Formatted: Font: Italic

- 3) foragers, hive bees, bee brood and the queen are exposed to concentrations of the chemical mainly via ingestion;
- 4) if the exposure concentration is high enough, toxic effects on forager bees, hive bees, bee brood and/or the queen result in reduced queen fecundity, brood development success or survival of adult bees; and,
- 5) colony strength is affected as a result of reduced fecundity, brood success or adult survival.

The duration of exposure of forager bees depends on the persistence of the chemical in the soil and within the treated plants, the duration of bloom, and the chronology of application (planting of treated seeds or application to the soil) of the chemical to agricultural fields within the landscape around the hive. Based on the risk hypothesis, key questions that need to be answered during risk analysis are:

- 1) To what extent do foraging honey bees visit treated plants and collect materials (pollen, nectar, resins, honey) that may contain residues of the chemical being assessed?
- 2) At what level is the parent compound and the toxic metabolite present in materials (pollen, nectar, *etc.*) collected by honey bees?
- 3) How do the subject concentrations change over time when stored in the hive?
- 4) What concentrations in pollen and nectar when fed to a bee colony result in a significant decrease in queen fecundity, brood success, adult survival, and ultimately, colony strength?

Conceptual Model Diagram

The conceptual model diagram depicted in **Figure 6-2** below illustrates the relationships presented in the risk hypothesis for the assessment of risk of a systemic pesticide applied to the soil or as a seed dressing.

The source of exposure is application of the systemic plant protection product to the soil or as a coating to seeds planted in the soil. The primary routes of exposure are assumed to be via residues in pollen and nectar (yellow boxes); however, other routes of exposure such as ingestion of residues in surface water, plant exudates (*e.g.*, guttation fluid), and abraded seed dust are also included. Primary routes of residue transfer are indicated by thick arrows, lesser routes by thin arrows. Forager worker bees may be exposed by both contact and oral ingestion; however, since the chemical is applied to the soil, potential for contact exposure is assumed to be limited. The attendees of the Workshop believe that the main route of

exposure for worker bees is the oral route, particularly the ingestion of nectar, since nectar is the primary food consumed by forager worker bees. Pollen is also collected on hairs on the forager worker bees' bodies, or in small pouches (pollen baskets) on their hind legs. The nectar and pollen collected by worker bees are brought back to the hive where they are incorporated into the food stores, consumed by hive bees, and in turn used to produce food for the queen and developing brood. If the pesticide concentration is high enough, toxic effects on forager bees, hive bees, bee brood and/or the queen may result in reduced queen fecundity, brood development success or survival of adult bees. If these effects are severe enough and/or last long enough, a significant effect on colony strength may result.

[SHAPE * MERGEFORMAT]

Figure 6-2. Depiction of stressor source, potential routes of exposure, receptors and attribute changes for a systemic pesticide applied to the soil or as a seed dressing.

Analysis Plan

The final component of the PF is the analysis plan, which identifies how the risk hypothesis will be assessed. The analysis plan identifies the data needs and the methods for conducting the assessment. The analysis plan describes the measures of exposure (*e.g.*, estimated environmental concentrations, monitoring data) and measures of effects (*e.g.*, no-observed adverse effect concentrations (NOAEC)) that will be used. In the case of this example, the analysis plan may generally discuss the attribute changes that will be used for assessing risk to pollinators, including, individual bee mortality, colony strength (such as percent coverage of hive frames by adult bees, percent open brood and/or percent capped brood).

Data Needs for Exposure Characterization

While it may be possible to develop a computer model to predict residues of systemic chemicals in various plant tissues, such models are not currently available and direct measurements are obtained through field studies. For the purposes of this problem formulation, let us assume that field studies have been conducted to measure residue levels of the parent compound and the toxic degradate(s) in pollen and nectar. These measurements can be used to determine the median (50%tile) and high end (defined here as the 95%tile) concentrations expected in the pollen and nectar following and application. Estimated daily

intake rates for pollen and nectar by various castes of honey bees listed in Table 1 of Rortais *et al.* (2005) may be used to convert food concentrations (μg chemical/g of food) to a daily dose (μg chemical/individual bee/d). Some toxicity endpoints are expressed in units of a test concentration (*e.g.*, μg chemical/kg test matrix = parts per billion or ppb); or as a dose (*e.g.*, μg chemical/individual bee). The units of the measure of exposure must match the units of the measure of toxicity in order for a valid risk estimate to be calculated.

Data Needs for Effects Characterization

As described briefly in Chapter 8, the progression of effects data development begins with standard laboratory assays and then, if necessary, the continues on to higher tier studies which may consist of specialized laboratory, semi-field and/or field tests. In this sort of testing sequence, the results of higher tier studies are used to refine the overall conclusions about risk.

Because the main route of exposure expected for systemic chemicals is oral ingestion, toxicity testing of the oral route of exposure is needed to characterize potential effects of residues in bee foods. Standard protocols are available for conducting acute but not chronic oral toxicity tests. Food with residues of systemic compounds may be stored in the hive and used by the colony for long periods of time. The development of a standardized chronic feeding test may be needed. A 10-day feeding test of individual adult honey bees has been proposed by the International Commission on Plant-Bee Relationships (Alix *et al.*, 2009) as a means to provide a chronic toxicity measure. Alternatively, experiments in which whole colonies are fed prescribed concentrations of the test chemical for periods ranging from weeks to months have been performed with some systemic chemicals. Measures of effects of these various chronic tests have included the median lethal concentration and the NOAEC for various colony attributes, including colony strength (*e.g.*, percent frame coverage with adult bees, open brood, or capped brood).

If unacceptable risks cannot be discounted on the basis of simple laboratory test results, and conservative exposure assumptions, then higher tier studies may be conducted to determine the likelihood and severity of risks under conditions simulating actual agricultural use. Semi-field (tunnel) and field studies may have the advantage of evaluating all routes of exposure simultaneously under conditions reasonably similar to actual field use, whereas laboratory studies are generally limited to evaluation of a single route of exposure under artificial conditions.

1833

1834 **Risk Characterization Approach**

1835 Most assessments of ecological risks of pesticides use a conventional risk quotient (RQ) or
 1836 toxicity-exposure ratio (TER) approach that compares point estimates of exposure (*e.g.*,
 1837 typical and high end estimates of residue levels in various food types) to estimated thresholds
 1838 of toxicity (*i.e.*, median lethal concentration or NOAEC). The RQ equals the exposure point
 1839 estimate divided by the toxicity point estimate. Although RQ values are dimensionless
 1840 numbers, the greater the RQ, the greater is the presumed risk. TERs are the reciprocal of the
 1841 RQ, so the greater the TER, the lower the risk. Regulatory agencies compare the RQ or TER
 1842 to an established level of concern (LOC) that is presumed to represent a threshold between
 1843 minimal and non-minimal risk. If the RQ is less than the LOC, or the TER is greater than the
 1844 LOC, the risk may be presumed to be minimal and further testing is unnecessary provided the
 1845 constituent elements of the RQ are considered to be sufficiently inclusive. Risk assessment
 1846 is iterative with screening-level point estimates of exposure and toxicity often used in initial
 1847 assessments. If the RQ of a screening-level assessment exceeds the LOC, the conclusion is
 1848 the risk is potentially not minimal, and further testing may be appropriate to clarify the risk.
 1849 If semi-field and/or field tests are performed, these results may be incorporated into the risk
 1850 characterization (provided the studies are of sufficient quality) using a weight-of-evidence
 1851 approach.

1852

1853

1854

1855 ***Case 2: PF for a Contact Chemical Applied as a Foliar Spray***

1856

1857 **Stressor description**

1858 The stressor of concern is a “knock-down” insecticide product applied as a spray to field and
 1859 orchard crops such as cotton, maize, vegetables, citrus and pome fruit to control pest insects
 1860 that feed on stems, leaves, inflorescences and fruit. In this model, the pesticide does not
 1861 penetrate treated plant surfaces and so it is not translocated systemically throughout the plant
 1862 (note, however, that certain pesticides that have systemic properties may be foliarly applied).
 1863 For the purposes of this example, it is assumed that residues on plant foliage dissipate fairly
 1864 rapidly, with a foliar dissipation half-life of 2-3 days. Because of the short residual toxicity,
 1865 several applications may be necessary to protect plants during critical phases of the growing
 1866 season. Based on their chemical structure, none of the chemical’s major breakdown products

are expected to exhibit significant toxicity to insects. The product label recommends application rates that vary from 20 to 30 g active ingredient (a.i.) per hectare (ha), depending on crop and growth stage.

Management Goals

As discussed above, protection goals are policy decisions that are set by government agencies and other organizations that represent the interests of the societies they serve. In the absence of specific protection goals, the participants used those developed during the workshop, these included;

- Protection of pollination services provided by *Apis* and non-*Apis* species'
- Protection of honey production and other hive products; and,
- Protection of pollinator biodiversity,

Assessment Endpoints

For honey bees, logical assessment endpoints include colony strength (population size and demographics) and colony survival (persistence). Bumble bees too can be measured against colony strength (e.g., larval ejection, number of offspring, or colony weight) and colony survival (persistence). Since a colony loss simply represents the situation when colony strength is minimal, it could be argued that *colony survival* is not needed as a separate assessment endpoint. Various measures of colony strength are often made when beehives are rented and placed in agricultural crops. Rental fees are greater for strong colonies than weak colonies because colony strength is expected to be related to the quality of pollination service provided by the colony. Colony strength will likely be significantly impacted if queen viability, brood development or general worker bee health is negatively impacted for an extended period of time. There are many known cases where pesticide exposure has caused effects on colony strength. Colony strength appears to meet very well the previously listed criteria for an assessment endpoint. Colony strength

- (1) has ecological relevance;
- (2) is susceptible to known or potential stressors; and,
- (3) is relevant to protection goals and societal values.

As above, for solitary bees, assessment endpoints may include adult survival, adult fecundity, larval survival and larval development time. Populations will be significantly impacted by decreased adult or larval survival and adult fecundity. Increased time for larval development

could impact individual bees emergence time and reduce the number of generations per year in multi-voltine species, or by causing bees to enter diapauses too late; and, ultimately relate to fecundity and/or a sign that larvae will not emerge as healthy adults. There are known cases where pesticide exposure has affected these endpoints. These endpoints also fulfill the tested assessment criteria, as for the honey bee (see above).

Conceptual Model

The fourth component of PF listed previously is the conceptual model, which identifies the relationship between ecological entities and the chemical stressor under consideration. The conceptual model has two components, *i.e.*, the risk hypothesis and conceptual diagram.

Risk Hypothesis

The risk hypothesis describes the predicted relationships among the chemical stressor, exposure and assessment endpoint responses along with a rationale to support the hypothesis.

For a non-systemic pesticide applied as a foliar spray, the risk hypothesis involves the following steps describing how exposure most likely occurs and results in effects on the assessment endpoint (colony strength). The hypothesis is:

- 1) residues in spray droplets may (1) contact bees directly (*i.e.*, bees hit directly by the spray); (2) be deposited on plant surfaces visited by honey bees, and, (3) contaminate standing water (*e.g.*, puddles) from which bees drink, or
- 2) spray deposits hitting open flowers may contaminate nectar and pollen sources for a short period of time post-application (until these flowers are replaced by others that were not open during spray);
- 3) Forager honey bees may ingest contaminated water and/or contaminate nectar, and may collect and transport contaminated nectar and pollen back to the hive where these materials are processed, then incorporated into the food stores of the colony;
- 4) If the exposure concentration is high enough, toxic effects on forager bees, hive bees, bee brood and/or the queen may result in reduced survival of adult bees, brood development, or queen fecundity;
- 5) Colony strength is affected as a result of reduced fecundity, brood development or adult survival if these effects are severe enough or last long enough.

Formatted: Font: Italic

- 6) Since the chemical is knock-down insecticide with short residual time on foliage, the primary effect expected may be direct mortality of forager bees shortly after spraying (*i.e.*, a bee kill event).

The duration of exposure of forager bees will depend on the persistence of the chemical on plant surfaces, and the persistence (duration of bloom) of individual flowers that were hit by the application. As new blooms replace old ones, the potential for exposure may rapidly decrease. Thus, the main concern for foliar spray applications has traditionally been acute exposure of forager worker bees that results in a discrete bee kill event. However the possibility of residues in bee-collected pollen and nectar being brought to, processed and stored in the hive should be considered since this scenario may lead to chronic exposure of the hive bees, queen and bee brood.

Based on the risk hypothesis, key questions that need to be answered during risk analysis are:

- 1) To what extent are forager honey bees active when spray applications are made? (or, what is the relation between the application and the flowering of that crop?)
- 2) If forager bees incur contact exposure during or shortly after application, are the levels of exposure great enough to cause “knock-down” intoxication?
- 3) If spray deposits represent an initial lethal hazard to honey bees, how long does this situation last?
- 4) To what extent do foraging honey bees visit sprayed plants and water sources and collect materials (*e.g.*, pollen, nectar, resins, water) that may contain residues of the chemical?
- 5) What levels of the chemical are present in materials (*e.g.*, pollen, nectar, resins, water) collected by honey bees and brought back to the hive?
- 6) How do the above concentrations change over time, including changes in concentrations in hive-stored pollen and nectar?
- 7) What concentrations in pollen, nectar or beebread when fed to a bee colony result in a significant decrease in queen fecundity, brood development, adult survival, and ultimately, colony strength?

Conceptual Model Diagram

The conceptual model diagram depicted in **Figure 6-3** below illustrates the relationships presented in the risk hypothesis for the assessment of risk of a non-systemic chemical applied as a foliar spray.

1968
 1969 The source of exposure is foliar spray application of the non-systemic plant protection
 1970 product to crop plants. The primary routes of exposure are assumed to be via contact of
 1971 foraging bees with spray as it is applied or with freshly deposited residues on plant surfaces.
 1972 For flowers open during spraying, residues may occur in pollen and nectar, and these
 1973 materials may be brought back into the hive, processed and stored as food that is later utilized
 1974 by hive bees, bee brood and the queen. Another possible route of exposure is via surface
 1975 water (e.g., puddles) that are oversprayed and used by bees as a source of drinking water.
 1976 Primary routes of residue transfer are indicated by thick arrows, lesser routes by thin arrows.
 1977 Greatest exposure is expected for forager bees that may be exposed via contact with spray
 1978 droplets and residues on plant surfaces, and via ingestion of residues in water and nectar. If
 1979 the exposure level is sufficient enough, then forager bees may be killed to the extent that
 1980 colony strength is reduced (*e.g.*, large bee kill event).

Formatted: Font: Italic

1981
 1982 Bees in the hive could also be exposed, but the exposure levels are not expected to be as great
 1983 as for forager bees unless the hive is inadvertently sprayed (overspray) during application.
 1984 However, if pesticide residue in the forage area are high, then other bees may be exposed to
 1985 these high residues during social grooming. In addition, if concentrations in pollen and
 1986 nectar brought into the hive are high enough, toxic effects on hive bees, bee brood and/or the
 1987 queen may result. If these effects are severe enough and/or last long enough, a significant
 1988 adverse effect on colony strength may result.

1989
 1990
 1991

1992 [SHAPE * MERGEFORMAT] **Foliar Spray Application**
 1993 **Figure 6-3. Depiction of stressor source, potential routes of exposure, receptors and attribute changes for**
 1994 **a nonsystemic pesticide applied as a foliar spray.**

1995
 1996

1997 **Analysis Plan**
 1998 The final component of the PF is the analysis plan. The analysis plan identifies how the risk
 1999 hypothesis will be assessed. It identifies data needs and methods for conducting the
 2000 assessment and what measures of exposure (*e.g.*, estimated environmental concentrations)
 2001 and measures of effects (*e.g.*, no-observed adverse effect concentrations (NOAEC) and

2002 attribute changes (*e.g.*, colony strength attributes might include estimates of the percent
2003 coverage of hive frames by adult bees, open brood and capped brood) will be used.
2004

2005 **Screening Assessment**

2006 A simple Hazard Quotient approach is currently used in Europe to predict whether foliar
2007 applications of plant protection products have the potential to cause observable bee kills of
2008 adult foragers. This screen has been validated by comparing predictions to results of field
2009 studies and incident monitoring programs (see Mineau *et al.* 2008).
2010

2011 The HQ calculation is made as follows:

$$2012 \quad \text{HQ} = \text{application rate (g a.i./ha)} / \text{LD}_{50} (\mu\text{g/bee})$$

2013

2014 If $\text{HQ} < 50$, a minimal risk may be presumed

2015 If $\text{HQ} > 50$, a potential risk concern may be presumed -(more testing needed)
2016

2017 For example, it is assumed an acute contact toxicity study has been conducted and the LD₅₀
2018 for the chemical in question is 0.1 µg/bee. Using the maximum application rate of 30 g ai/ha,
2019 the HQ calculation would be $30/0.1 = 300$. Since this value is greater than 50, the risk of bee
2020 kills cannot be discounted as minimal. Further assessment is needed to evaluate risk.
2021

2022 **Data Needs for Refined Exposure Characterization**

2023 A label statement prohibiting application to crops during bloom until the evening or night
2024 time hours could go a long ways toward eliminating the possibility that foraging bees will be
2025 hit by the spray droplets as they are applied to the crop. A key piece of information needed is
2026 how long residues on sprayed vegetation remain toxic to visiting honey bees. This could be
2027 estimated from field studies that measure the magnitude and dissipation of residues on
2028 sprayed vegetation. It may be simpler to determine this using a standard EPA Tier 2 bioassay
2029 (discussed in greater detail in Chapter 7). Another key piece of information is to determine
2030 the residue levels in plant materials (mainly pollen and nectar) collected by forager bees and
2031 brought in to the hive. It may be necessary to conduct field studies to obtain direct
2032 measurements. Such measurements can be used to determine the median (50%tile) and high
2033 end (*e.g.*, 95%tile) concentrations expected to be present in pollen and nectar following an
2034 application. Estimated daily intake rates for pollen and nectar by various castes of honey
2035 bees listed in Table 1 of Rortais *et al.* (2005) may be used to convert food concentrations (ug

Formatted: Font: Italic

chemical/g of food) to a daily dose (μg chemical/individual bee/d). Some toxicity endpoints are expressed in units of a test concentration (*e.g.*, μg chemical/kg test matrix = ppb); others as a dose (*e.g.*, μg chemical/individual bee). The units of the measure of exposure must match the units of the measure of toxicity in order to for a valid risk estimate to be calculated.

Data Needs for Effects Characterization

The logical progression of effects data development is to begin with standard laboratory assays and, if necessary to conduct higher tier studies which may consist of specialized laboratory, semi-field and/or field tests. In this sort of testing sequence, the results of higher tier studies are used to refine the assessment and are weighted more heavily in reaching overall conclusions about risk.

Because the main route of exposure for forager bees is expected to be contact, the standard EPA Tier 2 bioassay with honey bees (*i.e.*, toxicity of residues on foliage (EPA 2012) may be appropriate. In this test, groups of honey bees are exposed via contact to vegetation which was sprayed in the field and then collected for testing after prescribed time intervals. For example, a common protocol is to evaluate the contact toxicity of vegetation at 2, 8 and 24 hours post-application. In the case of this chemical, let's assume it was found that a high level of mortality occurred in bees exposed to 2-h old foliar residues, but that normal honey bee survival was noted when bees were exposed to foliar residues collected 8 and 24 hours after application. Because this is a laboratory based study, results such as these would indicate that there is window of acute hazard from contact that exists for 2-8 hours after application of the subject pesticide.

To assess the significance of residues in pollen and nectar that may be brought into and stored in the hive, oral toxicity testing is needed. As a minimum, an acute oral toxicity test can be used to establish oral dose levels that are potentially lethal to adult bees. If there are indications that significant residues will be contained in stored food (pollen, honey, beebread), then a chronic feeding study may be needed to identify the no observed adverse effect concentration. A 10-day feeding test of individual adult honey bees has been proposed by the International Committee on Plant-Bee Relationships (ICPBR) as a means to provide a chronic toxicity measure to adult bees. Various kinds of larval feeding tests have been developed to establish dose levels that affect larval survival and development. Alternatively, experiments in which whole colonies are fed prescribed concentrations of the test chemical

for periods ranging from weeks to months have been performed with some chemicals. Measures of effects directly related to colony strength can be obtained from such studies.

If adverse effects cannot be discounted on the basis of simple laboratory test results, higher tier studies may be conducted to determine the likelihood and severity of effects under conditions simulating actual agricultural use. Semi-field (tunnel) and field studies may have the advantage of evaluating all routes of exposure simultaneously under conditions reasonably similar to actual field use, whereas laboratory studies are generally limited to evaluation of a single route of exposure under artificial conditions.

Risk Characterization Approach

Calculation of the screening assessment HQ represents an initial risk characterization of the chemical. If the HQ < 50, there is a presumption of minimal acute risk in the EU, based on historical investigations of bee kill incidents (Mineau *et al.* 2008). Based upon the results of the acute toxicity test and the use pattern, higher tier tests may be required by the EPA, which may provide some insight into whether the label statement requiring applications be made in late afternoon or evening will mitigate the potential risk. Since, in this example, a study showed residual toxicity lasting less than 8 hours, residues from applications made in the late afternoon or evening should not pose an acute hazard to bees that begin foraging the following day. A RQ or TER calculation could be calculated to assess the risk posed by residues in pollen and nectar. The RQ or TER calculation would compare the concentration measured in these matrices or dose taken in by various castes of bees to available toxicity endpoints (LD₅₀, no-observed-adverse-effect concentration, etc.). Finally, well-designed semi-field or field studies may provide the more reliable information regarding the level of risk actually occurring under field use conditions. A weight-of-evidence approach may be taken to integrate the various lines of evidence.

References

- Alix A, Chauzat M-P, Duchard S, Lewis G, Maus C, Miles MJ, Pilling E, Thompson HM, Wallner K. 2009. Guidance for the assessment of risks to bees from the use of plant protection products applied as seed coating and soil applications – conclusions of the ICPBR dedicated working group. *Julius-Kühn-Archiv* 423, 160 p.
- Mineau P, Harding KM, Whiteside M, Fletcher MR, Garthwaite D, and Knopper LD. 2008. Using reports of bee mortality in the field to calibrate laboratory-derived pesticide risk indices. *Environ. Entomol.* 37(2): 546-554.
- Pesticide RA for Pollinators 4-13-13

[PAGE * MERGEFORMAT]

2108 Rortais A, Arnold G, Halm M-P, Touffet-Briens F. 2005. Modes of honey bees' exposure to systemic
2109 insecticides: estimated amounts of contaminated pollen and nectar consumed by different categories of bees.
2110 *Apidologie* 36, 71-83.
2111
2112 USEPA. 1998. Guidelines for Ecological Risk Assessment. Published on May 14, 1998, Federal Register
2113 63(93): 26846 – 26924. [HYPERLINK "http://www.epa.gov/raf/publications/pdfs/ECOTXTBX.PDF"]
2114
2115 USEPA. 2012. Ecological Effects Test Guidelines OCSPP 850.3030 Honey Bee Toxicity of Residues on
2116 Foliage. EPA 712-C-018. January 2012. [HYPERLINK "http://www.regulations.gov/" \l
2117 "!documentDetail;D=EPA-HQ-OPPT-2009-0154-0017"]
2118
2119
2120

CHAPTER 7 ASSESSING EXPOSURE OF PESTICIDES TO BEES

Wisk, J.D., Pistorius, J., Beevers, M., Bireley, R., Browning, Z., -Chauzat, M.P., -Nikolakis, A., Overmyer, J., Rose, R., Sebastien, R., Vaissière, B.E., and Vaughan, M.

Introduction

An essential component of an ecological risk assessment is a prediction of exposure of the organisms being assessed. This chapter outlines exposure pathways for the different pesticide delivery methods, both non-systemic and systemic, and discusses methods used to predict pesticide exposure to honey bees and non-*Apis* bees. This chapter also provides an outline of techniques employed to measure pesticide residues in relevant matrices and discusses higher-tier field study designs that are used to refine bee exposure assessments for specific products. Finally, this chapter presents perspectives regarding pesticide application technologies that can be employed to mitigate bee exposure, as well as future research needs to further refine exposure assessments for this taxa.

Potential Exposure to Foraging Bees

Sprayed Compounds

Honey bees can be exposed to direct spray, or through contact with the crop to which a pesticide is applied. Bees can be exposed to pesticides that drift to plants on the edges of the treated field, potentially leading to either contact or oral exposure, as well as water sources near the treated field which may contain residues either from drift or surface run-off. Pesticide drift can also reach hives directly if the hives are located in or near a treated field. When foliar applications are made directly onto flowers, oral exposure can occur through the collection of contaminated pollen, nectar, or honeydew and/or by contact exposure if the product is directly sprayed on foraging bees or the plant parts that they can come in contact with during foraging

Micro-encapsulated Compounds

Microencapsulated technology is designed to increase adhesion of the product to the plant surface or soil through the use of a sticking agent.³⁷ Microencapsulation formulation technology is also used to control exposure by slowly releasing the pesticide. Bees can potentially be exposed to certain micro-encapsulated pesticides if the micro-capsules are similar in size to pollen. Bees may inadvertently collect the micro-capsules and bring them back to the hive. If the microcapsules are collected by bees and mixed into the beebread, the exposure may affect the whole colony as the pesticide will thus be fed to the larvae. Such incidents have been reported following the use of Pencap-M, a micro-encapsulated formulation of methyl-parathion (Mason, 1986).

Dust

Abraded dust that is contaminated with pesticide can be released from treated seed during planting operations involving pesticide treated seed (Alix *et al.*, 2009c). The exposure can be oral and/or contact from bees foraging on flowers upon which abraded dust falls. Bees may also be exposed if they flies through the dust or vapors released during planting operations;

Alix et al., 2009c; Fomici, 2007; Pastorus et al., 2009; Tapparo et al., 2012 (need to add) or, may receive exposure if they forage on weeds and flowers (*i.e.*, understory or in material that is adjacent to the target site) covered with contaminated dusts.

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Compounds with Systemic Properties

Pesticides that have systemic properties will move within the plant and may be expressed in the pollen and nectar. Pollen and nectar of plants treated with systemic compounds (such as treated seed, soil applications, ground drench or chemigation applications) may contain pesticide residues. These residues may be collected by foragers and brought back to the hive to be stored, processed and fed to adults and larvae.

Bees may be exposed to pesticide residues that may occur in rotational crops or alternative forage (understory or adjacent areas) that may take up and express pesticide residues applied at an earlier date. Even if target crops are not attractive to bees, compounds that are persistent may represent a potential source of exposure through soil, or through residues in the nectar and pollen of the succeeding (rotational) crop or associated weeds. The presence of pesticide residues in a succeeding crop may be influenced by the type of crop, treatment pattern, the physicochemical properties, and of course the environmental fate of the compound

2190 Other potential routes of exposure for foraging bees include inhalation (Seiber and
2191 McChesney, 1987; Seiber *et al.*, 1991), and consumption of aphid honeydew, guttation water
2192 (Girolami *et al.*, 2009), or chemigation water from soil treatments.

Formatted: Font: Italic

Formatted: Font: Italic

2195 **Potential Exposure to Non-foraging Bees (Wax)**

2196
2197 All members of a colony may be potentially exposed to contaminants through the wax which
2198 composes the hive. Larvae are reared in cells made of beeswax, and as adults they are in
2199 constant contact with the wax while they are in the hive. After pupation, bees chew through
2200 the wax coating on the brood capping and emerge as an adult. During colony development,
2201 worker bees continuously modify the wax cell structure (*e.g.*, converting male cells into
2202 worker cells, cleaning brood cells to stock honey and vice-versa). Pesticides that are
2203 lipophilic tend to accumulate in wax (Tremolada *et al.*, 2004) and if the beeswax contains
2204 pesticide residues, members of the colony, especially larvae, may be subject to contact
2205 exposure, depending upon the bioavailability of the pesticide (Chauzat *et al.*, 2007)
2206

2207 ***Nurse bees***

2208 For the first one to three weeks after emergence adult worker bees remain in the hive to
2209 perform many duties including, but not limited to, feeding and cleaning larvae, cleaning cells,
2210 building new cells, processing nectar and storing honey, packing pollen, and capping cells.
2211 Nurse bees may be potentially exposed to higher levels of pesticide residues by virtue of their
2212 duties. Nurse bees process pollen and nectar into beebread and honey, respectively, and also
2213 produce larval jelly. Nurse bees are the only caste/life-stage of honey bees that consume
2214 significant amounts of raw pollen, which is regurgitated and processed into beebread.
2215 Beebread is then stored in the hive until it is processed by nurse bees into brood food and fed
2216 to larvae. In addition, nurse bees can potentially be exposed to pesticides through water
2217 brought back to the hive for cooling and brood rearing. Nurse bees may also be exposed as
2218 they process nectar into honey within beeswax cells as well as through contact with wax
2219 while moving through the hive. Pesticides applied directly to the hive for *Varroa* sp. control
2220 and other pests are a direct route of exposure to nurse bees (Martel *et al.*, 2007). Nurse bees
2221 can potentially be exposed to pesticides during all of these activities if residues are present in
2222 the hive.
2223

2224 ***Drones***

2225 Upon emergence as adults, drones receive food from worker bees or eat stored honey. As
2226 larvae, drones receive more food than worker larvae, but the composition of that food is
2227 similar (Free, 1977). Similar to larvae and nurse bees, drones may be exposed to pesticides
2228 through food or residues within the hive.
2229

2230 ***Queens***

2231 Larvae that are fed only royal jelly beyond three days after hatching develop into queens
2232 (Free, 1977). A queen may live within the hive from 6 months to several years. Therefore,
2233 the queen may be exposed to multiple pesticides and residues within the hive over a relatively
2234 long period of time. Feeding on royal jelly and contact with residues in the hive are the
2235 potential routes of contaminant exposure for queens.
2236

2237 ***Honey bee larvae***

2238 Honey bee larvae can be exposed to pesticides through ingestion of contaminated food
2239 including pollen, beebread, honey, and larval jelly. Larval worker bees are fed royal jelly
2240 (also referred to as worker jelly or larval jelly) for three days after egg hatch. Royal jelly is a
2241 glandular secretion from the hypopharyngeal glands of nurse bees, and consists of some
2242 white components (mostly lipids) and a clear secretion (Free, 1977). Honey bees exposed to
2243 some pesticides can potentially produce contaminated larval jelly (Tremolada *et al.*, 2004)
2244 that could be fed to the queen, workers and the larvae. From the fourth to the sixth day after
2245 egg hatch, worker larvae are fed bee bread, which is largely processed pollen, but also
2246 includes some larval jelly, honey, and pollen (Free, 1977). The beebread can be
2247 contaminated if processed with contaminated pollen (Orantes Bermejo *et al.* 2010).
2248

2249 Water is brought back to the hive and used to cool the hive, dilute stored honey, and prepare
2250 larval food. If pesticide residues are present in this water that is brought back to the hive,
2251 larvae may be exposed through direct contact to the water or through ingestion of food
2252 prepared with the water. Larvae may also be exposed via contact exposure to pesticides that
2253 accumulate in wax or from residues on foraging bees. Additionally, larvae, as well as adults,
2254 may be exposed to insecticides/miticides applied directly to the hive by the beekeeper for
2255 varroa control and/or fungicides, bactericides or any other active substance applied for
2256 disease control.

2257

2258 **Residue movement through the hive**
2259

2260 Pesticides can be transferred into the hive environment from foraging honey bees that bring
2261 residues back to the hive in contaminated pollen and nectar. Pesticide residues can also move
2262 throughout the hive as workers pass food (especially nectar and diluted honey) among
2263 themselves as it is processed, stored, or consumed. All potential pesticide transfer to, and
2264 movement within in a hive is highly dependent on the use pattern of the pesticide product, as
2265 well as the physical and chemical properties of the contaminants. Some chemicals may
2266 persist in the hive, resulting in prolonged exposures, while others dissipate and/or degrade
2267 into metabolites. Some pesticide metabolites can also be toxic to honey bees (Suchail *et al.*,
2268 1999; Martel *et al.*, 2011). Therefore, while research continues to shed light on the fate and
2269 movement of a compound in a hive, it is important to understand and consider these
2270 properties of a compound in assessing potential exposure. Below is a conceptual model of
2271 exposure routes for pesticides to honey bee colonies.
2272




Figure 7-1 Conceptual Model showing how contaminants may potentially reach various matrices within honey bee colonies. Pollen, and nectar, are the main sources of in-hive contamination. Arrows show potential major contamination transfer routes. For minor routes, please refer to the text.

Figure 7-1 Needs to Be Redone

Potential Routes of Exposure for Non-*Apis* Bees

Most routes of exposure that have been examined for honey bees are valid for non-*Apis* bees as well. However, because of their diverse and often different biology, non-*Apis* bees may be prone to other routes of pesticide exposure. Understanding different exposure routes is important because it is not feasible to conduct tests on the more than 20,000 species of non-*Apis* bees worldwide (Michener, 2007). A risk assessment for non-*Apis* bees can be based mainly on the exposure routes reviewed for honey bees and tailored for different non-*Apis* species groups. If more specific exposure information is required for risk assessment refinements, actual measures of unique exposure pathways may be adapted from tests conducted on some key non-*Apis* species (see section below on Higher Tier Studies). Because of the large diversity of non-*Apis* biological features, this section will be structured around some broad features of non-*Apis* bee ecology.

Nesting sites and nesting materials for non-*Apis* species

Social non-*Apis* bees, such as stingless bees nest in cavities that are usually located aboveground. In addition, plant resins used for nest construction may be contaminated by

pesticide applications (Romaniuk *et al.*, 2003), and while honey bees also use resin in nest construction, certain non-*Apis* species employ resins to a greater extent in nest building (Murphy and Breed, 2008; Roubik, 1989). Most bumble bee species, (*e.g.*, *Bombus terrestris*, *B. lapidarius* and *B. subterraneus*), nest underground in abandoned nests of rodents and, therefore, are protected from direct spray applications. However, other non-*Apis* species nest above ground in cavities (*e.g.*, *Melipona* spp. and *Trigona* spp.) or under patches of grasses and vines (*e.g.*, *B. pascuorum* and *B. ruderarius*) where there is greater potential exposure to drift, or direct pesticide applications (Pouvreau, 1984; Thompson, 2001). Stingless bees and bumble bees mainly use wax to build their nests, but, unlike honey bees, they also commonly mix it with pieces of grass, leaves and various substrates (Pouvreau, 1984; Roubik, 1989), which may also be a source of exposure to contaminants.

Among solitary bees, the location of the nests as well as the material used to build them can vary considerably. The gregarious ground nesting species can occur in large aggregations of several thousand individuals in natural sites (*e.g.*, Potts and Willmer, 1998) or in man-made bee beds such as for *Nomia melanderi* (Cane, 2008). In addition, ground-nesting bees can be found along the border of fields planted with annual crops, but also in the soil within such fields (Vaissière *et al.*, 1985; Shuler *et al.*, 2005; Kim *et al.*, 2006). Therefore, the dissipation rate of pesticides in soil is a key factor affecting potential exposure to species that nest in the field. Among the “tunnel nesters”, leafcutter bees (Megachilidae, especially *Megachile* spp.) use excised leaf or petal pieces, as their common name suggests, to line their burrows and seal each cell once their egg has been laid on a ball of pollen and nectar. These leaf pieces are collected from a large array of plants, such as alfalfa and rose bushes.

The second largest group of solitary bees consists of species that nest in pre-existing cavities (mostly tunnels) in dead wood, hollow twigs and bamboo, or pithy stems such as elderberry (*Sambucus* spp.). These include most bees in the genera *Osmia* and *Megachile* (Cane *et al.*, 2007). Other species, such as carpenter bees (*Ceratina* spp., *Lithurgus* spp. and *Xylocopa* spp.) drill their nest tunnels in soft wood or the soft pith of some plant stems.



Leafcutter bee on blanket flower, photo by Mace Vaughan

Other bees build their nests with flower petals (*e.g.*, *Hoplitis* spp.), or plant hairs (*e.g.*, wool-carder bees such as *Anthidium manicatum*) (Gibbs and Sheffield, 2009), and many mason bees, *Osmia* spp., use mud to build partitions between the different cells of their nests (*e.g.* Bosch and Kemp, 2001; Mader *et al.*, 2010), and exposure to pesticides may occur from these materials if contaminated (Waller, 1969; Johansen and Mayer, 1990). The increasing use of systemic insecticides, not only in commercial agriculture but also in residential or recreational scenarios, may result in exposure of certain species (Vera Krischik, personal communication), especially some species of *Osmia* that chew up pieces of leaves to create walls of pulp to separate brood cells. This however, requires further study to better understand.

Exposure at immature stages of non-*Apis* species

As stated previously, honey bee worker and drone larvae feed on food that has been processed, which may result in modifications (*e.g.* degradation) of pesticide active ingredients in food stores. However, this differs from scenarios of solitary non-*Apis* bees whose larvae feed directly on raw pollen and nectar in either a mass provisioning manner or sequential mass provisioning manner (*i.e.*, brood cells are provisioned over various timeframes). As such, exposure via food may differ between *Apis* and non-*Apis* species feeding on mostly unprocessed pollen, nectar, and other floral resources (O'Toole & Raw 1996, Pereboom 2000). Therefore, exposure estimates based on stored honey bee pollen which is converted to royal jelly may not be predictive of the chemical residues fed to non-*Apis* bee brood (Konrad *et al.* 2008). In addition, with bees that mass provision their cells, (*i.e.*, most non-*Apis* bees), the egg(s) and larvae are in direct contact with the pollen and

Formatted: Font: Italic

nectar provision during the early life stages (*i.e.*, the egg and first instar). Honey bees, on the other hand, are isolated in their cells and are fed progressively by nurse honey bees, and therefore, have a very different exposure profile (Winston, 1987).

Foraging Time and Mating

Among solitary non-*Apis* bees, males are the first ones to emerge from the nest, followed a few days later by females. Non-*Apis* bees vary considerably in adult size from a few mm (*e.g.*, *Perdita* spp.) to the very large carpenter bees (*Xylocopa* spp.) and bumble bee queens (*Bombus* spp.) that routinely reach 3-cm long or more (Michener, 2007). Most non-*Apis* bees are smaller than honey bees and, therefore, can be exposed to relatively higher amounts of pesticides by contact because of the higher surface area to volume ratio of smaller species. (This has been demonstrated with intra-specific [pesticide toxicity] tests that have indicated that some smaller bees are more sensitive than larger bees at similar exposures on a unit / bee basis (Thompson and Hunt, 1999; Malone *et al.*, 2000).

Peak foraging time for honey bees is generally during warm, non-overcast conditions (Riedl *et al.*, 2006; Tew, 1997; Johansen and Mayer, 1990). However, this is not the case for many non-*Apis* bee species, such as bumble bees and mason bees (*Osmia* spp.), which are known to forage during cool, inclement weather, as well as earlier and later in the day and earlier and later in the season than honey bees (Thompson and Hunt, 1999; Vicens and Bosch, 2000; Bosch and Kemp, 2001; Thompson, 2001). Similarly, squash bees (*Peponapis*, and *Xenoglossa* spp.) are active in the early pre-dawn hours (Sampson *et al.*, 2007). In addition, males of many non-*Apis* bees often spend the night in flowers or hanging from plants, potentially leading to higher exposures (Sapir *et al.*, 2005). However, male squash bees that spend the night in closed squash blossoms may receive some level of protection from nighttime pesticide applications because the blossoms close tightly around them.

Food Sources

Honey bees are extreme generalists in that a colony will forage for nectar and pollen on a large array of plant species (polylecty). This is not so for most non-*Apis* bees, especially for the 80% or more which are solitary. These species often gather their pollen on a few species of taxonomically related plant species (oligolecty) and sometimes on a single species. Indeed, non-*Apis* bees may also forage, and even specialize, on plants not readily visited by honey bees, (*e.g.* potato, many legumes, and some ornamentals). As a result, pesticide

exposure (to generalists) may be “diluted” from various floral resources across a wide landscape. For example, tomato and potato flowers do not produce nectar but will release their pollen through buzz-pollination (sonication). Although, it is possible that pollen from flowers of this type could be shielded from foliar pesticide applications (because of the unique plant morphology), and considered safe for honey bees, they remain a potential exposure scenario for non-*Apis* bees.

Size

Another factor affecting foraging and exposure in non-*Apis* bees is the size of some non-*Apis* bees, and the relationship between foraging distance and species size. Some non-*Apis* bees are much smaller than honey bees (e.g., bees of the genera *Perdita* or *Dialictus* in the U.S. and *Nomioides* in Europe), and therefore are subject to relatively greater exposure because of the higher surface area to volume ratio of smaller bodies (i.e., µg of pesticide that contacts the body/mg body weight). Indeed, even intra-specific tests of pesticide toxicity to bumble bees have confirmed that smaller bees may be more effected than larger bees for a specific dose

A second size-related factor affecting potential exposure of non-*Apis* bees is the relationship between size and foraging distance. Whereas large bees, such as honey bees, bumble bees or carpenter bees (*Xylocopa* spp.), easily forage over several km from their nest (Beckman and Ratnieks, 2000; Goulson and Stout, 2001; Pasquet *et al.*, 2008), small bees may only fly a few hundred meters from their nest site (Greenleaf *et al.*, 2007). This factor may potentially result in higher exposure to small bees, compared to larger species, that are attracted to blooming crops, where their limited foraging range necessitates nearby nesting, and ongoing exposure to pesticide applications throughout the growing season. In some landscapes (e.g., New Jersey, USA), small bees (e.g., *Halictus* and *Lasioglossum* spp.) perform a significant amount of crop pollination (Winfree *et al.*, 2007a; Winfree *et al.*, 2007b).

Somewhat related to foraging distance is the tendency of certain solitary bees to collect pollen from one area, and often from only one or a few plant species, whereas honey bees forage on a wide variety of plant species across a large landscape. Honey bee foraging areas and sources of nectar and pollen can vary considerably from one day to the next (Visscher and Seeley 1982). Therefore, due to the foraging behavior, the pesticide residues on one crop may be diluted in a honey bee colony diet, but not so in the nest of a non-*Apis* species.

2424

2425

2426 **Methods and Models for Estimating Exposure of Bees to Pesticides**

2427

2428 Currently, there are no globally accepted approaches for estimating exposure of pesticides to
2429 bees for screening-level risk assessments. Participants of the Workshop reviewed current
2430 methodologies employed in the U.S. and EU, and evaluated information that can be used or
2431 developed to establish exposure estimates for screening-level risk assessments for both honey
2432 bees and non-*Apis* bees.

2433

2434 **Screening Level Exposure Estimates**

2435 Atkins *et al.* (1981) conducted laboratory contact toxicity studies and corresponding field
2436 studies with 65 pesticides. The field hazards were studied in a large number of commercial
2437 fields during bloom using crops that were highly attractive to honey bees. Data developed by
2438 Atkins *et. al.* indicated that, for foliar applied products, the median lethal dose (LD₅₀) in
2439 micrograms of active ingredient per bee (µg a.i./bee) can be expressed as the equivalent
2440 number of kilograms of chemical per hectare (kg ai./ha) (that would yield an media lethal
2441 dose) by multiplying by 1.12. For example, an acute contact LD₅₀ of 1 µg a.i./bee (highly
2442 toxic according to Atkins *et al.* classification scheme) would equate to an application rate of
2443 1.12 kg a.i./ha, (or pound per acre). In the European Union, the Hazard Quotient (HQ)
2444 approach is used as a screening-level assessment to distinguish between compounds with
2445 either potentially low or high risk of acute poisoning from foliar pesticide applications. The
2446 HQ relates the application rate of a product with laboratory oral and contact LD₅₀ values.

2447

2448 $HQ = \text{Application rate (g a.i./ha)} / \text{Contact or Oral LD}_{50} (\mu\text{g a.i./bee})^8$

2449

2450 **EPA Residue Unit Dose (T-Rex), comparison of lab contact toxicity data with residue**
2451 **data from T-REX**

2452

2453 EPA has typically employed the Terrestrial Residue Exposure Model (Trex) when
2454 investigating foliar applied pesticides. This model is used to predict residues on food items
2455 (*e.g.*, vegetation, seeds, insects) for birds and mammals, and is based on a nomogram
2456 developed by Hoeger and Kenaga (1972). The contact exposure to a bee (which to this point
2457 has only been done for endangered species analysis) is calculated by multiplying the residue

⁸ See Chapter 8 for more a discussion on acute (dermal or oral) toxicity tests
Pesticide RA for Pollinators 4-13-13

2458 predicted for broadleaf plants/small insects by the assumed weight of a foraging honey bee
2459 (0.128 g) (Mayer and Johansen, 1990) to establish a dose per bee ($\mu\text{g ai/bee}$).

2460
2461 Although the TREX method could potentially be useful for developing a screening-level
2462 exposure estimate for bees in a risk assessment process, the values developed by Hoeger and
2463 Kenaga (1972) are not based on residue data for insects but rather on plants or plant parts of
2464 similar size (Fletcher *et al.*, 1994). Data from Hart and Thompson (Hart *et al.*, 2001) indicate
2465 that the 95th percentile value for an insect residue per unit dose (RUD) is 24 mg/kg compared
2466 to 135 mg/kg for broadleaf plants (EPA's surrogate for small insects) which is approximately
2467 six-fold higher. Data from additional studies (Fischer and Bowers, 1997; Brewer *et al.*, 1997)
2468 also suggest that the insect residue estimates developed by Hoeger and Kenaga (1972) are
2469 greatly overestimated.

2470

2471

2472 **ICPBR (EPPO) proposal for seed treatment or soil applied systemic compounds**

2473

2474 The main route of exposure of bees to residues from systemic compounds (such as those
2475 applied as a seed treatment or soil application) is through the translocation of the compound
2476 into nectar and pollen. Data on measured residue levels in different plant parts have been
2477 compiled and analyzed by Alix *et al.* (2009a). Residue levels in plant parts were measured
2478 after treatment with systemic insecticides for the purpose of developing Tier 1 exposure
2479 assessments. The compiled residue data base considered residues values as close as possible
2480 to flowering. Based on their analysis, a default maximum residue value of 1 mg a.i./kg plant
2481 matrix has been proposed as a peak value for the screening-level exposure estimate for
2482 systemic compounds used as seed treatments or applied to soil (Alix *et al.*, 2009a, Alix and
2483 Lewis, 2010). In the event the Tier 1 risk assessment based on this worst-case estimate
2484 indicates a potential risk, actual measured residues from higher-tier studies can be used for a
2485 refined risk assessment. If there is a need to transform the Tier 1 predicted concentrations in
2486 pollen and nectar into predicted doses for honey bees, it is recommended to follow the
2487 proposals as outlined by ICPBR (Alix *et al.*, 2009a), which uses pollen and nectar
2488 consumption rates by different castes of honey bees (Rortais *et al.*, 2005). The published
2489 consumption rates are provided later in this chapter (see Predicted Dietary Exposure to Foliar
2490 Applied Products).

2491

Physical and chemical properties of pesticide active ingredients that affect exposure

The physicochemical properties of the pesticide active ingredient determine its fate in soil and in hive matrices which can affect the exposure of the various life stages of both *Apis* and non-*Apis* species to these chemicals.

1) Fate in soil – systemic products

Systemic products applied to soil can be taken up by the plant and translocated into plant foliage, floral nectar and pollen. Persistent systemic products that remain in the soil for over one year could potentially be translocated into the nectar and pollen of rotational crops planted in succeeding years. The dissipation time or DT₅₀ is used to characterize the persistence of pesticides in soil.

Physicochemical properties of the pesticide active ingredient that can affect persistence in soil include water solubility, the octanol-water partition coefficient (K_{ow}), dissociation constant (K_a), the soil adsorption coefficient (K_d) and the organic carbon partition coefficient (K_{oc}). Pesticides with high water solubility and low K_{oc} (e.g., <50) values have a higher potential for mobility, do not strongly adsorb to soil particles and can be prone to leaching depending on soil conditions, weather and persistence of the compound. The log of the K_{ow} (log K_{ow} or log P) is the measure of a chemical's propensity to bioaccumulate. Pesticides with a high log P (e.g., > 3) usually have low water solubility and are not highly mobile in soil. The log of the dissociation constant (p K_a) is a measure of the extent to which a substance ionizes in equilibrium with water. The p K_a of a pesticide indicates the ratio of the forms (ionized or undissociated) in which the chemical will exist in environments of various pH values, and extent of its potential involvement in ion-exchange binding processes in soils or sediments. The form of a pesticide (anion or cation) can influence its mobility and hence persistence in soil. Soil type and meteorology (amount of rainfall, temperature) can also influence the persistence of a pesticide in soil.

Specific criteria to classify compounds as being persistent in soil have been identified by the EU (EEC, 2006) and other regulatory agencies to trigger the requirement of rotational crop residue studies (used to inform human health risk assessment). It has been proposed that similar criteria be used to require assessment for the risk of residues in pollen and nectar for succeeding crops (Alix and Lewis, 2010).

2) Fate in hive matrices – systemic and non-systemic products

Physicochemical properties including water solubility, log P, and the pK_a can influence fate of the active ingredient in the hive. Compounds with a high log P that are hydrophobic (*i.e.*, tending to be insoluble in water) may accumulate in wax, pollen, and beebread, which contain lipids. Compounds with a high solubility in water (hydrophilic) can partition to nectar and honey which contain water. If the compound dissociates, the dissociation constant may be used to indicate fate in acidic matrices such as honey.

Information needed to develop refined predictive exposure models

As stated above, there are no defined predictive models currently used for estimating exposure levels in bees or bee matrices for use in a screening-level ecological risk assessment. The procedures described here that have been previously used by the EU and Canada for example, and employ values for potential exposure, have been effective in screening-out compounds that have low potential risk to adult worker bees from foliar-applied products. However, for crop protection products where potential risk cannot be excluded based on current Tier 1 screening analysis, the current method to refine assessments consists of higher-tier effects or exposure assessment studies (*e.g.*, EPA Tier 2 foliar residue study, EPPO tunnel test).

Optimally, there should be methods to predict residue levels in relevant matrices (*e.g.*, bees, pollen, nectar). These predicted exposure concentrations could then be used to compare with laboratory toxicity data, such as acute contact LD₅₀ values for adult bees, and acute and chronic dietary toxicity data for adult bees and larvae to estimate risk to both foraging bees and other castes and life-stages in the hive, including larvae.

Predicted Contact Exposure for Foliar-Applied Products

For foliar-applied products, the prediction of residues on foraging bees due to contact exposure (*i.e.*, direct spray on foraging bees or bees contacting residues post-spray) can be estimated. The U.S. EPA has proposed using predicted concentrations in insects based on

estimates in their T-REX wildlife exposure model. However, as noted above, there are some inherent uncertainties with using this approach. In this approach, values from T-REX Version 1.4.1, which relies on residue estimations developed by Hoeger and Kenaga (1972) for plants, fruits, and seeds, would be used as surrogate data to estimate contact exposure for insects. However, actual field residue data are available for honey bees (Koch and Wei er, 1997) and a variety of flying, soil-dwelling and leaf-dwelling arthropods (Schabacker *et al.*, 2005) that can be used for estimating contact exposure to bees. In a multi-year study by Koch and Wei er (1997), the fluorescent tracer sodium fluorescein was applied to flowering apple orchards or flowering *Phacelia* fields while honey bees were actively foraging, to determine contact doses in individual honey bees. After applications of 20 g sodium fluorescein/ha, doses in honey bees ranged from 1.62 to 20.84 ng/bee, and 6.34 to 35.77 ng/bee for honey bees foraging in apples and *Phacelia*, respectively. If the maximum detected residue in this study (35.77 ng/bee after an application of 20 g/ha) was used as a point estimate for a screening-level exposure assessment, a Predicted Environmental Dose due to contact exposure (PEDc) in adult honey bees after an application of 1 kg/ha (1000 g/ha) would be 1789 ng/bee or 1.79 µg/bee. The assumption here is that there will be a linear relationship between application rate and contact dose of foraging bees, which is an area of uncertainty.

Formatted: Font: Not Bold

In the report by Schabacker *et al.* (2005), maximum residues in flying, ground-dwelling and foliage-dwelling arthropods from a number of field trials were compiled and residue unit doses (RUDs) were calculated. The mean and 90th percentile RUDs in mg/kg after application of pesticides at a rate of 1 kg as/ha are summarized in Table 7-1 below.

Table 7-1. Predicted Concentrations (in mg/Kg) After Foliar Application of 1 kg/ha*

Arthropod classification	Mean Predicted Concentration in mg/kg	90 th Percentile Predicted Concentration in mg/kg

Formatted: Centered, None, Space Before: 0 pt, Don't keep with next, Don't keep lines together

Formatted Table

Flying insects	1.4	6.6
Ground-dwellers (orchard/vines, grasslands, late growth stages of leafy crops and cereals (insecticides and fungicides))	3.6	9.8
Ground-dwellers (orchard/vines (herbicides), early growth stages of leafy crops and cereals (all pesticides)	6.7	15.6
Leaf-dwellers	9.5	47.8

*Data from Schabacker *et al.* (2005)

When residue data for flying insects are used to develop a screening-level point estimate for contact exposure of foraging bees, a 90th percentile PEDc after an application of 1 kg a.i./ha is calculated to be 0.84 µg/bee. This is derived by multiplying the 90th percentile concentration in flying insects (6.6 mg/kg) by the weight of an adult foraging honey bee (128 mg) (Mayer and Johansen, 1990). This point estimate (0.84 µg/bee) is close to the exposure value calculated using the data of Koch and Weißer (1.79 µg/bee), and is consistent with the data developed by Atkins *et al.* (1981), where a dose of 1 µg/bee represents an application rate of 1 lb a.i./acre. Therefore, according to the Atkins method, an application of 1 kg a.i./ha is equivalent to an exposure value of 0.89 µg/bee. Based on this information, a worst-case estimate predicted exposure dose for contact (PEDc) to honey bees after an application of 1 kg a.i./ha is 1.79 ug/bee.

To evaluate the sensitivity of the proposed point estimate of exposure for honey bees a generic data set (LD50 values) can be used to calculate Hazard Quotients and TER⁹s, along with the value of 1.79 µg/bee after an application of 1 kg a.i./ha. Using a generic data set with an application rate of 100 g a.i./ha, the corresponding HQ, TER and RQ values are summarized in Table 7-2, below..

Table 7-2. Comparison of Hazard Quotient (HQ), Toxicity/Exposure Ratios (TER) and Risk Quotients (RQ) assuming a predicted contact exposure dose (PEDc) of 1.79 µg a.i./bee after an application of 1 kg a.i./ha.

Use Rate	PEDc	Contact	HQ	TER	RQ
----------	------	---------	----	-----	----

⁹ TER = LD₅₀ in µg a.i./bee / PEDc in µg a.i./bee; and, Risk Quotients (RQ) = PEDc / LD₅₀.
Pesticide RA for Pollinators 4-13-13

		LD ₅₀			
0.1 kg / ha	0.179 µg / bee	1 µg / bee	100	5.6	0.18
0.1 kg / ha	0.179 µg / bee	2 µg / bee	50	11	0.09
0.1 kg / ha	0.179 µg / bee	5 µg / bee	20	28	0.036
0.1 kg / ha	0.179 µg / bee	20 µg / bee	5	112	0.009

Formatted: Subscript

Formatted: Centered

Formatted: Centered

Formatted: Centered

Formatted: Centered

According to Annex VI of the EU Uniform Principles, a TER of ≥ 10 , designed to cover potential variabilities (such as inter-species), typically indicates acceptable risk for terrestrial organisms, and has been recommended as an appropriate assessment factor for oral exposure to systemic insecticides by ICPBR (Alix *et al.*, 2009a,b; Alix and Lewis, 2010). U.S. EPA on the other hand uses a level of concern (LOC) RQ of 0.1 for non-listed threatened or endangered aquatic or avian species. Based on this analysis, the screening-level risk assessment based on a PEDc of 0.179 µg/bee is in-line with the current EU screening HQ of 50.

Although the published field trial data (Koch and Weißer, 1997) for residues on honey bees are most appropriate for developing exposure estimates for honey bees, it might be more appropriate to use the data for leaf-dwelling and soil-dwelling arthropods developed by Schabacker *et al.* (2005) to address exposure to leaf-dwelling and soil-nesting non-*Apis* bee species, respectively. Therefore, for the initial, conservative point estimate of contact exposure, the 90th percentile predicted concentration for leaf-dwelling arthropods (47.8 mg/kg), can be used to develop a PEDc for leaf-dwelling species, while the 90th percentile predicted concentration for soil-dwelling arthropods (15.6 mg/kg) can be used to develop a PEDc for soil-nesting species. However, in order to complete this analysis and develop recommend PEDc values for leaf-dwelling and soil-nesting non-*Apis* bees, focal species need to be identified. For leaf-dwelling species, the leafcutter bee (*e.g.*, *Megachile rotundata*) is recommended as a surface dwelling non-*Apis* reference species, while the bumble bee (*Bombus* spp.), which typically nests on or underground, or mason bee (*Osmia* spp.), which collect mud for nest construction, is recommended for soil-nesting (gregarious) focal species. Ideally, ground-nesting solitary bees, such as sweat bees (*e.g.*, *Halictus* or *Lasioglossum* spp.), squash bees (*Peponapis* or *Xenoglossa* spp.), or alkali bees (*e.g.*, *Nomia melanderi*) could also be considered a representative soil-nesting species, for these insects dig nests underground. However, at least in North America, only *Nomia melanderi* is currently managed successfully on a larger scale. With the identification of focal species, the typical

Pesticide RA for Pollinators 4-13-13

body weights of the species can be used to convert predicted exposure concentrations in mg/kg to PEDc values in µg/bee for direct comparison to laboratory toxicity data.

Prior to adopting this proposed methodology into a formal regulatory assessment paradigm for bees, the method should be used to calculate toxicity/exposure ratios for some representative compounds to ensure that the exposure assessment methodology is sensitive enough to predict an acute risk to compounds that are highly toxic to non-*Apis* bees (e.g., pyrethroid insecticides), while not predicting a high risk for compounds that are known to have low inherent toxicity and present a low risk to non-*Apis* bees. Such an exercise would provide some feedback that the proposed methodology would not potentially be inconsistent with protection goals.

Predicted Dietary Exposure for Foliar Applied Products

For assessing acute or chronic dietary risk to adults or larvae, predicted concentrations in relevant food items (e.g., pollen, nectar, beebread, honey, and larval jelly) should be used as the dietary exposure estimate. Currently, models to predict residues in these items from foliar applied pesticide products do not exist. Although the results from survey-style analysis indicate that agricultural pesticides are entering managed honey bee colonies through contaminated pollen (Chauzat *et al.*, 2010; Mullin *et al.*, 2010), there are limited published data from controlled studies that relate foliar application rates to measured pesticide levels in pollen and nectar or in any processed hive food.

In a study by Choudhary and Sharma (2008), residues of three foliar applied pesticides were determined in nectar and pollen following applications to flowering mustard. Pesticides evaluated in this two-year study were endosulfan, lamda-cyhalothrin, and spiromesifen. Mean measured residues in pollen and nectar, and predicted concentrations after application of 1 kg a.i./ha are summarized in the following table.

Table 7-3. Day 0 Measured Concentrations of Three Foliar Applied Pesticides in Pollen and Nectar after Application to Flowering Mustard^a

Compound	Application rate (g a.i./ha)	Mean Measured Residues	Mean Measured Residues	Mean Predicted Nectar	Mean Predicted Pollen

Pesticide RA for Pollinators 4-13-13

Formatted: Centered
Formatted Table

		Nectar ^b (mg/kg)	Pollen ^b (mg/kg)	Residues (mg/kg) After Application of 1 kg/ha	Residues (mg/kg) After Application of 1 kg/ha
Endosulfan	525	1.725 ± 0.031	2.126 ± 0.088	3.15	3.99
		1.583 ± 0.006	2.068 ± 0.048		
<i>Lamda-</i> cyhalothrin	75	0.858 ± 0.038	1.607 ± 0.004	10.6	21.2
		0.728 ± 0.022	1.577 ± 0.018		
Spiromesifen	225	1.541 ± 0.078	2.003 ± 0.040	6.54	8.45
		1.401 ± 0.016	1.799 ± 0.033		

^aData from Choudhary and Sharma (2008)

^bMean measured residues from two successive application and sampling years

In a study by Wallner (2009), residues of the fungicides boscalid and prothioconazole were determined in pollen and nectar samples from foraging bees following applications to oil seed rape (canola). Mean measured residues in pollen and nectar and predicted concentrations after application of 1 kg a.i./ha are summarized in Table 7-4 below.

Table 7-4 Day 0 Measured Concentrations of Two Foliar Applied Fungicides in Pollen and Nectar Collected from Honey Bees after Application to Flowering Oil Seed Rape^a

Compound	Application Rate (g a.i./ha)	Mean Measured Residues Nectar (mg/kg)	Mean Measured Residues Pollen (mg/kg)	Mean Predicted Nectar Residues (mg/kg) After	Mean Predicted Pollen Residues (mg/kg) After
----------	------------------------------------	---	---	---	---

				Application of 1 kg/ha	Application of 1 kg/ha
Boscalid	500	1.43	26.2 ^b	2.86	52.4
Prothioconazole	250	0.69	nd (LOQ = 0.001)	2.76	-----

Formatted: Centered

Formatted: Centered

^aData from Wallner (2009)

^bConcentrations 1 day after treatment, which were higher than day-0 values

Finally, in a study by Dinter *et al.* (2009), concentrations of the insecticide chlorantraniliprole in pollen and nectar collected from foraging bees following applications to *Phacelia* in a semi-field study were determined. The maximum concentrations in pollen and nectar 1-day after treatment are summarized in Table 7-5 below.

Table 7-5. Day 1 Measured Concentrations of Chlorantraniliprole in Pollen and Nectar Collected from Honey Bees after Application to Flowering *Phacelia*^a

Compound	Application Rate (g a.i./ha)	Maximum Measured Residues Nectar (mg/kg)	Maximum Measured Residues Pollen (mg/kg)	Maximum Predicted Nectar Residues (mg/kg) After Application of 1 kg/ha	Maximum Predicted Pollen Residues (mg/kg) After Application of 1 kg/ha
Chlorantraniliprole	60	0.033	2.60	0.55	43.3

It is difficult to draw any firm conclusions based on these limited data. For instance, there is not a linear relationship between application rate and measured concentration in pollen and nectar across the different compounds. Therefore, the predicted concentrations after applications of 1 kg/ha (*i.e.*, PEDc's) may be greatly exaggerated for some compounds. It is likely that the variation in residue levels seen between these studies (Dinter *et al.*, Wallner, and Choudhary and Sharma) is likely a result of different factors such as sampling, extraction methods, fate properties of the different compounds, or product formulation.

Formatted: Font: Italic

Formatted: Font color: Red

2708 Although limited published data are available for maximum residue levels in nectar and
 2709 pollen after controlled applications of foliar products, there is likely to be a significant
 2710 amount of data that have been developed by pesticide manufacturers for individual products.
 2711 Therefore, the participants of the Workshop proposed that nectar and pollen residue data from
 2712 semi-field exposure studies conducted according to EPPO guidelines be compiled and
 2713 analyzed. These data should represent maximum residues in bee food items in a bee-
 2714 attractive crop, and developing models around these data would likely provide realistic,
 2715 worst-case predicted residues for a screening-level risk assessment.

2716
 2717 Once these data are compiled, a conservative estimate for residues on/in pollen and nectar
 2718 (*e.g.*, 90th percentile RUDs) can be used to calculate TER or RQ values. These screening-
 2719 level predicted values would represent a conservative estimate of dietary exposure for honey
 2720 bees from foliar application of pesticide products. For a dietary risk assessment, the
 2721 predicted concentration of residues in food items can be directly compared with the results
 2722 from dietary toxicity studies with adult bees and bee larvae, if the results from the studies are
 2723 expressed as exposure concentrations (*i.e.*, LC₅₀, NOEC). However, if the toxicity results are
 2724 expressed as a dose (*i.e.*, LD₅₀ in µg/bee), the predicted dose can be calculated based on
 2725 predicted concentrations on food items and consumption rates by different castes of bees.
 2726 Honey bee consumption data, based on complete life-stages, have been reported by Rortais *et*
 2727 *al.* (2005), and are summarized below.

2728
 2729 Nectar foragers: 224 – 898.8 mg sugar
 2730 Pollen foragers: 72.8 – 109.2 mg sugar
 2731 Nurse bees: 65 mg pollen
 2732 Worker larvae: 59.4 mg sugar + 5.4 mg pollen
 2733 Drone larvae: 98.2 mg sugar

2734
 2735 The following daily consumption rates for the different honey bee casts were calculated by
 2736 Thompson (2007):

2737
 2738 Nectar foragers: 32 – 128.4 mg sugar/bee/day
 2739 Pollen foragers: 10.4 – 15.6 mg sugar/bee/day
 2740 Nurse bees: 6.5 mg pollen/bee/day
 2741 Worker larvae: 11.9 mg sugar + 1.1 mg pollen/bee/day
 2742 Drone larvae: 15.1 mg sugar/bee/day

2743
2744 For dietary exposure estimates, it will be important to choose the appropriate consumption
2745 rate with respect to life stage, *i.e.*, the daily consumption rate should be compared with acute
2746 oral toxicity data to estimate acute risks, while life-stage consumption data should be
2747 compared with chronic toxicity data to estimate chronic risk.

2748
2749

2750 **Predicted Exposure for Soil and Seed Treatment Systemic Compounds**

2751

2752 For soil-applied or seed treatment systemic products, the current ICPBR proposal
2753 recommends using a default maximum exposure value of **1 mg/kg for pollen and nectar**,
2754 which is based on analysis of existing residue data (Alix *et al.*, 2009a). Currently, the
2755 number of standardized exposure studies evaluating residues in pollen and nectar for systemic
2756 pesticides is limited to a few compounds for the same class of chemistry (*i.e.*, neonicotinoids)
2757 (Alix *et al.*, 2009b). Therefore, there may not be enough data to develop a predictive
2758 exposure model applicable to all soil-applied or seed treatment systemic compounds. In the
2759 case of systemic compounds, it appears that residues in pollen and nectar are not only
2760 influenced by the physical and chemical properties of the compound (*e.g.*, K_{oc} , soil DT_{50} , K_d ,
2761 pollen and nectar uptake and dissipation), but also by soil properties, crop, weather, and
2762 application timing versus time of bloom. Therefore, as pollen and nectar residue data for
2763 other classes of systemic compounds are developed, the additional variables should be
2764 considered. As more residue data are developed for systemic compounds (both neonicotinic
2765 and other classes), the concept of developing a predictive screening-level exposure model
2766 should be explored further. In the interim, the default value of 1 mg/kg is recommended as
2767 the point estimate for exposure in Tier 1 risk assessment for dietary exposure to systemic
2768 compounds, as it represents a current worst-case estimate of residues in matrices that are
2769 consumed by bees (*i.e.*, pollen and nectar). However, as more data are developed for
2770 systemic compounds, the value of 1 mg/kg should be re-evaluated to ensure that is
2771 sufficiently conservative for use in a screening-level risk assessment.

Formatted: Font: Not Bold

2772
2773

2774 **Predicted Exposure for Tree-Injected Compounds**

2775

2776 Certain insecticides can be directly injected into tree trunks for control of wood boring
2777 insects. The chemical enters the xylem and is systemically transported to all parts of the tree
2778 including nectar (if produced) and pollen, and potentially propolis, which is not consumed,
2779 but is used by bees in the construction and maintenance of nests and hives. There is a
2780 scarcity of data on residues of pesticides resulting from tree-injections. Until more data are
2781 developed or collected, it is unclear if the residue value of 1 mg/kg, as proposed by ICPBR
2782 for soil and seed treatments, is appropriate as a maximum default residue for a screening level
2783 risk assessment for tree injection.
2784

Formatted: Font: Not Bold

2785 **Measuring Pesticides in Matrices Relevant for Assessing Exposure to Bees**

2786
2787 When quantification of pesticide residues in bees or bee food is required to refine an
2788 exposure assessment, it must be determined whether the goal is to assess exposure of adult
2789 forager bees or other members of the hive (queen, nurse bees, drones and larvae). To
2790 determine exposure of foragers from foliar applications, analysis of bees collected from the
2791 sprayed crop can be conducted. For exposure of forager bees from oral sources, samples of
2792 nectar and pollen can be collected by hand from flowers or from foraging bees on the crop.
2793 Bees may be sampled by drawing nectar from the honey stomach and pollen can be removed
2794 from the pollen baskets. Whether it is more time-, and cost-effective to use bees to collect
2795 samples or to do it by hand sampling is dependent on the type of crop flower being sampled.
2796

2797 Where collection of nectar from the target crop is possible by hand, this can be done by
2798 inserting a micro capillary tube or pipette into the nectary and extracting the nectar.
2799 Collection of pollen by hand can be done by shaking flowers or using scissors to remove
2800 anthers followed by separation of the pollen from the anthers either in the field or after
2801 transportation to a laboratory. Flowers from several crops have very little, if any, nectar and
2802 pollen, making hand collection impractical. In these instances, bees can be used to collect the
2803 samples. Obtaining nectar samples using bees can be done by collecting the bees that are
2804 actively foraging on flowers in the crop of interest, (such as by vacuuming, which, in certain
2805 cases may be impractical). Another way to sample bees is by collecting them at the hive
2806 entrance. In either scenario, verification of exposure from the crop of interest should be done
2807 by identifying pollen brought back to the hive or by confining the bees during the exposure
2808 portion of the study using a semi-field study design. To obtain the nectar sample from honey
2809 bees, the honey stomach can be dissected from the bee and contents drained into a vial or be
2810 pierced with a syringe or micropipette and the nectar extracted. Pollen can be obtained from
Pesticide RA for Pollinators 4-13-13

2811 bees collected from flowers or at the hive entrance by removing the pollen from the pollen
2812 baskets. Pollen samples can also be collected in pollen traps attached to the hive entrance. If
2813 either pollen or nectar cannot be efficiently collected in large enough quantities for residue
2814 analysis, whole flower samples could also be analyzed for possible use as a surrogate
2815 (pending further collection and analysis of these data).

2816
2817 For potential exposure to residues in stored pollen, nectar and larval jelly, samples from the
2818 hive can be drawn. Stored pollen can be sampled by identifying frames where fresh pollen is
2819 being stored and removing this pollen with a spatula from individual cells. Adding an empty
2820 comb can ensure that the pollen and nectar is freshly collected. Nectar can be sampled by
2821 identifying the frame where fresh nectar is being stored, removing the frame from the hive,
2822 and shaking the frame into a large pan to release the nectar. The released nectar can then be
2823 transferred to a vial using a pipette, or pouring if the volume allows. Alternatively, fresh
2824 nectar can be identified and extracted from individual cells using a syringe or pipette and
2825 transferred to a vial. Larval jelly can be identified on the frames and collected either by
2826 extracting it from the cells with a capillary tube or pipette, or by removing the larvae and
2827 scooping out the jelly with a spatula and transferring it to a vial.

2828
2829 All samples collected in the field should be kept on ice until received by the analytical
2830 laboratory. At the laboratory, samples should be stored frozen (-20°C) and protected from
2831 light until analysis. Experience shows that plastic storage containers should be used with
2832 caution because some pesticides can sorb to plastic. Standardized procedures for sampling,
2833 including appropriate storage and transport, should be established in order to avoid
2834 contamination, and provide adequate sample size. Specific, statistically valid plans for sample
2835 size and number also should be established in the study protocol. Dedicated coolers, chain of
2836 custody, records of transport and storage conditions and other appropriate Good Laboratory
2837 Practice procedures should be used and documented to ensure sample integrity. The quantity
2838 of samples needed for analysis of pesticide residues should be determined prior to sampling
2839 and might vary based on limits of detection and limits of quantification for each pesticide in
2840 the individual matrices. Use of spiked samples, to accompany samples collected from the
2841 field, can be used to ensure sample integrity (as well as sample stability). Analytical
2842 methods also need to be properly validated to insure that extraction methods are adequate and
2843 the residues of interest are accurately identified.

2844

At the present time, it is recommended that collection of nectar and pollen directly from the flowers, or collecting and removing pollen and nectar from foraging bees would be the most conservative and most relevant estimates of exposure for bees outside the hive. For larvae, nurse bees, drones and the queen in the hive, sampling freshly deposited nectar and pollen from the combs would be the most conservative dietary exposure estimate, considering additional processing of these materials by bees may result in lower concentrations in other hive food sources. To further refine these estimates, data on the comparative residue levels in flowers, nectar, pollen and hive products (such as stored pollen, nectar, honey, larval jelly, and beebread) can to be generated to determine worst-case oral exposure estimates for either foraging bees or hive bees.



Mircopipetting nectar samples; photo by Mike Beevers



Hand-collecting pollen by removing flower anthers, photo by Mike Beevers

Higher-Tier Studies to Assess Exposure of Pesticides to Bees

Higher-tier study to evaluate contact exposure to honey bees

In the U.S., if a compound is classified as toxic to honey bees by contact exposure (*i.e.*, LD₅₀ < 11 µg/bee), a Tier 2 contact residue study is required. In this study, a bee attractive plant (typically alfalfa) is sprayed with formulated product at the maximum application rate. Groups of worker bees are caged over the treated crop at various time points after application (typically, 0, 4, 8 and 24 hours), to evaluate the bioavailability and persistence of pesticide residue. These data are used to determine the length of time between application and when bees can be safely exposed to a treated crop. From this test, a residual toxicity time is established indicating where the pesticide residue is lethal to 25% of the test population, referred to as the RT₂₅.

Higher-tier exposure studies using honey bee colonies

Since it is not economical to conduct exposure studies in every crop, realistic worst case model crops should be used for assessing exposure of bees under field-relevant use conditions in semi-field and field trials. Choosing a realistic worst case model crop should include the following considerations:

Pesticide RA for Pollinators 4-13-13

- attractive to bees
- provides both nectar and pollen
- provides sufficient flower density and sufficient duration of flowering

EPPO PP 1/170 (OEPP / EPPO, 2001) proposes *Phacelia*, oilseed rape (canola), and mustard. Buckwheat (*Fagopyrum esculentum*) may also be used. Application parameters (*i.e.*, rate, interval, formulation) used in any higher-tier study should be those that are expected to produce the greatest potential exposure that is prescribed by the product label being assessed.

For a worst-case assessment of exposure, semi-field or tunnel studies can be conducted. In these studies, colonies are placed within a tent or mesh tunnel and exposed to the treated crop during or immediately after application. Using a highly bee-attractive crop would simulate a worst-case exposure to residues in pollen and nectar. Because of the controlled nature of semi-field studies for foliar-applied products, the location of the study is not as important as it is for a field study. Therefore, data from semi-field studies may be useful in risk assessments beyond the country in which it was performed, assuming that maximum application rates are assessed. However, in some instances, soil type and weather can influence nectar production. See Chapter 8 for additional discussion on effects measurements through semi-field studies.



Honey bee semi-field study with *Phacelia*. Photo provided by BASF

Studies to evaluate exposure from seed treatments and soil applications of systemic compounds

Regarding seed treatments and soil applications with systemic compounds, specific semi-field or field studies can be designed to measure residues in nectar and pollen in order to refine a screening-level risk assessment for systemic compounds. If the purpose of the study is to measure residue data only, the actual crop of interest should be used. If higher tier studies are conducted with a foliar applied compound and the aim is to concurrently assess residues and potential effects, preferably a crop with the highest application rate and highest attractiveness to bees should be used. If such an effort is undertaken with a systemic compound, then the target crop *per se*, should be considered first as the test crop, utilizing the maximum application rate for that use scenario. If the target crop is not feasible for conduct of either semi-field or field studies, the use of a surrogate crop is recommended but must be scientifically justified (*e.g.*, supported by plant metabolism data, measured residue levels in nectar and pollen). Data on the uptake and decline of pesticide residues in pollen and nectar after systemic pesticide applications to the test crop should be evaluated prior to initiating field testing with honey bees. (Certain residue chemistry information, typically used for human health assessments may be useful in these cases.) In reviews of reports for two compounds submitted to the State of California (Bireley, 2008; Omer, 2008; Papathakis, 2008; Bireley, 2009), leaf residues in treated perennial shrubs and trees treated with imidacloprid were initially low. Residue levels were below the limit of detection for several weeks after application, but increased to levels above 10 ppm over the next several months in some instances, illustrating that expression of residues in pollen and nectar may follow a curve dependent upon numerous variables. Regardless of the timing of application, it is important that the analysis phase of field studies include sampling of the most important bee-relevant matrices (*i.e.*, pollen, nectar) and characterize the level of residues during plant bloom. Consideration may also need to be given to characterizing the persistence of residues over time, *i.e.*, accumulation from one year to the next (depending upon environmental fate properties).

Field treatments for honey bee colonies, spiked sucrose and spiked pollen

For evaluating the distribution of a pesticide throughout a hive, sucrose, pollen or protein (pollen substitute) supplements spiked with the proposed test compound (*e.g.*, pesticide active

ingredient) should be considered as a potential method of exposure in semi-field and field tests. Spiked pollen, protein (pollen substitute), or sucrose can also be utilized in laboratory and field tests to ensure and accurately quantify exposure to the hive.

When spiked sucrose solution is used as the route of exposure for three or more days, a protein supplement is recommended to ensure effects observed are due to treatments and not insufficient nutrition. If exposure to the compound is expected to be through pollen collection and feeding, spiked protein can be fed to the test bees. An alternative is to collect and homogenize pollen from a pollen trap, spike the pollen samples with the compound being evaluated, and pressing the spiked pollen into empty combs. However, for some lipophilic compounds, pressing the pollen into a comb could end up extracting the compound if it partitions to the wax. An alternative would be to prepare pollen cake on which the bees can forage. Also, certain pollens should be avoided because they may contain contaminants such as flavonoids that are toxic to bees. In addition, the pollen used should be pesticide free. Finally, the protein content of some pollen, and differences in preference may reduce feeding. In some cases, researchers have used spiked protein supplements. One recommendation is to provide a 500 gram protein supplement to the colony each week during a brood cycle (*e.g.*, 21 days). Palatability or toxicity of the test compound may result in the need to alter the size of the supplement. A pollen trap may be used to significantly reduce the quantity of pollen that foraging bees bring into the hive (field studies), thus, encouraging consumption of the spiked protein supplement. A local sucrose feeder may also be used to reduce long distance foraging.

An advantage of using spiked protein supplements is that treated crops are not required and the field size where hives are placed is not relevant as long as there is adequate forage for the number of hives. In these studies, pollen traps can be used to reduce any extraneous pollen from entering the hive. Spiked protein supplements ensure that the hives are exposed to the test substance. Since the protein supplement is not specific to a particular crop, exposure is applicable to any plant where pollen is a food source.

As discussed above, appropriate steps should be taken to validate the proper handling of residue samples during collection, handling, shipping, and processing. Validated results indicate that the field handling is appropriate and that the results from the field samples accurately represent actual field residues. See Chapter 8 for more discussion on considerations and conduct of field studies for measuring potential effects.

Health of honey bee colonies can influence exposure

In typically managed colonies, pests and pathogens are present in amounts not necessarily found in the simulated scenarios of laboratory-based or field studies. Honey bee pathogens such as *Nosema* (Fries *et al.*, 2006; Chauzat *et al.* 2007) and various bee viruses (Chen *et al.*, 2006; Ribière *et al.* 2007; Chen *et al.*, 2011) are commonly present in managed honey bee colonies. When colonies are subjected to changes caused by pesticide exposure, the pathogen loads can change in honey bees (Alaux *et al.*; 2010, Pettis *et. al.*; 2010), and in turn, influence biological and behavioral traits of honey bees. The behavior of diseased honey bees can be modified. For example, diseased honey bees may forage earlier in their life cycle (Ribière *et al.*; 2008), or may be less vigorous foragers, leading to less overall foraging activity and consequently a lower pesticide exposure. Conversely, [REDACTED] has been observed that the strength of [REDACTED] health is likely most affected by [REDACTED] [REDACTED] [REDACTED] Colonies used for testing should be healthy colonies, with minimal levels of pests and pathogens, as these can influence foraging behavior.


Higher Tier studies with non-*Apis* bee species

If a screening-level risk assessment does not indicate a presumption of low risk to non-*Apis* bee species, exposure can be evaluated using higher-tier studies. In many cases, exposure assessments for honey bee workers may address potential exposure for non-*Apis* bees. However, in some cases, non-*Apis* bees face unique exposure pathways not addressed by exposure assessments for honey bees (see section of this chapter on Potential Routes of Exposure for Non-*Apis* Bees Species) and consequently, exposure estimates for non-*Apis* bees should be pursued through higher tier studies. Higher tier studies may be pursued solely for exposure information but given their complexity and cost, they likely will be undertaken for information on both exposure and effects. A brief discussion regarding alfalfa leaf-cutter bees and mason bees provides an example.

Alfalfa Leaf-Cutter Bees: contamination of nesting materials

Alfalfa leaf-cutter bees (*Megachile rotundata*) and other species of *Megachile* and *Osmia* will collect leaf pieces from a variety of plants to either wrap or build partitions between their brood cells. Common examples of plants used by these non-*Apis* species include species such as rose (*Rosa spp.*), snow berry (*Symphoricarpos albus*), bindweed (*Convolvulus arvensis*), buckwheat (*Fagopyrum esculentum*), honeysuckle (*Lonicera spp.*), wild grape (*Vitis vinifera*), or wild senna (*Senna hebecarpa*) (---go to ref. and find scientific names) (Mader *et al.*, 2010). Alfalfa leaf-cutter bees deployed for alfalfa pollination also use material collected from the fields in which they are pollinating and/or foraging. Whether the bees use the target crop or surrounding non-cropped area, there is a potential for exposure from direct application to the crop or drift to adjacent plants.

In the case of the alfalfa leaf-cutter bee used for alfalfa pollination, it is critical to understand the level of exposure from contaminated leaf pieces and, ultimately, the toxicity of this exposure. See also Chapter 8 on Laboratory Testing Approaches for a discussion laboratory-based effects studies using treated foliage and see also Chapter 9 for a discussion on considerations with respect to effects information from either semi-field or field studies. One possible approach would be to use a modification of U.S. EPA's guidelines for assessing the toxicity of pesticides on foliage, where alfalfa is sprayed and then brought into a laboratory at various post-application time points, and allowing bees to forage on the foliage. Another approach would be to use a semi-field or field study design as described below.



Mason bee. Photo by Mace Vaughan

Formatted: Not Highlight
Formatted: Font: Italic, Not Highlight
Formatted: Not Highlight
Formatted: Font: (Default) Times New Roman, Italic, Font color: Auto
Formatted: Not Highlight
Formatted: Font: (Default) Times New Roman, Italic, Font color: Auto
Formatted: Not Highlight
Formatted: Font: (Default) Times New Roman, Italic, Font color: Auto
Formatted: Not Highlight
Formatted: Font: Italic, Not Highlight
Formatted: Not Highlight
Formatted: Font: (Default) Times New Roman, Italic, Font color: Auto
Formatted: Font: Not Italic
Formatted: Not Highlight
Formatted: Font: Italic
Formatted: Not Highlight

Semi-field studies

The following steps relate to assessing potential levels of exposure from contaminated mud, such as with mason bees (*e.g. Osmia cornifrons*, *O. cornuta*, *O. lignaria*, or *O. rufa*) that collect mud to build partitions between their brood cells.

1. Plant enclosed shelter (6 m by 2.5 m or larger) with Phacelia (*Phacelia tanacetifolia*), sweetclover (*Melilotus* spp.), or other favored forage plant. (Note: In this case, it is also possible to consider the use of artificial nectar or pollen feeder).

2. Deploy incubated *Osmia* spp. cocoons as loose cells or natal tubes in the enclosure at least 15 days prior to pesticide application (see Bosch and Kemp, 2001; Mader *et al.* 2010 for management advice).

Provided the bees have undergone appropriate diapause (generally 100 to 200 days at 1.7 to 4.4 °C.), bees will begin emerging 5 to 10 of days after initiating incubation at temperatures of at least 21°C. More rapid emergence can be stimulated by incubating cocoons at 29 °C, until all bees have emerged.

Note that male emergence precedes female emergence, often by several days, and nesting typically will not begin until one to two days after mating (which usually occurs on the day of female emergence).

3. Provide a source of wet mud with high clay content in a 1 m wide shallow pan or tray. Water this tray on a daily basis from below in order not to wash pesticide from surface. Ensure that the moisture level is not excessive leading to drowning.
4. Use observation tunnel-nests for the bees (*i.e.*, boards with grooves routed into one side (8 mm for *O. cornuta*, 7.5 mm for *O. lignaria*, 6 mm for *O. cornifrons*), covered by a layer of clear acetate and sandwiched with second piece of wood to create a dark tunnel that can be opened to allow for monitoring.

5. Open observation tunnel nest and note completed cells.

6. Temporarily close nest tunnels and apply pesticide at levels of interest to mud.

7. Note new cells created.

8. Open nests and pull out mud partitions divided cells provisioned post-application to measure:
- Pesticide residue in pollen-nectar stores (pollen ball), and
 - Pesticide residue in mud partitions.
9. Remove exposed cells at 15, 20, and 25+ days to assess the movement of the pesticide into bee bread, larval mortality, etc. Depending on the species, full development from egg hatching to adult emergence is completed between 60 and 125 days at 28 to 17 °C. Higher temperatures will result in faster development, but should not exceed 28 °C.

Field or semi-field studies

- Deploy leaf-cutter bees in closable/sealable shelters in an alfalfa field 10 days prior to pesticide application (see Chapter 8 for further discussion on proper incubation timing).

Observation tunnel-nests for the bees can be constructed to facilitate monitoring by boring a 0.6 cm (¼-inch) holes or grooves into one side of a wood plank, and covering the holes/grooves with clear acetate. The acetate on such nests should be covered with a removable opaque cover to increase nest attractiveness. The opaque cover can be removed temporarily in order to make notations on the acetate. See also Abbott *et al.* (2008).
- During the active nesting period, close the shelter at night to prevent foraging in the green house, cage or field until the following day. With the nest shelter closed, carefully enter it and note the constructed cells (pre-treatment) in the observation tunnels. With the shelter closed, pesticides can be applied to the field adjacent (at least 200 m radius) around the shelter.
- After an appropriate time has elapsed (depending upon study goals and active ingredient being used), open the shelter to allow bees to forage, build, and provision the cells.

4. Note new cells created in the observation nests.
5. Newly constructed cells can be monitored for development: Eggs will hatch in ca. 15 days at 15.6 °C down to 1-to-2 days at 35 °C. Prior to egg hatching, cells may also be dissected to separate leaf pieces from cell contents (beebread and egg) to assess:
- Pesticide residues in the pollen-nectar mixture (pollen ball), and
 - Pesticide residues on leaf pieces.
6. At 15, 20, and 25+ days, cells can be sampled for presence of pesticide residues in the pollen ball, monitored for larval mortality, and other parameters. Full development from egg hatching to adult emergence takes 35 days at 15.6 °C, but only 11 days at 35 °C.

Using non-*Apis* bees to measure pesticide contamination of pollen and nectar

Using the techniques described here, pollen balls may be removed from the cells of solitary tunnel nesting bees (*e.g. Osmia* spp. or *Megachile rotundata*) placed in shelters deployed in fields or orchards treated with pesticides, including systemic pesticides applied as drench or trunk injection. If sufficient forage is available, then these managed non-*Apis* solitary bees typically forage in the area immediately surrounding their nest (40 – 60 m), thereby helping to ensure that the study organism is coming in contact with the treated plants in well-designed field studies. These bees can also be used readily in semi-field studies as they forage readily in enclosures when provided with adequate forage and nesting material (Bohart and Pedersen, 1983; Abel *et al.*, 2003).

Female foragers of *Osmia* or *Megachile* spp. may also be netted in front of their nest shelters. If they are returning with pollen, it may be gently scraped or brushed from their abdomens or removed by holding the bee with entomological forceps and applying a vibrating tuning fork to the forceps. Note that, unlike honey bees, members of the family Megachilidae, which includes both *Osmia* and *Megachile*, carry pollen in long hairs (scopae) on the underside of their abdomens. This pollen is carried dry, unlike honey bees that carry wet pollen with nectar or honey in order to pack it onto their pollen baskets (corbiculae; Vaissière and

Vinson, 1994). It is unknown if wetted pollen may interact with pesticides in the field differently compared to dry pollen.

With regards to nectar contamination, the crop portion of the alimentary track of non-*Apis* bees can be extracted just as easily as with honey bees. Clearly the amount of nectar that can be recovered will be a bit less in smaller species such as mason bees or leaf-cutter bees, but the procedure is the same as with honey bees. It may be advantageous to anesthetize the foragers prior to squeezing their abdomen gently so as to avoid being stung repeatedly at the same spot though the smaller non-*Apis* species are usually less prone to sting and agile at doing so than honey bees (but this is not true with bumble bee workers).

Field techniques using non-*Apis* bees are presented in greater detail in Chapter 9 on semi-field and field approaches to testing pesticide risk to bees.

Non-*Apis* (solitary species) as an exposure surrogate for *Apis* bees

In certain respects, non-*Apis* bees may serve as a useful surrogate for honey bees in exposure studies. Solitary bees, such as leaf-cutter (*Megachile* spp.) and mason (*Osmia* spp.) bees, typically forage over a much smaller area than honey bees. For example, solitary bees typically forage within a few hundred meters of a nest, rather than two miles (several kilometers) as is common with honey bees. Because of this smaller foraging area, it is possible that a field experiment may provide a more accurate picture of potential exposure, even chronic exposure. Where a honey bee colony will forage over potentially 500 hectares or more, if sufficient forage is present, solitary bees will visit flowers as close to the nests as possible and thus be exposed consistently to local field applications and residues.

Summary and Recommendations

Participants of the Workshop agreed that the most significant route of exposure to bees from foliar applied pesticides is from both contact and oral exposure (of foraging adults, hive adults and larvae) to contaminated pollen, nectar and processed food (e.g., beebread, honey, and larval jelly). For systemic compounds (applied as a seed treatment, soil drench, or trunk

injection), the most significant route of exposure is through oral ingestion of residues in pollen, nectar and processed food (e.g., beebread or larval jelly). Other potential routes of exposure include contaminated drinking water and hive material (e.g., contaminated comb wax) and inhalation. For non-*Apis* bee species, unique potential exposure routes include contaminated soil (for solitary ground nesting species and tunnel nesting species that use mud to build cell partitions), contact with sprayed leaves and nesting material that may also be contaminated. Workshop participants agreed that when assessing the major routes of exposure, methods should be conservative enough to account for various potential exposure routes. Unique potential exposure routes, for systemic pesticides, include contaminated abraded dust from seed treatment scenarios, consumption of contaminated aphid honeydew, or possible consumption of contaminated guttation water.

Exposure Estimates

For contact exposure estimates for foliar-applied products, published insect data from direct application exposure studies with honey bees (Koch and Weißer, 1997) can be used to estimate the Predicted Environmental Dose through contact exposure of foraging honey bees (PEDc). Using this data, a worst-case estimate of 1.79 µg/bee is predicted after an application of 1 kg/ha directly to foraging bees.

For non-*Apis* species, Workshop participants recommended using the data for leaf-dwelling and soil-dwelling arthropods from the data developed by Schabacker *et al.* (2005) to address exposure to leaf-dwelling and soil-nesting non-*Apis* bee species, respectively.

For predicting oral exposure to bees for products applied as spray solutions during crop bloom, there is a limited amount of public data available to make an exposure estimate based on predicted concentrations in pollen and nectar. There is however, a larger set of proprietary data that may be available from semi-field studies conducted by pesticide registrants. Therefore, Workshop participants discussed the possibility and value of an industry coalition to compile pollen and nectar residue data from both published and proprietary studies to develop a nomogram that can be used to predict concentrations in pollen and nectar based on field application rates. Preferably, a nomogram such as this would contain both mean and 90th percentile predictions.

Pollen and nectar residue levels, reported as mg/kg, can be compared to results from oral exposure toxicity studies with bees if the results of the studies are based on concentrations in Pesticide RA for Pollinators 4-13-13

diet, *i.e.*, LC₅₀, or as a NOEC (also expressed as mg/kg bee diet). However, if the results from oral exposure toxicity studies are expressed as a median lethal dose (*e.g.*, LD₅₀ in µg/bee), then the predicted exposure dose (in µg/bee) can be calculated based on the concentrations in pollen and nectar, and reported as (adjusted per) consumption rates for different castes of honey bees.

For systemic compounds applied as seed treatment coating, soil applications, or trunk injections, the most significant routes of exposure for adult and larval bees will be through ingestion of pollen, nectar and processed pollen (*i.e.*, beebread or larval jelly) and processed nectar (*i.e.*, honey). Recognizing the limited field data available to develop exposure models, participants of the Workshop considered the proposal by the International Commission for Plant-Bee Relationships (ICP-BR) for a default value of **1 mg/kg in pollen and nectar** (Alix and Lewis, 2010), as a potentially appropriate point estimate of exposure for a screening-level assessment for seed treatment and soil applications. Once again, if the results from oral exposure toxicity studies are expressed as a dose (*e.g.*, µg/bee), then the predicted dose can be calculated based on the concentrations in pollen and nectar coupled with reported consumption rates from different castes of honey bees.

Higher-Tier Studies to Refine Exposure Assessments

When a screening level assessment indicates potential risks, higher-tier studies with applications to bee attractive plant materials are an option to refine exposure estimates for a specific product. A tier 2 [contact] toxicity study of residues on foliage with honey bees may be conducted. In this laboratory study a bee-attractive plant (*e.g.*, alfalfa) is sprayed with the formulated product and the bioavailability and persistence of toxic residues are evaluated at various exposure time-points after application. The results can be used to determine the length of time between application and when bees can be safely exposed to residues on leaves or flowers of a treated crop (*i.e.*, residual toxicity time, referred to as RT).

Refining Oral Exposure of Honey Bees to Foliar-Applied Compounds

Tier 3 semi-field or tunnel tests are recommended to refine the oral exposure assessment for honey bee colonies to both systemic and non-systemic products sprayed on foliage. As discussed in the Hazard –Field section, Workshop participants recommend that semi-field

3249 studies should use a bee-attractive crop such as *Phacelia*, oilseed rape (*Brassic anapus*),
 3250 mustard (*Sinapis hirta*) or buckwheat (family Polygonaceae). Use of these study/crop
 3251 scenarios would provide a better opportunity to ensure exposure because the bees would only
 3252 have the treated crop to forage on for a specified duration. Therefore, the results from a
 3253 semi-field test would provide data for a realistic, worst-case prediction of exposure of limited
 3254 duration resulting from labeled use conditions. In these studies, pollen, nectar, beebread,
 3255 honey and if desired, larval jelly can be collected and analyzed for residue levels. Unlike
 3256 honey bee larvae that consume mostly processed pollen and nectar in the form of brood food
 3257 and/or larval jelly, many non-*Apis* bee larvae consume only raw pollen. As such, in studies
 3258 using non-*Apis* bees, oral exposure measurements can be obtained directly via the pollen.
 3259

3260 **Refining Oral Exposure of Honey Bees to Soil Applied and Seed Treatment Systemic** 3261 **Compounds** 3262

3263 Once again, a semi-field study is recommended for assessing exposure of honey bee colonies
 3264 to systemic pesticides delivered via seed dressings or through soil treatments. For studies
 3265 with systemic compounds, the actual crop being assessed should be used, (or potential worst
 3266 case when multiple crops are being considered) since there may be different rates of uptake,
 3267 distribution and metabolism of a compound in different plant species (*i.e.*, between an
 3268 attractive surrogate crop such as *Phacelia* and a commercial target crop such as melon).
 3269 Residue analysis should be timed to coincide with the highest nectar/pollen residues expected
 3270 in the treated crop based on application timing as well as peak residues during bloom.
 3271 Residues of systemic pesticides in leaves of trees may be highest several months after soil
 3272 application, indicating that individual characteristics of the treated crop should be considered
 3273 in assessing the residues in pollen and nectar. Similar to semi-field studies conducted with
 3274 foliar spray products, residues in pollen, nectar, beebread, honey and if desired, larval jelly
 3275 can be collected and analyzed for residues. The measured residue levels can be used in a
 3276 refined risk assessment.
 3277

3278 **Refining Exposure of Non-*Apis* Bees** 3279

3280 If a screening-level risk assessment indicates potential risk, exposure as well as the effect of a
 3281 compound to non-*Apis* bee species can be refined using field or semi-field study designs. For
 3282 assessing exposure to pesticides in pollen and nectar, solitary nesting bees such as blue
 3283 orchard bees (*Osmia lignaria*) or alfalfa leafcutter bees (*Megachilero tundata*), can be used.

3284 However, nectar and pollen residue data gained from honey bee trials can also be used to
 3285 assess exposure for non-*Apis* bees. Similar to studies with honey bees, for foliar-applied
 3286 pesticides, studies with non-*Apis* bees should be conducted using a bee-attractive crop such as
 3287 *Phacelia* or sweetclover. Pollen and nectar can be collected directly from the foraging bees.
 3288 Semi-field or field studies can also be conducted with *Megachile* to evaluate potential
 3289 [dermal and/or oral] exposure via contaminated nesting material. For assessing exposure to
 3290 systemic pesticides used as a seed treatment, or applied as a soil treatment or trunk injection,
 3291 a field study design can be used with these non-*Apis* species to evaluate worst-case exposure
 3292 because of the limited foraging range of these species. Potential exposure via soil can also be
 3293 evaluated using these species.

3294
 3295 *van der Steen 1994, Thompson and Hunt 1999, Malone et al. 2000) (include in references)*

3296 References

- 3297
- 3298 Abel CA, Wilson RL, Luhman RL. 2003. Pollinating efficacy of *Osmia cornifrons* and *Osmia lignaria* subsp.
 3299 *lignaria* (Hymenoptera: megachilidae) on three Brassicaceae species grown under field cages. Journal of
 3300 Entomological Science. 38: 545-552.
- 3301
- 3302 Abbott, VA, J.L., Nadeau, H.A. Higo, and M.L. Winston. 2008. Lethal and sublethal effects of imidacloprid on
 3303 *Osmia lignaria* and clothianidin on *Megachile rotundata* (Hymenoptera: Megachilidae). Journal of Economic
 3304 Entomology. 101(3): 784-796.
- 3305
- 3306 Alix A, Chauzat MP, Duchard S, Lewis G, Maus C, Miles MJ, Pilling E, Thompson HM, Willner K. 2009a.
 3307 Guidance for the assessment of risks to bees from the use of plant protection products applied as seed coating
 3308 and soil applications – conclusions of the ICPBR dedicated working group. Julius-Kühn Archive 423: 15- 26.
- 3309
- 3310 Alix A, Chauzat MP, Duchard S, Lewis G, Maus C, Miles MJ, Pilling E, Thompson HM, Willner K. 2009b.
 3311 Environmental risk assessment scheme for plant protection products – conclusions of the ICPBR dedicated
 3312 working group. Julius-Kühn Archive 423: 15- 26.
- 3313
- 3314 Alix A., Lewis G. 2010. Guidance for the assessment of risks to bees from the use of plant protection products
 3315 under the framework of Council Directive 91/414 and Regulation 1107/2009. Bulletin OEPP/EPPO Bulletin,
 3316 40: 196-203
- 3317
- 3318 Alix A, Vergnet C, Mercier T. 2009c. Risks to bees from dusts emitted at sowing of coated seeds: concerns, risk
 3319 assessment and risk management. Julius-Kühn Archive 423: 131- 132
- 3320
- 3321 Alaux C, Brunet J, Dussaubat C, Mondet F, Tchamitchan S, Cousin M, Brillard J, Baldy A, Belzunces LP, Le
 3322 Conte Y. 2010. Interactions between *Nosema* microspores and a neonicotinoid weaken honeybees (*Apis*
 3323 *mellifera*). Environmental Microbiology. 12(3): 774-782.
- 3324
- 3325 Atkins EL, Kellum D, Atkins KW. 1981. Reducing Pesticide Hazards to Honey Bees: Mortality prediction
 3326 techniques and integrated management strategies. Univ. Calif., Div. Agric. Sci. Leaflet 2883.
- 3327
- 3328 Anonymous. 2001. OEPP/EPPO: EPPO Standards PP1/170(3). Test methods for evaluating the side effects of
 3329 plant protection products on honeybees. Bulletin OEPP/EPPO Bulletin 31: 323-330.
- 3330
- 3331 Babendreier D, Karlberger N, Romes J, Fluri P, Bigler F. 2004. Pollen consumption in honey bee larvae: a step
 3332 forward in risk assessment of transgenic plants. Apidologie. 35: 293-300.
- 3333

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

- 3334 Beekman M, Ratnieks FLW. 2000. Long-range foraging by the honey-bee, *Apis mellifera* L. Functional
3335 Ecology. 14: 490-496.
3336
- 3337 Bireley R. 2008. Department of pesticide Regulation, Pesticide Evaluation Report Fish and Wildlife Review for
3338 Thiamethoxam, Sacramento, CA, 95814.
3339
- 3340 Bireley R. 2009. Department of pesticide Regulation, Pesticide Evaluation Report Fish and Wildlife Review for
3341 Thiamethoxam, Sacramento, CA, 95814.
3342
- 3343 Bohart GE, Pedersen MW. 1963. The alfalfa leaf-cutting bee *Megachile rotundata* for pollination of alfalfa in
3344 cages. Crop Science. 3: 183-184.
3345
- 3346 Bosch J, Kemp W. 2001. How to Manage the Blue Orchard Bee as an Orchard Pollinator. Sustainable
3347 Agriculture Network. Beltsville, MD. 88 pp.
3348
- 3349 Brunet J, Stewart C. 2010. Impact of bee species and plant density on alfalfa pollination and potential for gene
3350 flow. Psyche. 2010. doi:10.1155/2010/201858.
3351
- 3352 Brewer LW, Sullivan JP, Atkins JM, Kamiri LK, Mihaich EM. 1997. Measured pesticide residues on insects in
3353 relation standard EPA estimates. Presented at the 18th Annual Meeting of the Society of Environmental
3354 Toxicology and Chemistry, San Francisco.
3355
- 3356 Cane JH. 1991. Soils of ground-nesting bees (Hymenoptera: Apoidea): texture, moisture, cell depth and climate.
3357 Journal of the Kansas Entomological Society. 64: 406-413.
3358
- 3359 Cane JH. 2003. Annual displacement of soil in nest tumuli of alkali bees (*Nomia melanderi*) (Hymenoptera:
3360 Apiformes: Halictidae) across an agricultural landscape. Journal of the Kansas Entomological Society. 76: 172-
3361 176.
3362
- 3363 Cane J. 2008. Bees (Hymenoptera: Apoidea: Apiformes). Encyclopedia of Entomology. Springer Verlag. 2: 419-
3364 434.
3365
- 3366 Cane JH, Griswold T, Parker FD. 2007. Substrates and materials used for nesting by North American *Osmia*
3367 bees (Hymenoptera: Apiformes: Megachilidae). Annals of the Entomological Society of America. 100: 350-
3368 358.
3369
- 3370 Cane J, Sipes S. 2006. Characterizing floral specialization among bees: analytical methods and a revised lexicon
3371 for oligolecty. p. 99-122 in Waser NM, Ollerton J (eds.) Plant-pollinator interactions: from specialization to
3372 generalization. University of Chicago Press.
3373
- 3374 Chauzat MP, Faucon JP, Martel AC, Lachaize J, Cougoule N. 2006. A survey of pesticide residues in pollen
3375 loads collected by honey bees in France. Journal of Economical Entomology. 99: 253-262.
3376
- 3377 Chauzat MP, Faucon JP. 2007. Pesticide residues in beeswax samples collected from honey bee colonies (*Apis*
3378 *mellifera*) in France. Pest Management Science. 63: 1100-1106.
3379
- 3380 Chauzat MP, Higes M, Martín-Hernández, Aranzazu Meana R, Nicolas Cougoule N, Faucon, JP. 2007.
3381 Presence of *Nosema ceranae* in French honey bee colonies. Journal of Apicultural Research 46: 127-128.
3382
- 3383 Chauzat MP, Martel AC, Cougoule N, Porta P, Lachaize J, Zeggane S, Aubert M, Carpentier P, Faucon JP.
3384 2010. An assessment of honeybee colony matrices, *Apis mellifera* (Hymenoptera: Aphidae) to monitor pesticide
3385 presence in continental France. Environmental Toxicology and Chemistry. 2011: 30(1): 103-111.
3386
- 3387 Chen YP, Pettis JS, Collins A, Feldlauer M. 2007. Prevalence and transmission of honeybee viruses. Applied
3388 Environmental Microbiology. 72: 606-611.
3389
- 3390 Chen YP, Evans JD, Pettis JS. 2011. The presence of chronic bee paralysis virus infection in honey bees (*Apis*
3391 *mellifera* L.) in the USA. Journal of Apicultural Research 50(1): 85-86.
3392
- 3393 Choudhary A, Sharma DC. 2008. Dynamics of pesticide residues in nectar and pollen of mustard (*Brassica*
3394 *juncea* (L.) Czern.) grown in Himachal Pradesh (India). Environmental Monitoring and Assessment. 144: 143-
3395 150.
- Pesticide RA for Pollinators 4-13-13

Formatted: Font: Italic

Formatted: Superscript

Formatted: Font: Italic

3396
3397
3398
3399
3400
3401
3402
3403
3404
3405
3406
3407
3408
3409
3410
3411
3412
3413
3414
3415
3416
3417
3418
3419
3420
3421
3422
3423
3424
3425
3426
3427
3428
3429
3430
3431
3432
3433
3434
3435
3436
3437
3438
3439
3440
3441
3442
3443
3444
3445
3446
3447
3448
3449
3450
3451
3452
3453
3454
3455
3456

Cowles RS, Montgomery ME, Cheah CAS-J. 2006. Activity and residues of imidacloprid applied to soil and tree trunks to control Hemlock woolly adelgid (Hymenoptera: Adelgidae) in forests. *Journal of Economic Entomology*. 99(4): 1258-1267.

Dinter A, Brugger KE, Frost NM, Woodward MD. 2009. Chlorantraniliprole (Rynaxypyr): A novel Dupont™ insecticide with low toxicity and low risk for honey bees (*Apis mellifera*) and bumble bees (*Bombus terrestris*) providing excellent tools for uses in integrated pest management. *Julius-Kühn Archives*. 423: 84-96.

Fernandez da Silva PG, Serrao JE. 2000. Nutritive value and apparent digestibility of bee-collected and bee-stored pollen in stingless bee, *Scaptotrigona postica* Latr (Hymenoptera, Aphidae, Meliponini). *Apidologie*. 31: 39-45.

Fischer DL, Bowers LM. 1997. Summary of field measurements of pesticide concentrations in invertebrate prey of birds. Presented at the 18th Annual Meeting of the Society of Environmental Toxicology and Chemistry, San Francisco.

Fletcher JS, Nellessen JE, Pfeeger TG. 1994. Literature review and evaluation of the EPA food-chain (Kenaga) nomogram, an instrument for measuring pesticide residues on plants. *Environmental Toxicology and Chemistry* 13: 1383-1391.

Forster R, 2009. Bee poisoning caused by insecticidal seed treatment of maize in Germany in 2008, *Julius - Kühn Archive* 423: 126- 131.

Free JB, 1977. The social organization of honey bees. *North American Bee Books*, Hebden Bridge.

Fries I, Martín R, Meana A, García-Palencia P, Higes M. 2006. Natural infections of *Nosema ceranae* in European honeybees. *Journal of Apicultural Research*. 45:230-233.

Gallai N, Salles JM, Settele J, Vaissière BE. 2009. Economic valuation of the vulnerability of world agriculture confronted with pollinator decline. *Ecological Economics*. 68: 810-821.

Gibbs J, Sheffield CS. 2009. Rapid range expansion of the wool-carder bee, *Anthidium manicatum* (Linnaeus) (Hymenoptera: Megachilidae), in North America. *Journal of the Kansas Entomological Society*. 82: 21 -29.

Gilliam M, Prest DB, Lorenz BJ. 1989. Microbiology of pollen and bee bread: taxonomy and enzymology of molds. *Apidologie*. 20: 53-68.

Girolami VM, Greatti M, Di Bernardo A, Tapparo A, Giorio C, Squartini A, Mazzon L, Mazaro M, Mori N. 2009. Translocation of neonicotinoid insecticides from coated seeds to seedling guttation drops: a novel way of intoxication for bees. *Journal of Economic Entomology*. 102(5): 1808-1815.

Goulson D, Stout JC. 2001. Homing ability of the bumblebee, *Bombus terrestris*. *Apidologie*. 32:105-112.

Greenleaf S, Kremen C. 2006a. Wild bees enhance honey bees' pollination of hybrid sunflower. *Proceedings of the National Academy of Sciences USA*. 103(37): 13890-13895.

Greenleaf S, Kremen C. 2006b. Wild bee species increase tomato production and respond differently to surrounding land use in Northern California. *Biological Conservation*. 133: 81-87.

Greenleaf SS, Williams NM, Winfree R, Kremen C. 2007. Bee foraging ranges and their relationship to body size. *Oecologia*. 153: 589-596.

Guerra-Sanz J. 2008. Crop Pollination in Greenhouses. *Bee Pollination in Agricultural Ecosystems*. Oxford Press. New York, NY. 27-47.

Hart A, Thompson H. 2001. Estimating pesticide residues on invertebrates eaten by birds and mammals. Poster presentation at the SETAC 22nd annual meeting, Baltimore, MD.

Haydak MH. 1970. Honey bee nutrition. *Annual Review of Entomology*. 15: 143-156.

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Superscript

3457 Hoeger F, Kenaga E. 1972. Pesticide residues on plants: correlation of representative data as a basis for their
3458 estimation of their magnitude in the environment. Environmental Quality and Safety: Chemistry, Toxicology
3459 and Technology, F Korte, ed, pp 9 – 25, George Thieme Publishers, Stuttgart.

3460

3461 Joachimsmeier I, Heimbach U, Schenke D, Pistorius J. 2010. Residues of different systemic neonicotinoids in
3462 guttation droplets of oil seed rape in a field study. Julius Kühn-Archiv. 428: 468-469.

3463

3464 Javorek SK, Mackenzie KE, Vander Kloet SP. 2002. Comparative Pollination Effectiveness Among Bees
3465 (Hymenoptera: Apoidea) on Lowbush Blueberry (Ericaceae: *Vaccinium angustifolium*). Annals of the
3466 Entomological Society of America. 95: 345-351.

3467

3468 Johansen C, Mayer D. 1990. Pollinator protection: A bee and pesticide handbook. Wicwas. Cheshire, CT.
3469 Kearns CA, Thompson JD. 2001. The Natural History of Bumblebees. A Sourcebook for Investigations.
3470 Boulder: University Press of Colorado. 130pp.

3471

3472 Kim J, Williams N, Kremen C. 2006. Effects of Cultivation and Proximity to Natural Habitat on Ground-nesting
3473 Native Bees in California Sunflower Fields. Journal of the Kansas Entomological Society. 79: 309-320.

3474

3475 Klein AM, Vaissière BE, Cane JH, Steffan-Dewenter I, Cunningham SA, Kremen C, Tscharntke T. 2007.
3476 Importance of pollinators in changing landscapes for worldcrops. Proceedings of the Royal Society B-Biological
3477 Sciences. 274: 303-313.

3478

3479 Koch H, Weißer P. 1997. Exposure of honey bees during pesticide application under field conditions.
3480 Apidologie, 28: 439-447.

3481

3482 Konrad RN, Ferry A, Gatehouse, Babenreier D. 2008. Potential effects of oilseed rape expressing oryzacystatin-
3483 1 (OC-1) and of purified insecticidal proteins on larvae of the solitary bee *Osmia bicornis*. PLoS ONE.
3484 3(7):e2664. doi:10/1371/journal.pone.0002664.

3485

3486 Kremen C, Williams NM, Thorp RW. 2002. Crop pollination from native bees at risk from agricultural
3487 intensification. Proceedings of the National Academy of Sciences. 99: 16812-16816.

3488

3489 Kremen C, Williams NM, Bugg RL, Fay JP, Thorp RW. 2004. The area requirements of an ecosystem service:
3490 crop pollination by native bee communities in California. Ecology Letters. 7: 1109-1119.

3491

3492 Losey JE, Vaughan M. 2006. The economic value of ecological services provided by insects. Biosciences 56:
3493 311-323.

3494

3495 Mader E, Spivak M, Evans E. 2010. Managing alternative pollinators. SARE handbook 11, Univ. Maryland,
3496 College Park. 170 p.
3497 ([HYPERLINK "http://www.sare.org/publications/pollinators/"] pollinators.pdf).

3498

3499 Maeta Y. 1990. Utilization of wild bees. Farming Japan 24(6): 13-22.

3500

3501 Malone L, Burgess E, Stefanovic D, Gatehouse H. 2000. Effects of four protease inhibitors on the survival of
3502 worker bumblebees, *Bombus terrestris* L. Apidologie. 31: 25-38.

3503

3504 Martel AC, Zeggane S, Aurière C, Drajnudel P, Faucon JP, Aubert M. 2007. Acaricide residues in honey and
3505 wax after treatment of honey bee colonies with Apivar[®] and Asuntol[®]. Apidologie. 38: 534-544.

3506

3507 Martel AC, Lair C. 2011. Validation of a highly sensitive method for the determination of neonicotinoid
3508 insecticide residues in honeybees by liquid chromatography with electrospray tandem mass spectrometry.
3509 International Journal of Environmental Analytical Chemistry. In press.

3510

3511 Mason CE. 1986. Progression of knockdown and mortality of honey bees (Hymenoptera: Apidae) sprayed with
3512 insecticides mixed with PennCap-M. Environmental Entomology. 15: 170-176.

3513

3514 Mayer D, Johansen C. 1990. Pollinator Protection: A Bee and Pesticide Handbook. Wicwas Press, Cheshire,
3515 Conn, p. 161.

3516

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Superscript

Formatted: Superscript

3517 Mayer D, Johansen C. 2003. The rise and decline of *Nomia melanderi* (Hymenoptera: Halictidae) as a
3518 commercial pollinator for alfalfa seed. For Nonnative Crops, Whence Pollinators of the Future. Entomological
3519 Society of America. Lanham, MD. 139-149.

3520 McFrederick QS, LeBuhn G. 2006. Are urban parks refuges for bumble bees *Bombus spp.* (Hymenoptera:
3521 Apidae). Biological Conservation. 129: 372-382.

3522 Michener CD. 2007. The Bees of the World. 2nd ed. John Hopkins Univ. Press, Baltimore, Maryland, USA. 913
3523 pp.

3524 Morse RA, Calderone NW. 2000. The value of honeybees as pollinators of US crops in 2000. Bee Culture.
3525 128: 2-15.

3526 Mullin C, Frazier M, Frazier J, Ashcraft S, Simonds R, vanEngelsdorp D, Pettis J. 2010. High levels of
3527 miticides and agrochemicals in North American apiaries: implications for Honey Bee Health. Plos ONE. 5(3):
3528 e9754.

3529 Murphy CM, Breed MD. 2008. Nectar and resin robbing in stingless bees. American Entomologist. 54: 37-44.

3530 National Academy of Sciences. 2006. Status of Pollinators in North America. Committee on the Status of
3531 Pollinators in North America, National Research Council, National Academies Press. ISBN: 0-309-10289-98,
3532 396 pages.

3533 Nikolakis A, Chapple A, Friessleben R, Neumann P, Schad T, Schmuck R, Schnier HF, Schnorbach HJ,
3534 Schöning R, Maus C. 2009. An effective risk management approach to prevent bee damage due to the emission
3535 of abraded seed treatment particles during sowing of seeds treated with bee toxic insecticides. Julius-Kühn
3536 Archive 423: 132- 148.

3537 Omer A. 2008. Department of Pesticide Regulation. Pesticide Evaluation Report Pest and Disease Protection
3538 Review for Imidacloprid. Sacramento, CA. 95814.

3539 Orantes Bernejo FL, Gomez Pajuelo A, Megias Megias M, Fernandez Pinar CT. Pesticide residues in beeswax
3540 and beebread samples collected from honey bee colonies in Spain. Possible implications for colony losses.
3541 Journal of Agricultural Research. 48(1): 246-250.

3542 O'Toole C, Raw A. 1999. Bees of the World, 192 pp. London: Blandford.

3543 Papathakis M. 2008. Department of Pesticide Regulation. Pesticide Evaluation Report Chemistry Review for
3544 Imidacloprid. Sacramento, CA. 95814.

3545 Pasquet RS, Peltier A, Hufford MB, Oudin E, Saulnier J, Paul L, Knudsen JT, Herren HS, Gepts P. 2008. Long
3546 distance pollen flow assessment through evaluation of pollinator foraging range suggests transgene escape
3547 distances. Proceedings of the National Academy of Science USA. 105: 13456-13461.

3548 Peach L, Alston D, Tepedino V. 1994. Bees and bran bait: Is cabaryl bran bait lethal to alfalfa leafcutting bee
3549 (Hymenoptera: Megachilidae) adults or larvae? Journal of Economic Entomology. 87(2): 311-317.

3550 Pistorius J, Bischoff G, Heimbach U, Stähler M. 2009. Bee poisoning incidents in Germany in spring 2008
3551 caused by abrasion of active substance from treated seeds during sowing of maize. Julius-Kühn Archive 423:
3552 118- 126.

3553 Pistorius J, Joachimsmeier I. 2010. Residues of active ingredients from seed treatments in guttation droplets –
3554 relevance to honey bee colonies? Julius Kühn Archiv. 428: 132.

3555 Prescott-Allen C, Prescott-Allen R. 1986. The First Resource: Wild Species in North American Economy. Yale
3556 University Press, New Haven.

3557 Potts SG, Willmer P. 1998. Compact housing in built-up areas: spatial patterning of nesting aggregations of a
3558 ground-nesting bee. Ecological Entomology. 23: 427-432.

Formatted: Font: Italic

Formatted: Superscript

3577 Potts SG, Vulliamy B, Roberts S, O'Toole C, Dafni A, Ne'eman G, Willmer PG. 2005. Role of nesting
3578 resources in organizing diverse bee communities in a Mediterranean landscape. *Ecological Entomology*. 30: 78 -
3579 85.

3580
3581 Pouvreau A. 1984. Biologie et écologie des bourdons. p. 595-630. /in P. Pesson & J. Louveaux (eds.)
3582 Pollinisation et productions végétales. Inst. Nat. Rech. Agron., Paris, F.

3583
3584 Rautmann D, Osteroth HJ, Herbst A, Wehmann HJ, Ganzelmeier H. 1990. Testing of drift reducing maize
3585 sowing machines, *Journal für Kulturpflanzen*. 61(5): 153-160.

3586
3587 Ribière M, Lallemant P, Iscache AL, Schurr F, Celle O, Blanchard P, Oliver V, Faucon JP. 2007. Spread of
3588 infectious chronci bee paralysis virus by honeybee (*Apis mellifera* L.) feces. *Applied Environmental*
3589 *Microbiology*. 73(23): 7711-7716.

3590
3591 Ribière M, Ball B, Aubert M. 2008. Natural history and geographical distribution of honey bee viruses. Pages
3592 15-84 in Aubert M, Ball B, Fries I, Moritz R, Milani N, Bernadinelli I, editors. *Virology and the honey bee*.
3593 European Commission, Bruxelles.

3594
3595 Richards, K.W. 1987. Diversity, density, efficiency and effectiveness of pollinators of cicer milkvetch,
3596 *Astragalus cicer* L. *Canadian Journal of Zoology*. 65: 2168-2176.

3597
3598 Rortais A, Arnold G, Halm MP, Touffet-Briens F. 2005. Modes of exposure of honeybees to systemic
3599 insecticides: estimated amounts of contaminated pollen and nectar consumed by different categories of bees.
3600 *Apidologie* 36: 71-83.

3601
3602 Romaniuk K, Spodniewska A, Kur B. 2003. Residues of chlorinated hydrocarbons in propolis from Warmia
3603 and Muzuria voivodship apiaries. *Medycyna Wet.* 11: 1023-1026.

3604
3605 Roubik DW. 1989. Ecology and natural history of tropical bees. Cambridge Univ. Press, New York. 514 pp.

3606
3607 Sampson BJ, Knight PR, Cane JH, Spiers JM. 2007. Foraging behavior, pollinator effectiveness, and
3608 management potential of the new world squash bees *Peponapis pruinosa* and *Xenoglossa strenua* (Apidae:
3609 Eucerini). *HortScience*. 42: 459.

3610
3611 Sanford JC, Hanneman RE. 1981. The use of bees for the purpose of inter-mating in potato. *American Potato*
3612 *Journal*. 58: 481-485.

3613
3614 Sapir Y, Shmida A, Ne'eman G. 2005. Pollination of *Oncocyclus irises* (Iris: Iridaceae) by night-sheltering male
3615 bees. *Plant Biology*. 7: 417-424.

3616
3617 Schabacker J, Barber I, Ebalng M, Edwards P, Riffel M, Welter K, Pascual J, Wolf C. 2005. Review on initial
3618 residue levels of pesticides in arthropods sampled in field studies. Report from the European Crop protection
3619 Organization.

3620
3621 Schenke D, Joachimsmeier I, Pistorius J, Heimbach U. 2010. Pesticides in guttation droplets following seed
3622 treatment – Preliminary results from greenhouse experiments. Presented at the 20th Annual Meeting of SETAC
3623 Europe, Seville (abstract book ET05P-TU155, p. 259.

3624
3625 Scott-Dupree CD, Conroy L, Harris CR. 2009. Impact of currently used or potentially useful insecticides for
3626 canola agroecosystems on *Bombus impatiens* (Hymenoptera: Apidae), *Megachile rotundata* (Hymenoptera:
3627 Megachilidae), and *Osmia lignaria* (Hymenoptera: Megachilidae). *Journal of Economic Entomology*. 102(1):
3628 177-182.

3629
3630 Seiber JN, McChesney MM. 1987. Measurement and computer model simulation of the volatilization flux of
3631 molinate and methyl parathion from a flooded rice field. Final Report to the California Department of Food and
3632 Agriculture, Contract #6854.

3633
3634 Seiber JN, McChesney MM, Majewski MS. 1991. Volatilization rate and downward contamination from
3635 application of Dacthal herbicide to an onion field. Final Report to the California Department of Food and
3636 Agriculture, Contract #7820.

3637

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Superscript

Shuler RE, Roulston TH, Farris GE. 2005. Farming practices influence wild pollinator populations on squash and pumpkin. *Journal of Economic Entomology*. 98: 790-795.

Stephen WP. 2003. Solitary bees in North American agriculture: A perspective. For Nonnative Crops, Whence Pollinators of the Future. *Entomological Society of America*. Lanham, MD. 41-66.

Suchail S, Guez D, Belzunces LP. 1999. Toxicity of imidacloprid and its metabolites in *Apis mellifera*. Hazards of Pesticides to Bees, INRA, Belzunces LP, Pélissier G, Lewis, GR, eds., Avignon (France), 98: 122-126.

Tapparo, A., D. Marton, C. Giorio, A. Zanella, L. Soldà, M. Marzoni, L. Vivian, and V. Girolami. 2012. Assessment of the Environmental Exposure to Honeybees to Particulate Matter Containing Neonicotinoid Insecticides Coming from Corn Coated Seeds. *Environmental Science and Technology* 46: 2592 – 2599.

Tepedino VJ. 1981. The pollination efficiency of the squash bee (*Peponapis pruinosa*) and the honey bee (*Apis mellifera*) on summer squash (*Cucurbita pepo*). *Journal of the Kansas Entomological Society*. 54: 359-377.

Tew JE. 1997. Protecting Honey Bees from Pesticides. The Ohio State University, Horticulture and Crop Science, Factsheet HYG-2161-97. Wooster, OH.

Thompson HM, Hunt LV. 1999. Extrapolating from honeybees to bumblebees in pesticide risk assessment. *Ecotoxicology*. 8: 147-166.

Thompson HM. 2001. Assessing the exposure and toxicity of pesticides to bumblebees (*Bombus sp.*). *Apidologie*. 32: 305-321.

Thompson HM. 2007. Assessment of the risk posed to honeybees by systemic pesticides. DEFA Research Project PS2322.

Torchio P. 1973. Relative toxicity of insecticides to the honey bee, alkali bee, and alfalfa leafcutting bee (Hymenoptera: Apidae, Halictidae, Megachilidae). *Journal of the Kansas Entomological Society*. 46: 446-453.

Tremolada P, Bernardinelli I, Colombo M, Spreafico M, Vighi M. 2004. Coumaphos distribution in the hive ecosystem: case study for modeling applications. *Ecotoxicology*. 13(6): 589-601.

Vaissière BE, Merritt SJ, Keim DL. 1985. *Melissodes thelypodii* Cockerell (Hymenoptera: Anthophoridae), an effective pollinator of hybrid cotton on the Texas High Plains. (Abst.) p. 398-399. in J.M. Brown (ed.) *Proceedings Beltwide Cotton Production Research Conference*, National Cotton Council. Am., Memphis, TN.

Vaissière BE, Vinson SB. 1994. Pollen morphology and its collection effectiveness by honey bees, *Apis mellifera* L. (Hymenoptera : Apidae), with special reference to upland cotton, *Gossypium hirsutum* L. (Malvaceae). *Grana*. 33: 128-138.

Valdovinos-Núñez GR, Quezada-Euán JJG, Ancona-Xiu P, Moo-Valle H, Carmona A, Sánchez ER. 2009. Comparative Toxicity of Pesticides to Stingless Bees (Hymenoptera: Apidae: Meliponini). *Journal of Economic Entomology*. 102(5): 1737-1742.

Van der Steen JJM, Bortolotti L, Chauzat MP. 2008. Can pesticide acute toxicity for bumblebees be derived from honeybee LD50 values. Hazards of pesticides to bees – 10th International Symposium of the ICP-BR Bee Protection Group, October 8-10, Bucharest (Romania).

Vaughan M, Skinner M. 2009. Using Farm Bill programs for pollinator conservation. United States Department of Agriculture Natural Resources Conservation Service. Pollinator Technical Note No: 78.

Vicens N, Bosch J. 2000. Weather-dependent pollinator activity in an apple orchard, with special reference to *Osmia cornuta* and *Apis mellifera* (Hymenoptera: Megachilidae and Apidae). *Environmental Entomology*. 29: 413-420.

Visscher, PK. & Seeley, TD. 1982. Foraging strategy of honeybee colonies in a temperate deciduous forest. *Ecology* 63: 1790-1801.

Waller G. 1969. Susceptibility of an alfalfa leafcutting bee to residues of insecticides on foliage. *Journal of Economical Entomology*. 62: 189-192.

Pesticide RA for Pollinators 4-13-13

Formatted: Font: Italic

Formatted: Font: 10 pt

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Font: Italic

Formatted: Superscript

3700
3701 Wallner K. 2009. Sprayed and seed dressed pesticides in pollen, nectar and honey of oil seed rape. *Julius-Kühn*
3702 *Archives*. 423: 152-153.
3703
3704 Winfree R, Williams NM, Dushoff J, Kremen C. 2007b. Native bees provide insurance against ongoing honey
3705 bee losses. *Ecology Letters*. 10: 1105-1113.
3706
3707 Winfree R, Williams NM, Gaines H, Ascher JS, Kremen C. 2008. Wild bee pollinators provide the majority of
3708 crop visitation across land-use gradients in New Jersey and Pennsylvania, USA. *Journal of Applied Ecology*.
3709 45(3): 793-802.
3710

3711
3712

3713 **CHAPTER 8 ASSESSING EFFECTS THROUGH LABORATORY TOXICITY TESTING**

3714

3715 Frazier, J., Pflugfelder, J., Aupinel, P., Decourtye, A., Ellis, J., Scott-Dupree, C., Huang, Z., Grimm,
3716 V., Thompson, H., Bachman, P., Dinter, A., and Nocelli, R.C.F.

3717

3718 **Introduction**

3719

3720 Toxicity testing in support of a risk assessment process for determining the potential impacts
3721 of chemicals to pollinator insects and more specifically honey bees has typically involved
3722 both laboratory and field studies. Initially, tests are conducted that are intended to serve as a
3723 screen for whether a chemical represents a potential hazard. These tests are typically
3724 laboratory-based studies conducted on individual bees and are intended to provide
3725 conservative estimates of toxicity based on acute exposures of individual organisms under
3726 highly controlled environmental conditions. Based on the likelihood of exposure and the
3727 degree of sensitivity of the test species in the initial laboratory tests, higher tiered tests may
3728 be required to understand whether the effects observed in laboratory studies conducted on
3729 individual insects extend to the colony/population level under environmentally relevant
3730 exposure conditions.

3731

3732 For reasons discussed earlier, testing to determine the potential effects of chemicals on non-
3733 target organisms has typically relied on the use of surrogate test species. Selection of a
3734 surrogate species must consider the availability of the species and its ability to thrive under
3735 laboratory testing conditions. As such, the husbandry/environmental needs of the test species
3736 must be well known/documented so that tests can be readily conducted and
3737 reproduced/replicated. Ideally, the test species should be a relatively sensitive indicator of
3738 toxicity; however, it is generally recognized that the test species is unlikely be the most

sensitive of all species it is intended to represent. Although the European honey bee (*Apis mellifera*) has been used extensively in testing chemicals for potential effects, it is recognized that its biology is different from non-*Apis* bees (e.g., solitary bees) and other pollinating insects and that these differences may translate into significant differences in how the organism may be exposed/affected. The extent to which data from any surrogate test species are considered biased can only be elucidated through equally rigorous studies using other species. Currently, data for non-*Apis* bee species are limited; however, differences in the sensitivity of *Apis* and non-*Apis* bees may not be as pronounced as differences in potential exposure between honey bees and non-*Apis* bees. As an example, solitary ground-nesting bees of similar sensitivity to honey bees may be more vulnerable to exposure to soil treatments compared to honey bees.

The intent of toxicity tests is to provide measurement endpoints that can be used to assess the adverse effects from exposure to a particular stressor, e.g., pesticides. Endpoints measured at the individual level are intended to provide insight on effects that are likely to impact entire populations/communities. In doing so, measurement endpoints drawn from laboratory-based tests should be readily linked to assessment endpoints (i.e., impaired survival, growth or reproduction) that, in turn, are linked to protection goals. These assessment endpoints relate directly to maintenance of insect pollinators at the population/community level.

To ensure greater consistency in toxicity testing across chemicals, regulatory authorities have established guidelines that outline study design elements that should be considered as well as the nature of data to be collected. To conserve resources (i.e., focusing resources where they are most needed), and limit the number of animals required for testing, regulatory authorities have approached ecological risk assessment in a tiered manner. Laboratory-based studies (Tier 1), which can be conservative, relatively rapid and economical, are the first tier in evaluating chemicals for their potential [toxic] effects. Tier 1 tests provide an understanding of acute lethality and potential sublethal effects. This information should guide the decision of the assessor whether additional testing is needed. If, based on the outcome of Tier 1 laboratory-based studies, more refined studies are required, then their design should be informed by the Tier 1 study. A higher tier study, such as a semi-field study, should be designed to answer questions identified in the lower-tier study(ies), which are limited. As such, a linkage should begin to be drawn between the different tiers, i.e., as moving from

studies that look at the individual to studies that begin to look at the colony, and ultimately look at the colony in a environmentally realistic setting.

Considerable testing has been conducted with the honey bee under relatively standardized conditions which has resulted in a sizeable database on the acute contact toxicity of a wide range of chemicals. This toxicity data generated through relatively standardized testing enables risk assessors to compare the relative toxicity of chemicals to bees across chemical classes with highly divergent modes of action. Workshop participants believed that since Tier 1 laboratory studies often serve as the basis upon which further testing is or is not required, these studies are relied upon to be accurate, informative and efficient. Further, studies must be designed and harmonized to provide the highest quality data with the least amount of variability. This chapter provides an overview of existing toxicity tests and their strengths/weaknesses and discusses proposed modifications to existing studies, or additional studies that could address limitations in the current battery of studies.

Overview of Laboratory Testing Requirements Among Several Countries

Overview of Honey Bee Laboratory Testing in the European Union

To assess the potential hazard of pesticides to honey bees, regulatory agencies in different world regions have developed varied approaches and requirements for hazard testing in support of ecological risk assessment. The requirements for regulatory testing on honey bees in the European Union (EU) can be found in Annex II and III of EU Directive 91/414. Additional regulatory guidance is being provided by the EU Terrestrial Guidance Document, SANCO/10329/rev 2 final, 2002, and recently revised EPPO documents (EPPO 2011, OECD 2007, EPPO 2010). A new EU Regulation (EC No 1107/2009) (EC No 1107/2009), intended to replace EU Directive 91/414, was published in October 2009, but the data requirements and risk assessment criteria to support this new directive has not been established.

European testing has always followed a sequential testing scheme, i.e., starting with laboratory-based testing and then moving on to higher tier studies if warranted. Where there is only one route of exposure (*e.g.*, oral exposure in case of soil application of systemic products), the acute testing can be restricted to that route (*i.e.*, contact or oral). For systemic products applied as a seed dressing, the acute oral toxicity of the active substance(s) has to be determined as oral exposure is a relevant route of exposure.)

3807 [REDACTED]
 3808 [REDACTED] Pistorius *et al.* 2009)
 3809 [REDACTED] Forster 2009, Alix *et al.* 2009) Can we cite Krupke and the Italian study here? In such a
 3810 case, potential routes of exposure would include oral and contact and, therefore, effects
 3811 testing would be required to account for both routes of exposure. Acute tests with the
 3812 formulated product, *i.e.*, active ingredient(s) plus inerts, is required if the product contains
 3813 more than one active substance, or if the toxicity of a new formulation cannot be reliably
 3814 predicted to be either the same or lower than a formulation tested (EU Directive 91/414, point
 3815 10.4.1).

Formatted: Font: Italic

Formatted: Font: Italic

3816
 3817 In the EU, regulatory authorities may require a bee brood feeding test to assess potential
 3818 hazard of a pesticide on honey bee larvae. Currently this testing must be carried out when the
 3819 active substance may act as an insect growth regulator, or when available data indicates that
 3820 there are effects on development at immature stages. Larval testing may be carried out
 3821 according to the method described by Oomen *et al.* (1992) in which colonies are fed
 3822 pesticide concentrations in sugar syrup. Dose levels used in this test should reflect maximum
 3823 levels [of active substance] expected in the applied product.

3824
 3825 If results of either the adult or larval tests indicate that a presumption of minimal risk cannot
 3826 be made, then further testing such as a semi-field or field testing is triggered in order to
 3827 determine whether any toxicity is observed under realistic exposure conditions. OECD
 3828 guidance document No 75 (OECD, 2007) and EPPO 170 (EPPO 2010; PP1/170) provide
 3829 recommendations on testing honey bee brood under semi-field and field conditions.

3831 **Overview of honey bee laboratory testing for Regulatory Purposes in North America** 3832

3833 Similar to the EU, North America (U.S. EPA, and Canada's PMRA) employ laboratory-based
 3834 tests as a first step for evaluating the potential toxicity of chemicals to insect pollinators. The
 3835 U.S. EPA's data requirements for insect pollinator testing are defined in the U. S. Code of
 3836 Federal Regulations 40 (CFR 40; Protection of the Environment) Part 158 (Data
 3837 Requirements for Pesticides) Subpart G (Ecological Effects) §158.630 (40 CFR Part 158,
 3838 2012). Similar to the European process, the North American process also follows a tiered
 3839 approach.

3840

Tier 1 consists of an acute contact toxicity tests with young adult honey bees, USEPA Guideline 850.3020, (USEPA 2012a). Until recently, US EPA has typically required just the acute contact toxicity test; however, in efforts to better harmonize with its counterparts in Canada and Europe and in recognition that exposure occurs through ingestion of pesticide residues as well as through contact, the US has begun to require oral toxicity tests consistent with OECD Guideline 214 (OECD 1998a). Higher tier studies may be required if the results of the acute toxicity tests indicate that the LD₅₀ < 11 µg a.i./bee toxicity, and/or if other lines of information, such as data in the open literature and incident data indicate that additional information is needed.

Currently, higher tier tests include (i) laboratory-based toxicity of residues on foliage test, *i.e.*, USEPA Guideline 850.3030, (USEPA 2012b) and field-based pollinator study, USEPA Guideline 850.3040 (USEPA 2012c). The toxicity of residues on foliage test is based on the work of Johansen et al. (1997) and Laigier *et al.* (1974) and is intended to provide data on the residual toxicity of a compound to honey bees. In this study, the test substance is applied to a sample of crop material (alfalfa is preferred) at the typical label rate and placed in with caged test bees which are allowed to forage on the treated plant material. Mortality and adverse effects are recorded after 2, 8, and 24 hours of exposure to the treated foliage. If the mortality of bees exposed to 24-hour old residues is greater than 25%, sampling is continued at 24-hr intervals until mortality of bees exposed to treated foliage is not significantly greater than controls.

Beyond the toxicity test of residues on foliage, if any of the following conditions are met, EPA may require a pollinator field study (OPPTS Guideline 850.3040¹⁰):

- Data from other sources (*e.g.*, open literature, beekill incidents) indicate potential adverse effects on colonies, especially effects other than acute mortality (reproductive, behavioral, *etc.*);
- Data from toxicity of residue on foliage studies indicate extended residual toxicity.
- Data derived from studies with terrestrial arthropods other than bees indicate potential chronic, reproductive or behavioral effects.

¹⁰ *Ibid* USEPA. 2012c.
Pesticide RA for Pollinators 4-13-13

Field pollinator testing is intended to examine the potential effects of a chemical on the whole honey bee colony, and the nature of these studies is discussed in Chapter 9. U.S. EPA testing requirements stipulate that the acute contact toxicity tests be conducted using technical grade active ingredient (purity>95%), while higher tier tests are typically conducted using the formulated product.

Uncertainties in Current Testing Paradigms

Laboratory-based acute toxicity testing of honey bees in the U.S. has not formally included studies examining the potential effects of pesticides on honey bee larvae (brood). In addition, while test guidelines stipulate that sublethal effects must be reported in acute tests, the typical endpoint reported from these tests is the LD₅₀ and rarely is a median effect concentration (EC₅₀) based on a sublethal effect(s) reported. Given that the current U.S. test guidelines are designed to yield regression-based endpoints, *i.e.*, LD_x values, endpoints such as no-observed-adverse-effect concentrations (NOAEC) and lowest-observed-effect concentrations (LOAEC) which require hypothesis testing are not likely attainable since treatments are not sufficiently replicated.

Also, as noted earlier, under the U.S. testing process, the honey bee is used as a surrogate for other pollinator insects and for terrestrial invertebrates. In the EU however, specific test guidelines are available for examining the effects of pesticides on non-target arthropods and beneficial insects based on the ESCORT 2 guidance (Condolfi *et al.* 2000) independent of the studies examining toxicity to honey bees. Uncertainties regarding the use of honey bees as surrogates for other non-*Apis* bees were identified at the Pellston workshop. These uncertainties centered on the fact that the life history and social biology of honey bees is significantly different from that of other bees and arthropods. At this time, there are insufficient data to determine whether or not honey bees serve as a reasonable surrogates for other non-*Apis* bees or insect pollinators in general (*i.e.*, whether laboratory studies conducted with *A. mellifera* provide endpoints sufficiently protective of the range non-*Apis* bees or other insect pollinator insects and/or terrestrial invertebrates). However, it was noted by Pellston participants that since laboratory studies are intended to examine the intrinsic toxicity of a chemical to a particular test organism, differences in the biology of the test organism relative to those species for which it is intended to serve as a surrogate may not be critical. **Table 8-1** provides a comparison of the acute laboratory toxicity tests (OECD 213,

[PAGE * MERGEFORMAT]

3905 OECD 214 and OPPTS 850.3020) currently required by regulatory authorities in the EU and
3906 U.S.

3907

3908

Table 8-1. Comparison of acute contact test guidelines (OECD 214 and EPA OPPTS 850.3020) and acute oral test guideline (OECD 213)

	OECD 214 (acute contact)	EPA OPPTS 850.3020 (acute contact)	OECD 213 (acute oral)
Status and background	Adopted 21 September 1998 Based on EPPO GL 170 (1992) and improvements considered made by ICPBR (1993) Other GLs considered: SETAC (1995), Stute (BBA) (1991), EPA OPPTS 850.3020 (2012a).	Public draft April 1996 Based on OPP 141-1 (1982)	Adopted 21 September 1998 Based on EPPO GL 170 (1992) and improvements considered made by ICPBR (1993) Other GLs considered: SETAC (1995), Stute (BBA) (1991), EPA OPPTS 850.3020 (1995).
Test species and test organisms	Young, healthy, adult worker bees (<i>Apis mellifera</i>), same race, similar age and feeding stage, from queen-right colony, known history. Bees collected from frames without brood are suitable. Bees should not have been treated chemically for at least 4 weeks.	Young test bees, 1-7 days old (<i>Apis mellifera</i>), may be obtained directly from hives or from frames kept in an incubator, from same source	Young, healthy, adult worker bees (<i>Apis mellifera</i>), same race, similar age and feeding stage, from queen-right colony, known history. Bees collected from frames without brood are suitable. Bees should not have been treated chemically for at least 4 weeks.
Test cages	Clean and well ventilated made of any appropriate material, e.g., stainless steel, wire mesh, plastic, disposable wooden cages. Groups of <u>10 bees</u>	Test chambers may be constructed of metal, plastic, wire mesh, or cardboard, or a combination of these materials. Groups of at least <u>25 bees</u>	Clean and well-ventilated made of any appropriate material, e.g., stainless steel, wire mesh, plastic, disposable wooden cages. Groups of 10 bees
Handling, feeding, preparation	Food - <i>ad libitum</i> – as sucrose solution (50% w/v), e.g., via glass feeders Bees may be anaesthetized with carbon dioxide (CO ₂) or nitrogen (N ₂) for application. Amount should be minimal	A 50% sugar/water solution should be provided <i>ad libitum</i> (purified or distilled water should be used). Bees may be anaesthetized with carbon dioxide (CO ₂) or nitrogen (N ₂) for application.	Food - <i>ad libitum</i> – as sucrose solution (50% w/v), e.g., via glass feeders Feeding system should allow recording of food intake (e.g., glass tubes 50 mm long, 10 mm wide, and narrow end) Bees may be starved for up to 2h before test initiation

	Moribund bees should be rejected before testing		Moribund bees should be rejected before testing
Solvents	Test substance applied as solution in a carrier, <i>i.e.</i> , organic solvent – acetone preferred – or a water solution with a (commercial) wetting agent. <u>Two separate control groups, <i>i.e.</i>, water and solvent /dispersant</u>	A solvent is generally used to administer the test substance. The solvent of choice is <u>acetone</u> (or other volatile organic solvents) <u>Two concurrent control groups, <i>i.e.</i>, water and solvent (or carrier) control</u>	Test substance applied as 50% sucrose solution in a carrier, <i>i.e.</i> , organic solvent (<i>e.g.</i> , acetone), emulsifiers or dispersants at low concentration up to max 1% should not be exceeded. Two separate control groups, <i>i.e.</i> , water and solvent /dispersant
Test and control groups	Normally <u>5 doses</u> in geometric series with a factor <u>≤ 2.2</u> covering the range of LD ₅₀ for definitive test (ranger-finder proposed) Minimum of 3 replicates with 10 bees for each dose rate and control (<u>Minimum of 30 bees for each dose</u>) <u>Max. ≤ 10% control mortality at test end</u>	A minimum of <u>5 dosage levels</u> spaced geometrically. Recommended spacing for each dosage level to be <u>at least 60 percent of the next higher level</u> . Three or more dosages should result between 0 to 100% mortality. <u>Minimum of 25 bees for each dosage.</u> <u>Max. ≤ 20% control mortality during the test</u>	Normally 5 doses in geo-metric series with a factor ≤2.2 covering the range of LD ₅₀ for definitive test (ranger-finder proposed) Minimum of 3 replicates with 10 bees for each dose rate and control (<u>Minimum of 30 bees for each dose</u>) <u>Max. ≤ 10% control mortality at test end</u>
Limit test	<u>100 µg ai/bee</u> in order to demonstrate that the LD ₅₀ is greater than this value.	<u>25 µg ai/bee</u> in order to demonstrate that the LD ₅₀ is greater than this value.	<u>100 µg ai/bee</u> in order to demonstrate that the LD ₅₀ is greater than this value.
Toxic standard	At least 3 dose rates with 3 x 10 bees to demonstrate, <i>e.g.</i> , the <u>toxic standard</u> , dimethoate, is within the reported contact LD ₅₀ of 0.10-0.30 µg ai/bee (Gough <i>et al.</i> 1994). Other toxic standards are acceptable.	<u>A concurrent positive control is not required.</u> A lab standard is recommended; also when there is a significant change in source of bees.	At least 3 dose rates with 3 x 10 bees to demonstrated eg the toxic standard, dimethoate, is within the reported contact LD ₅₀ of 0.10-0.35 µg ai/bee (Gough <i>et al.</i> 1994). Other toxic standards are acceptable.
Exposure	<u>1 µL</u> per bee applied on dorsal side of thorax (higher volumes, if justified) via micro-applicator. Temperature: <u>25±2°C</u>	<u>5 µL</u> per bee should not exceeded	100-200 µL per 10 bees of 50% sucrose solution in water (or higher) provided for 3-4 (max. 6)h. Amount consumed amount is measured.

	<p>Relative humidity: <u>50-70%</u></p> <p>Test duration: <u>48h</u>.</p> <p>(If mortality increases by > 10% between 24h and 48h the duration is prolonged to <u>maximally 96h</u> provided that the control does not exceeding 10%.)</p>	<p>Temperature: <u>25-35°C</u></p> <p>Relative humidity: <u>50-80%</u></p> <p>Test duration: <u>48h</u></p>	<p>Temperature: 25±2°C</p> <p>Relative humidity: 50-70%</p> <p>Test duration: 48h.</p> <p>(If mortality increases by > 10% between 24h and 48h the duration is prolonged to maximally 96h provided that the control does not exceeding 10%.)</p>
Observations	<p>Mortality at 4h, 24h, 48h, and potentially at 72h and <u>96h</u>.</p> <p><u>Abnormal behavioural</u> effects during the test period should be recorded.</p>	<p>Mortality at 4h, 24h, 48h</p> <p>All <u>signs of intoxication and other abnormal behaviour</u> (e.g., ataxia, lethargy, hypersensitivity) during the test period should be recorded.</p>	<p>Mortality at 4h, 24h, 48h, and potentially at 72h and 96h.</p> <p>Amount of diet consumed per group should be measured to determine palatability of diet.</p> <p>Abnormal behavioural effects during the test period should be recorded.</p>
Data reporting	<p>Range-finding data</p> <p><u>LD₅₀ plus 95% confidence limits, i.e.,</u> at 24h, 48h and, if relevant 72h and 96h (in µg test substance per bee) and slope of curves</p> <p>Mortality statistics (e.g., probit analysis, moving-average, binominal probability)</p> <p>Other biological effects and any abnormal bee responses</p> <p>Deviations from test guideline</p>	<p>Range-finding data</p> <p><u>LD₅₀ plus 95% confidence limits, i.e.,</u> at 24h, 48h and, and slope of curves, goodness-of-fit test results</p> <p>Mortality statistics (e.g., probit analysis, moving-average, binominal probability)</p> <p>Signs of intoxication and other abnormal behaviour.</p> <p>Deviations from test guideline</p>	<p>Range-finding data</p> <p>LD₅₀ plus 95% confidence limits, i.e., at 24h, 48h and, if relevant 72h and 96h (in µg test substance per bee) and slope of curves</p> <p>Mortality statistics (e.g., probit analysis, moving-average, binominal probability)</p> <p>Other biological effects and any abnormal bee responses</p> <p>Deviations from test guideline</p>

Limitations and suggested improvements for Tier 1 testing

Adult *Apis mellifera* Worker Acute Toxicity

Exposure of honey bees can be from direct overspray while the bees are foraging, by contact with contaminated surfaces of the plant, or by intake of contaminated pollen and nectar. The hazard posed by short-term exposures can be assessed using acute toxicity tests.

As discussed in the preceding section, acute honey bee testing under laboratory conditions has been conducted for some time according to several different test guidelines and published methods, e.g., EFPO 130 (1992) and updated in 2010, SFL 141 (2012), and EPA OPPIS 801 (2011) EPA 111.

Workshop

participants considered the OECD test guidelines (OECD 1998a and 1998b) to be the most detailed of those available for assessing the acute toxicity of pesticides to honey bees for the reasons presented below.

Acute honey bee tests performed according to OECD 213 (acute oral toxicity; OECD 1998b), and OECD 214 (acute contact toxicity; OECD 1998a), can be designed as limit tests or as dose-response studies (with a minimum of 5 doses and a minimum of 3 replicates of 10 bees at each dose). The bees are held under controlled temperature and humidity conditions and mortality and behavior is monitored for a minimum of 48 hours (this is extended if effects are prolonged). The reported data include the LD₅₀ (with 95% confidence limits), at 24h, 48h and, if relevant 72h and 96h time points (in µg test substance per bee), the slope of dose-response curves, and any other observed abnormal bee responses. Both tests include both a control (treated with the same concentration of solvent as in the treated doses) and a toxic standard (e.g., dimethoate) with defined acceptance criteria.

The OECD 214 acute contact test (OECD 1998a) involves direct application of the test substance (active ingredient or formulation), usually as a 1 µl drop, diluted in an organic solvent or water as required, applied directly to the dorsal thorax of the bee. Among the advantages of the OECD 214 acute contact test guideline are:

Formatted: Font: Italic

Formatted: Font: Italic

- replication (at least 3 replicates);
- no in-hive treatments for 4 weeks prior to use in a study are permitted;
- higher number of test organisms is specified (30 bees);
- prescriptive environmental conditions;
- stringent control mortality is specified (10%);
- a toxic standard is required and validity criteria are stated; and,
- test duration is prolonged in case of delayed effects.

The only internationally accepted oral acute toxicity test guideline is OECD 213 (OECD 1998b). The test is similar in design to the OECD 214 (OECD 1998a), acute contact toxicity test, but consists of group feeding of a known volume of treated sucrose solution over a maximum period of 6 hours to the replicate bees within a cage and then untreated sucrose is supplied *ad libitum*. Group feeding can be used to administer the dose of test substance because honey bees exhibit trophallaxis, *i.e.*, the transfer of food among colony members; the applicability and repeatability of this is demonstrated by the toxic reference chemical (*e.g.*, dimethoate), which is stable within a testing facility. The test requires monitoring of the actual intake of the treatment to determine the intake of the test substance per bee as some pesticides, such as pyrethroids are repellent and the total dose may not be consumed.

Participants of the Workshop discussed the limited number of cases which would compel specific deviations from the OECD acute test guideline(s), such as when working with the Africanized bee (Nocelli personal communication). However, changes in study design can affect outcomes and reliability of the resulting data. Before data generated from modified study designs can be used reliably in risk assessment, methodology and the resulting data should undergo a separate validation exercise (*e.g.*, determination of appropriate toxic reference and control data).

Adult Oral Chronic toxicity – *Apis bees*

Undertaking an adult oral chronic toxicity study is a refinement step in the proposed risk assessment scheme. Currently, there is no standardized guideline for chronic toxicity testing with bees, but method proposals and study design elements from acute toxicity tests which may be applicable to longer-term studies can be found in a number of publications, *e.g.*, Schmuck (2004), Suchail *et al.* (2001), Moncharmont *et al.* (2003), Alioune *et al.* (2009) and the EPA Guideline OPPTS 850.3020 (USEPA 2012a). Participants of the Workshop identified several gross factors that should be considered when considering an adult chronic toxicity test, these are listed below. A more detailed list of chronic study design elements and considerations and proposed design elements, can be found in Appendix 1.

- There is no standardized duration for the study considering that the longevity of honey bees differs between summer and winter. However if the study aims at representing the typical exposure period of a forager on plants, then a 10-day period will cover most of the cases. Indeed, these bees will have already reached 14 days of age prior to being recruited as foragers, *i.e.*, the last activity of female worker bees. For summer bees with their shorter life span and greater likelihood of being in the immediate vicinity of a treated crop, it is unlikely that their lifespan would last any longer than 10 days on the treated crop. Should the treated crops not be in their immediate vicinity, then it is likely that exposure will take place over a more limited period as the number of possible foraging trips per day declines as the distance increases. It is currently recommended that the study be performed over a 10-day duration to ensure the most likely constant exposure period as well as high control survival (longer study durations may result in reduced control survival that can limit the ability of the study to detect treatment effects).
- To achieve a 10-day study duration, a mixed pollen (protein source) and sucrose (carbohydrate source) diet may be required.
- Some pesticides may induce reduced food intake due to repellency (*e.g.*, pyrethroids) and the longevity of the bees may be affected by the reduced food intake due to repellency rather than reflecting a toxic effect of the pesticide.

Therefore, food intake has to be assessed in parallel with mortality on a daily basis. The pattern of exposure may affect the observed toxicity *e.g.*, a single dose per day versus continuous exposure. Continuous exposure could mean: 1) dosed diet *ad libitum* or, 2) a fixed amount of dosed diet daily (*e.g.*, 2 hours plus untreated diet during the rest of the time). Research is still underway to determine which approach is most appropriate. ~~It is recommended that both approaches, single dose or continuous exposure, are used until sufficient data have been generated to clarify which is the most reliable.~~

Honey Bee Brood Tests in the Laboratory

The *in vitro* honey bee brood test provides quantitative oral/contact toxicity data on larvae for active ingredients or formulated products. These data should be used in an appropriate brood risk assessment scheme. *In vitro* larvae tests have been developed by Rembold and Lackner (1981) and used for the assessment of pesticides by Wittmann (1982). Some years later, Aupinel *et al.* (2005), improved this method in several aspects. Participants of the Workshop discussed brood tests, specifically the study design by Aupinel *et al.* (2005), and considered further design considerations and improvements to this test. A detailed list of suggested modifications to the Aupinel *et al.* study design can be found in Appendix 2.

Adult Toxicity Testing with non-*Apis* Bees

As discussed previously, there is always uncertainty regarding the extent to which a surrogate test species, such as the honey bee, is a sensitive indicator of the many other species it represents. Data currently available suggest that adult non-*Apis* bees are similar in pesticide sensitivity to *A. mellifera* when bodyweight is taken into account. This conclusion is based on analysis of a dataset composed mainly of test results for pesticides of older chemistries, so some caution may be in order when considering compounds of new chemical classes. Figure 8-1 shows the relative toxicity (contact LD₅₀ normalized to

1 g body weight) of 21 pesticides to bumble bees and solitary bees in comparison to the honey bee. Figure 8-2 depicts the decline in toxicity of residues on foliage for honey bee adults compared to the solitary alfalfa leaf-cutter bee (*Megachile rotundata*) and the alkali bee (*Nomia melanderi*). Figure 8-3 depicts the median lethal doses of sprayed residues of four pesticides (clothianidin, imidacloprid, lambda cyhalothrin and spinosad) to *A. mellifera*, *M. rotundata*, and *O. lignaria*. These data suggest that the toxicity of these pesticides falls within an order of magnitude of the values for *A. mellifera*. This indicates that an assessment factor of 10 may be adequate to account for interspecies differences in sensitivity when acute toxicity values for honey bees are used in risk assessments.

As part of the problem formulation for an ecological risk assessment, risk assessors and risk managers can consider whether testing should include non-*Apis* species, such as when evidence or information suggests that the honey bee is not likely to be a reasonable surrogate for a crop, landscape, or region owing primarily to concerns regarding marked differences in potential exposure rather than in toxicity *per se*, *i.e.*, rather than sensitivity. When selecting species to be used in the laboratory, it is important to consider their availability, ease of handling and survival under controlled laboratory conditions. Therefore, it is recommended that both relevance (to a risk assessment and attendant protection goals) and sensitivity and are considered when determining whether to employ non-*Apis* species in an assessment.

Owing to differences in potential exposure, non-*Apis* bees may provide a means of examining the potential effects of these differences on the of a species. For example, honey bees are capable of foraging over long distances and may have a wide range of forage available to them. However, non-*Apis* bees, *e.g.*, orchard mason bees (*O. lignaria*), are limited in the area in which they forage and may be confined to a particular treated area where the likelihood of exposure is increased.

Formatted: Font: Italic




Figure 8-1. Comparison of the contact toxicity (LD₅₀) of 21 pesticides to adults of *Apis mellifera* , 3 species of the social bee *Bombus* and 3 species of solitary bees (*Osmia*, *Megachilidae* and *Nomia*). Points below the diagonal line indicate greater sensitivity than *Apis mellifera*, while points above the diagonal line represent lower sensitivity than *Apis mellifera*. (Johansen *et al.*1986). Need to add a diagonal line running from (0.01,0.01) to (10000,10000).




Figure 8-2. Comparison of the toxicity of pesticides to adults of *Apis mellifera* with the solitary bees *Megachile rotundata* and *Nomia melanderi* based on time for sprayed residues to decline to a concentration causing 25% or less mortality. Points below the diagonal line indicate greater sensitivity than *Apis*

mellifera, while points above the diagonal line represent lower sensitivity than *Apis mellifera*. (Johansen *et al.* 1986) Need to add a diagonal line running from (1,1) to (1000,1000).




Figure 8-3. Comparison of the toxicity (LD₅₀) of sprayed residues of clothianidin, imidacloprid, *lambda*-cyhalothrin and spinosad to adults of *Apis mellifera*, *Megachile rotundata*, and *Osmia lignaria* (Scott-Dupree pers comm.). Points below the diagonal line indicate greater sensitivity than *Apis mellifera*, while points above the diagonal line represent lower sensitivity than *Apis mellifera*. (Johansen *et al.* 1986) Need to add a diagonal line running from (1,1) to (100,100).

Non-*Apis* Bee Testing Methods

As discussed earlier, toxicity tests intended to support regulatory decisions typically involve highly standardized testing protocols and rely on test species that are readily available and lend themselves to testing under laboratory conditions. The test species must be available in large enough numbers and have well-defined husbandry conditions to support replicate testing and thrive under specified test conditions used to examine particular routes of exposure. As with honey bees, the endpoints measured in toxicity

tests with non-*Apis* bees have frequently focused on lethality; measures of sublethal effects on non-*Apis* bees would require similar linkages to assessment endpoints as those identified for honey bees. The development of these linkages may be more challenging though, as sub-lethal effects on individual solitary bees may have a considerably different impact at the population level than similar effects to social bees that form large colonies where the colony may have sufficient redundancy to buffer it from such effects.

The social non-*Apis* bee species most readily manipulated in the laboratory are the *genera* *Bombini* and the *Meliponini* (stingless bees). Some *Bombus* species are also readily available as they are used in commercial pollination of greenhouse crops. Several laboratory studies with non-*Apis* species have been published which reflect a range of methods (Table 8-2). As mentioned earlier, the ability of one non-*Apis* bee species to act as a surrogate for others involves the ready availability, and ability for that species to tolerate testing conditions. This then would indicate that the husbandry needs of that organism are well understood.

Table 8-2 Published Laboratory Tests with non-*Apis* Bees and Associated Methodologies

Species	Oral	Contact	Reference
<i>Megachile rotundata</i> <i>Osmia lignaria</i>	Individually housed adult bees with access to plastic ampoule containing pesticide inserted at base of periwinkle flower 87-90% success rate		Ladurner <i>et al.</i> 2003; and Ladurner <i>et al.</i> 2005
<i>Megachile rotundata</i>	Group feeding of 10 newly emerged bees on 1 mL	1. Direct application – held at 25°C for 20 mins to reduce activity, 1 µL applied to dorsal thorax 2. Filter paper soaked in pesticide and	Huntzinger <i>et al.</i> 2008

Formatted: Centered, None, Space Before: 0 pt, Don't keep with next, Don't keep lines together
Formatted Table

		dried	
<i>Bombus impatiens</i> , <i>Megachile rotundata</i> , <i>Osmia lignaria</i>		Contact with treated filter paper	Scott-Dupree <i>et al.</i> 2009
<i>Megachile rotundata</i> (4-5 day old adults); <i>Nomia melanderi</i> (2-3 week old)		Direct application to mesoscutum	Mayer <i>et al.</i> 1998
<i>Osmia lignaria</i>	Individually fed using flower (cherry) method For delayed activity fed on fresh sucrose	Cooled to 4°C before dosing, 1 µL applied to thorax	Ladurner <i>et al.</i> 2005
<i>Nomia melanderi</i> , <i>Megachile rotundata</i>	Placed into tubes inserted in caps of glass vials with individual bees, group housed after dosing	Direct application to dorsal thorax	Johansen <i>et al.</i> 1983
<i>Megachile rotundata</i>		1 µL applied to thorax of males and females	Tasei <i>et al.</i> 1988
<i>Bombus terrestris</i>	Individually dosed and then group housed	1µL applied to ventral thorax	Thompson 2001

4116

4117

4118 **Non-*Apis* Larval Testing**

4119 Although toxicity testing with some species of adult non-*Apis* bees have been reported

4120 with some frequency, published laboratory studies conducted with non-*Apis* larvae are

4121 more limited, these are listed below (Table 8-4).

4122

4123 **Table 8-4.** Larval test methods for non-*Apis* bee species

Species	Test Elements	Measurement Endpoints	Reference
<i>Osmia lignaria</i>	Eggs raised on treated pollen in 24-well culture plates ; cocoons overwintered and emerged 29°C	Timing and completion of larval development; mortality; emergence, sex and weight	Abbott <i>et al.</i> 2008; Tesoriero et al 2003; Peach et al. 1995
<i>Megachile rotundata</i>	Eggs collected from leaf tunnels, separated into 96-well plates and dosed pollen; cocoons overwintered and emerged	Timing and completion of larval development; mortality; emergence, sex and weight	Abbott <i>et al.</i> 2008
<i>Osmia cornuta</i>	Eggs placed on provisions in gelatin capsules , 1µL applied to surface of provisions	Mortality	Tesoriero <i>et al.</i> 2003
<i>Megachile rotundata</i>	Leaf envelope opened and provision dosed	Weight of emerged adults	Peach <i>et al.</i> 1995
<i>Nomia melanderi</i> , <i>Megachile rotundata</i>	Eggs and young larvae directly dosed	Completion of cocoons	Johansen <i>et al.</i> 1983
<i>Megachile rotundata</i>	Male immature stages, dosed pollen provision	Number developing, cocoon completion,	Tasei <i>et al.</i> 1988
<i>Bombus terrestris</i>	Larvae kept 10/egg cup with 3 adults 28°C, and 50% relative humidity, tested 1-, 4- and 6-day old larvae, fed treated pollen dough or sucrose 24 hrs,	Mortality	Gretenkord and Drescher 1996

4124

4125

4126 **Sub-lethal effects and test developments**

4127

Sublethal effects are defined as the effects to individual that survive the exposure level eliciting the effect. As discussed, while not specifically designed for such, current acute tests include the recording and measuring of sublethal effects. The laboratory-based (10-day) chronic study however, is designed (*i.e.*, longer exposure duration) with the intent of providing more specific information on sublethal effect. Beyond these, experimental research published in the open literature has gone further into investigating sublethal effects of pesticides to bees. This research has revealed insights on physiology and behavior (Desneux *et al.* 2007). Most experimental research regarding the behavioral effects of pesticides on bees has occurred over the last ten years. While these test methods and results are interesting, further work is needed not only to standardize test methods but also to be able to understand the impact of a sublethal effect in the context of the whole colony. Only when the linkage between a sublethal effect at the individual level can be made to the colony level can its relevance to protection goals be understood. This section discusses some of the methods that have been developed to measure the potential sublethal effects of pesticides on honey bees.

Proboscis Extension Response (PER) in Laboratory

When a bee lands on a flower, it extends its proboscis as a reflex stimulated by nectar. This reflex leads to the uptake of nectar and induces the memorization of the floral odors diffusing concomitantly. Thus, the memorization of odors plays a prominent role in flower recognition during subsequent forage trips by the same individual (Menzel *et al.* 1993). Under laboratory conditions, learning and memory can be analyzed using a bioassay based on the olfactory conditioning of the PER on restrained individuals.

The PER assay is based on the temporal paired association of a conditioned stimulus (CS) and an unconditioned stimulus (US). During conditioning, the PER is elicited by contacting the gustatory receptors of the antennae with a sucrose solution (US) while an odor (CS) is simultaneously released. The proboscis extension is immediately rewarded (Reward R) by the uptake of the sucrose solution. Bees can develop the PER as a

conditioned response (CR) to the odor alone after even a single pairing of the odor with a sucrose reward.

The PER assay with restrained workers has been used to investigate the behavioral effects of a number of pesticides (Decourtye and Pham-Delègue 2002; Weick and Thorn 2002; Abramson *et al.* 2004; Decourtye *et al.* 2004). An acute exposure to a test compound can be applied before, during, or after the PER conditioning, and long-term scenarios may be explored with this method for compounds that are expressed in the pollen and nectar. The PER assay has been used to investigate how a chemical treatment can interfere with medium-term (Decourtye *et al.* 2004) or long-term olfactory memory (El Hassani *et al.* 2008). PER tests have recorded reduced learning performances for bees after 11 days of treatment with insecticides administered orally (Decourtye *et al.* 2003) and topically (Aliouane *et al.*, 2009).

PER assays can provide useful information that can be related to the memory and olfactory discrimination abilities of free-flying foragers. However, there is uncertainty regarding the extent to which the PER assay reflects what would occur under more typical settings (e.g., the bees are not restrained, or the exposure is not constant). PER testing that results in statistically significant effects on olfactory learning should be followed up with additional testing, *e.g.*, semi-field testing using intact colonies and tests such as those described in Chapter 9.

Artificial flowers in Semi-field Cage

Olfactory processing can be investigated using free-flying foragers visiting artificial flower feeders. The use of artificial flower feeders simulates a natural foraging situation more closely than does the laboratory tests on restrained worker bees using the conditioned PER procedure.

In artificial flower experiments, a nucleus colony (about 4000 workers and a fertile queen) is placed in an outdoor flight cage. Each artificial flower feeder is a plastic Petri

dish containing glass balls (allowing landing of foragers on the feeding sites) and filled with a sucrose solution that is or is not treated with the test chemical. To limit the influence of visual or spatial cues, the artificial feeder is rotated slowly (*e.g.*, 1/3 rpm), and an odorant (*e.g.*, pure linalool) is allowed to diffuse. The device is placed in front of the hive entrance. The conditioning (pairing odor/sucrose reward) is conducted for 2 hrs on the first day. Testing is then carried out on the following days. For each observation event, the number of forager visits on either the scented sites or the unscented artificial flowers, is recorded. (For more detailed list of design elements for the artificial flower experiment, please see Appendix 3.)

The comparison of responses of honey bees before and after exposure to the test chemical on the same colony is probably the main limit of this device. Moreover, there are many unknown points, such as the reliability, and the sensitivity to large panel of pesticides with various modes of action. Another uncertainty is the actual exposure to individual bees, as bees are not restricted in the length of time they feed at the artificial flowers. Therefore, it is very difficult to characterize the concentration-response relationship.

Visual Learning Performance in a Maze

Orientation performance of bees in a complex maze relies on associative learning between a visual mark and a reward of sugar solution. In a visual learning performance maze, bees fly through a sequence of boxes to reach a feeder containing a reward of sugar solution. The path through the maze spans a number of boxes, including decision boxes (*i.e.*, a box with three holes, each in a different wall, where the bee enters through one hole and is then expected to choose between the two other holes), and non-decision boxes (*i.e.*, a box with two holes, each in a different wall, where the bee entered through one hole and is then expected to leave through the other hole) (Figure 8-4).

During conditioning, bees are collectively trained to associate a mark (designating the correct hole/path) with food. To that end, an identical mark is fixed in front of the correct hole/path as well as the sucrose solution feeder outside the maze for one hour. After

conditioning, the capacity of an individual bee to negotiate a path through the maze is tested. An observer notes the number of correct and incorrect decisions, and then number of turns back. Finally, the bees are captured and placed in rearing cages equipped with a water supply and sugar syrup. Oral delivery of the treatment chemical is via the sucrose solution (50% w/w) available to the bees. After consumption of the treated sugar solution, and a starvation period, the bees are released at the test maze entrance. The effect of the treatment solution on performance is then compared with that of an untreated sucrose solution.




Figure 8-4. Maze paths used before, during and after treatment. Path 1 is used for the conditioning procedure and other paths are used for the retrieval tests. Each path started with the entrance (E), contained 3 decision boxes, 6 no decision boxes, and finished with the reward box (R).

Menzel *et al.* (1974) demonstrated that honey bees in flight can associate a visual mark to a reward and this associative learning is used by bees to negotiate a path in a complex maze (Zhang *et al.* 1996). After treatment with a sublethal dose of a chemical, the ability of bees to perform the task can be impaired compared to untreated control bees

(Decourtye *et al.* 2009). Studies have shown that orientation capacities of foragers in a complex maze can be affected by a pesticide. [REDACTED] The maze test relies on the visual learning of foragers in relation to navigation. However, while the maze test has demonstrated neurotoxic effects with pesticides, there are insufficient data at this time to determine whether the test will provide useful information for chemicals with other modes of action. Additionally, bee navigation in the field relies upon several guidance mechanisms, (*e.g.*, position of sun, magnetism, *etc.*), whereas in the maze test, performance is based on the use of a limited number of pertinent cues. Additional experiments are needed to establish whether effects on maze performance reflect what may actually occur when foragers are exposed to pesticides in the field and are then confronted with complex environmental cues. (For a more detailed discussion of Visual Learning Test, please see Appendix 4.)

RFID Tagged Bees to Measure Foraging Behavior

Experimental test situations have been designed in relation to feeding behavior and social communication (Schricker and Stephen 1970; Cox and Wilson 1984; Bortolotti *et al.* 2003; and, Yang *et al.* 2008). Initial experiments that looked at field level navigation were limited by the number of individual bees that could be simultaneously monitored (using bees marked with paint or colored number tags). To address this limitation, automated tracking and identification systems have been developed using radio frequency (RF) transponder technology. The use of transponders has the potential to revolutionize the study of insect life-history traits, especially in behavioral ecotoxicology.

Different transponder devices have been employed on honey bees: harmonic radar (*e.g.*, Riley and Smith 2002) and Radio Frequency Identification (RFID; Streit *et al.* 2003). Currently, the RFID tags seem to be the technology offering the most advantages. Advantages of RFID include:

- the large number of individual insects that can be tracked;

- the number of detections which can be monitored rapidly and simultaneously (milliseconds);
- limited transpondence interference from matrices such as propolis, glue, plastic, or wood;
- absence of the need for time consuming visual observations; and,
- reduced disruption to bee behavior given the small size of the RFID tags compared to what is needed for harmonic radar tracking.

Using this test technology, the experimental colony is maintained in an outdoor tunnel. A feeder, placed away from a hive can deliver sucrose solution. A tag-equipped bee passing underneath the reader is identified by the reader and is sent to a data base with real-time recording. By passing underneath the reader both at the hive and at the feeder, the foraging bee is monitored twice, thus determining the direction of target and the travel time between the two recording points. The reader software records the identification code and the exact time of the detection in a database for later analysis of spatial and temporal information. Such analyses may include time spent within the hive, the time spent at the feeder, the time spent between the feeder and the hive, the number of entries into and exits from the hive, and the number of entries into and exits from the feeder.

RFID devices allow the study of both the behavioral traits and the lifespan of bees, especially under biotic and/or abiotic stress. However, the large quantity of data obtained with this technique requires an interface for analyzing the data and providing the life-history traits of individual bees. Under semi-field conditions, RFID microchips have provided detectable effects due to exposure to an insecticide (Decourtye *et al.* 2011). (For a more detailed discussion of the RFID experimental test design, please see Appendix 5.)

Conclusions

Although laboratory toxicity tests are currently available for evaluating the potential effects of chemicals on bees, there is no single consistent approach used by different

regulatory authorities and, therefore, the design and scope of these tests vary. For the purposes of screening-level risk assessments, many regulatory authorities rely on acute tests using young adult honey bees to evaluate toxicity through contact and oral exposure routes. While guidelines are becoming available that include acute toxicity tests with honey bee larvae, there is also need to expand these laboratory test methods to examine the effects of chemicals from subacute and chronic exposure durations. Laboratory-based studies will likely continue to focus on individual test organisms; and, although laboratory-based toxicity testing has historically focused on mortality, tests are evolving to provide insight on sublethal effects such as impaired behavior. As the range of measurement endpoints continues to expand, there is a need to provide both qualitative and quantitative linkages between measurement endpoints and assessment endpoints on which regulatory authorities typically base decisions. Efforts are also underway to expand the range of test species to address concerns that *A. mellifera* may not be an adequate surrogate for non-*Apis* bees with considerably different life cycles.

References

- Abbott, V.A., Nadeau, J.L., Higo, H.A., Winston, M.L. (2008) Lethal and sublethal effects of imidacloprid on *Osmia lignaria* and clothianidin on *Megachile rotundata* (Hymenoptera: Megachilidae). *J Econ Entomol* 101 (3): 784-796.
- Abramson, C.L., J. Squire, A. Sheridan, P.G. Mulder. 2004. The effect of insecticides considered harmless to honey bees (*Apis mellifera*): proboscis conditioning studies by using the insect growth regulators: tebufenozide and diflubenzuron. *Environmental Entomology* 33: 378-385.
- Alouane, Y., El Hassani A.K., Gary V., *et al.* (2009) Sublethal exposure of honeybees to sublethal doses of pesticides: effects on behaviour. *Environ Toxicol Chem*, 28(1):113-122.
- Alex, A. C. Vergnet and T. Mercier. Risks to bees from dusts emitted at sowing of coated seeds: concerns, risk assessment and risk management. Pages 131 – 132 in P. A. Oomen and H. M. Thompson (editors). *Hazards of Pesticides to Bees*. 10th International Symposium of the ICP-BR Bee Protection Group, Bucharest (Romania), October 8 – 9, 2008. *Julius Kühn Archiv* 423.
- Aupinel P., Fortini D., Dufour H., Tassi J.N., Michard B., Odoux J.F., Pham-Delégue M.H. (2005) Improvement of artificial feeding in a standard *in vitro* method for rearing *Apis mellifera* larvae. *Boll. Insect.* 58, 107–111.
- Bortolotti L., Montanari P., Marcelino J., Medrzycki P., Mahi S., Parrini C. (2003) Effects of sub-lethal imidacloprid doses on the homing rate and foraging activity of honey bees. *Bull Insectol*; 56:63-67.

Candolfi, M., K. Barrett, P. Campbell, R. Forster, N. Grandy, M.-C. Huet, G. Lewis, P. Oomen, R. Schmuck, and H. Vogt. 2000. Guidance document on regulatory testing procedures for pesticides with non-target arthropods. *ESCORT Workgroup, Wageningen, The Netherlands 2000. Society of Environmental Toxicology And Chemistry - Europe (SETAC).*

Code of Federal Regulations 40, 2012. Protection of the Environment, Part 158 (Data Requirements for Pesticides, Subpart G (Ecological Effects)) § 158.630 (Terrestrial and aquatic nontarget organism data requirements table. [HYPERLINK "http://ecfr.gpoaccess.gov/cgi/t/text/text-idx?c=ecfr&sid=e2fa3dd8d45333c0c4427b3d556c30f9&tpl=/ecfrbrowse/Title40/40cfr158_main_02.tpl"]]

Cox R. L. and W. T. Wilson (1984) Effects of permethrin on the behavior of individually tagged honey bees, *Apis mellifera* L. (Hymenoptera: Apidae). *Environ Entomol.* 13:375-378.

Decourtye A, Arnaudaud C, Renou M, *et al.* (2004) Imidacloprid impairs memory and brain metabolism in the honey bee (*Apis mellifera* L.). *Pestic Biochem Physiol.* 75(2):83-92.

Decourtye A, Devillers J, Genevoise E, Menach K, Budzinski H, Chazeau S, Pham-Delégue M-H. Comparative sublethal toxicity of nine pesticides on olfactory learning performances of the honeybee *Apis mellifera*. *Arch Environ Contam Toxicol.* 2005;48:242-250.

Decourtye A, Devillers J, Aupinel P, Bruin E, Bagnis C, Fourrier J, Gauthier M (2011). Honeybee tracking with microchips: a new methodology to measure the effects of pesticides. *Ecotoxicology*: 20:429-437.

Decourtye A, Lacassie E., Pham-Delégue M.-N. 2003. Learning performances of honeybees (*Apis mellifera* L.) are differentially affected by imidacloprid according to the season. *Pest Manag Sci* 59:269-278.

Decourtye A, Lefort S, Devillers J, Gauthier M, Aupinel P, Tisseur M. 2009. Sublethal effects of fipronil on the ability of honeybees (*Apis mellifera* L.) to orientate in a complex maze. In: Oomen PA, Thompson BM, editors. *Hazards of pesticides to bees*. Berlin: Anne Brynna GmbH; 2009. pp. 75-83.

Decourtye, A., Pham-Delégue, M.-H., Kaiser, L., Devillers, J., Behavioral methods to assess the effect of pesticides on honey bees. *Apidologie* 33 (2002) 425-432.

Desnoux N, Decourtye A, Dalmosch JM (2007) The sublethal effects of pesticides on beneficial arthropods. *Annu Rev Entomol.* 52:81-106.

EC No 1107/2009: [HYPERLINK "http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2009:309:0001:0050:EN:PDF"]

El Hachemi AK, Dacher M, Gary V, *et al.* (2008) Effects of sublethal doses of acetamiprid and thiamethoxam on the behavior of the honeybee (*Apis mellifera* L.). *Arch Environ Contam Toxicol.* 54:653-661.

EPPO. EPPO standards PP1/170-Test methods for evaluating the side effects of plant protection products on honeybees. *Bull OEPP/EPPO Bull* 31: 323-330 (2011).

EPPO. 2010. Environmental risk assessment scheme for plant protection products, Chapter 10. Risk assessment to honey bees. PP 3/10 (3). OEPP/EPPO, Bulletin OEPP/EPPO Bulletin 40, 1-2.

EPPO. 2010. Efficacy Evaluation of Plant Protection Products: Side-effects on Honey bees. PP 1/170 (4). OEPP/EPPO Bulletin 40: 313-319

EPPO. 2010. Efficacy Evaluation of Plant Protection Products: Side-effects on Honey bees. PP 1/170 (4). OEPP/EPPO Bulletin 40: 313-319

EU Directive 91/414: [HYPERLINK "http://www.uksup.sk/download/oso/20030409_smernica_rady_91_414_eec.pdf"]

- Forster, R. 2009. Bee poisoning caused by insecticidal seed treatment of maize in Germany in 2008. *Pages* 126 – 130 in P. A. Oomen and H. M. Thompson (editors) *Hazards of Pesticides to Bees*. 10th International Symposium of the ICP-BR Bee Protection Group, Bucharest (Romania), October 8 – 9, 2008. *Julius Kühn Archiv* 423.
- Grettenkord, C., and Drescher, W. (1996) Laboratory and cage test methods for the evaluation of insect growth regulators (Insegar, Dimilin) on the brood of *Bombus terrestris* L. Proceedings of the 6th ICP-BR Symposium, on Hazards of Pesticides to Bees, Braunschweig, Germany.
- Huntzinger, C.I., James, R.R., Bosch, J., and Kemp, W.P. (2005) Fungicide tests on adult alfalfa leafcutter bees (*Hymenoptera: Megachilidae*). *J Econ Entomol* 101 (4): 1088–1094.
- Johansen, C. *et al.* 1977. Bee Research Investigations. Dept. of Entomology, Washington State University, unpublished, pp. 22.
- Johansen, C.A., Mayer, D.E., Eves, J.D., and Kiouss, C.W. (1983) Pesticides and Bees. *Environ. Entomol.* 12: 1513–1518.
- Ladurner, E., Bosch, J., Maini, S., and Kemp, W.P. (2003) A method to feed individual bees (*Hymenoptera: Apiformes*) known amounts of pesticides. *Apidologie* 34: 597–602.
- Ladurner, E., Bosch, J., Kemp, W.P., and Maini, S. (2005) Assessing delayed and acute toxicity of five formulated fungicides to *Osmia bicornis* Say and *Apis mellifera*. *Apidologie* 36: 449–460.
- Lapier, R.E. *et al.* 1974. Adjuvants Decrease Insecticide Hazard to Honey Bees. College of Agriculture Research Center, Washington State University Bulletin 801, 7 pp.
- Mayer, D.E., Kovacs, G., and Lunden J.D. (1998) Field and laboratory tests on the effects of cyhalothrin on adults of *Apis mellifera*, *Megachile rotundata* and *Nomia melanderi*. *J Apic Res* 37 (3): 33–37.
- Menzel, R., Greggers, U., Hammer, M. (1993) Functional organization of appetitive learning and memory in a generalist pollinator, the honey bee. In: Papaj, D.R., Lewis, A.C. eds. *Insect learning*. Chapman Hall, New-York, pp. 79–125.
- Mouchamout, F.D., Decourtye, A., Hanfien, C.H., Pons, O., Pham-Delegue, M. (2003) Statistical analysis of honeybee survival after chronic exposure to insecticides. *Environ Toxicol Chem* 22 (12): 3088–94.
- Peach, M.L., Alston, D.G., and Tepedino, V.J. (1995) Sublethal effects of carbaryl brain bait on nesting performance, parental investment and offspring size and sex ratio of the alfalfa leafcutter bee (*Hymenoptera: Megachilidae*). *Environ Entomol* 24 (1): 34–39.
- OECD/OCDE. 1999b. OECD Guidelines for the Testing of Chemicals Honeybees, Acute Oral Toxicity Test. [HYPERLINK "http://www.oecd-ilibrary.org/docserver/download/fulltext/9721301e.pdf?expires=1333215348&id=id&accname=freeContent&checksum=959BEB86B48777CDD914B00E36AA67F0"]
- OECD/OCDE. 1995a. OECD Guidelines for the Testing of Chemicals Honeybees, Acute Contact Toxicity Test. [HYPERLINK "http://www.oecd-ilibrary.org/docserver/download/fulltext/9721401e.pdf?expires=1333215085&id=id&accname=freeContent&checksum=39EF34D70EBB775A1FAE80D4FA4953EB"]
- OECD. 2007. Series on Testing and Assessment Number 75, Guidance Document on the Honey Bee (*Apis mellifera*) Brood Test Under Semi-field Conditions. ENV/JM/Mono(2007)22.

- OECD. 2007. Guidance document on the honey bee (*Apis mellifera* L.) brood test under semi-field conditions. Series on Testing and Assessment No. 75. ENV/JM/MONO(2007)22 (2007).
- Oomen, P.A., A. De Ruijter and J. Van Der Steen. 1992. Method for honeybee brood feeding tests with insect growth-regulating insecticides. Bulletin OEPP/EPPO Bulletin 22: 613 – 616.
- Pieterius, J., G. Bischoff, U. Heinrich and M. Stühler. 2009. Bee poisoning incidents in Germany in spring 2008 caused by abrasion of active substance from treated seeds during sowing of maize. *Pages* 118 – 125 in P. A. Oomen and H. M. Thompson (editors) Hazards of Pesticides to Bees 10th International Symposium of the ICP-BR Bee Protection Group. Bucharest (Romania), October 8 – 9, 2008. Julius Kühn Archiv 423.
- Reinhold H., Lackner B. (1981) Rearing of honeybee larvae *in vitro*. Effect of yeast extract on queen differentiation. *J. Apic. Res.* 20: 165–171.
- Riley JR, Smith AD (2002) Design considerations for a harmonic radar to investigate the flight of insects at low altitude. *Comput Electron Agric* 35:151–169.
- SANCO/10329/rev 2 final 2002. [HYPERLINK
"http://ec.europa.eu/food/plant/protection/evaluation/guidance/wrkdoc09_en.pdf"]
- Schmuck R. 2004. Effects of a Chronic Dietary Exposure of the Honeybee *Apis mellifera* (Hymenoptera: Apidae) to Imidacloprid. *Arch. Environ. Contam. Toxicol.* 47: 471–478.
- Schricker B, Stephen WP (1970) The effects of sublethal doses of parathion on honeybee behaviour. I. Oral administration and the communication dance. *J. Apicult. Res* 9:141–153.
- Scott-Dupree, C.D., Connel, L., Harris, C.R., (2009) Impact of currently used or potentially useful insecticides for canola agroecosystems on *Bombus impatiens*, (Hymenoptera: Apidae), *Megachile rotundata* (Hymenoptera: Megachilidae) and *Osmia lignaria* (Hymenoptera: Megachilidae). *J Econ Entomol* 102 (1) 177-182.
- SETAC (1995). Procedures for Assessing the Environmental Fate and Ecotoxicity of Pesticides. Edited by Dr. Mark R. Lynch. Published by SETAC-Europe, Belgium, March, 1995.
- Streit S, Bock E, Pick CWW, Tautz J (2003) Automatic life-long monitoring of individual insect behaviour now possible. *Zoology* 106:169–171.
- Stute, K. (1991). Auswirkungen von Pflanzenschutzmitteln auf die Honigbiene. Richtlinien für die Prüfung von Pflanzenschutzmitteln im Zulassungsverfahren, Teil VI, 23 - 1, Biologische Bundesanstalt für Land- und Forstwirtschaft (BBA), Braunschweig, Germany.
- Suchail S, Guet D, Belzances LP (2001) Discrepancy between acute and chronic toxicity induced by imidacloprid and its metabolites in *Apis mellifera*. *Environmental Toxicology and Chemistry* 20:2482–2486.
- Tammi, J.N., Carre, S., Moscatelli, B., and Grondeau C (1989) Recherche de la D.L. 50 de la deltaméthrine (Decis) chez *Megachile rotundata* F. Abeille pollinisatrice de la lucerne (*Medicago sativa* L.) et des effets de doses infra-létales sur les adultes et les larves. *Apidologie* 12 (3) 291-306.
- Teopiero, D., Maccagnani, B., Santi, F., and Celbi, G., (2003) Toxicity of three pesticides on larval instars of *Osmia cornuta*: preliminary results. *Bulletin of Insectology* 56 (1):169-171.
- Thompson H.M. (2001) Assessing the exposure and toxicity of pesticides to bumblebees (*Bombus* sp.) *Apidologie* 32: 305-321.

USEPA. 2012a. Ecological Effects Test Guidelines. OCSPP 850.3020 Honey Bee Acute Contact Toxicity. EPA 712-C-019. January 2012. [HYPERLINK "http://www.regulations.gov/" \! "documentDetail;D=EPA-HQ-OPPT-2009-0154-0016"]

USEPA. 2012b. Ecological Effects Test Guidelines OCSPP 850.3030 Honey Bee Toxicity of Residues on Foliage. EPA 712-C-018. January 2012. [HYPERLINK "http://www.regulations.gov/" \! "documentDetail;D=EPA-HQ-OPPT-2009-0154-0017"]

USEPA. 2012c. Ecological Effects Test Guidelines OCSPP 850.3040 Field Testing for Pollinators. EPA 712-C-017. Jan. 2012. [HYPERLINK "http://www.regulations.gov/" \! "documentDetail;D=EPA-HQ-OPPT-2009-0154-0018"]

Waick, L., and R.S. Thorn. 2002. Effects of acute sublethal exposure to coumaphos or diazinon on acquisition and discrimination of odor stimuli in the honey bee (Hymenoptera: Apidae). J. Econ. Entomol. 91: 227-236.

Wittmann D., Engels W. (1981) Development of test procedures for insecticide-induced brood damage in honeybees. Mitt. Dtsch. Ges. Allg. Angew. Entomol. 3, 187-190.

Yang EC, Chuang YC, Chen YL, and Cheng LH. 2008. Abnormal Foraging Behavior Induced by Sublethal Dosage of Imidacloprid in the Honey Bee (Hymenoptera: Apidae). J Econ Entomol, 101(6):1743-1748.

Zhang, S. W., Bartels, K., and Srinivasan, M. V. (1996). Maze learning by honeybee. *Neurobiol. Learn. Mem.* 66, 267-282.

XXXXXXXXXXXXXXXXXX

~~Abx, A. C. Vergnet and T. Mercier. Risks to bees from dusts emitted at sowing of coated seeds: economic risk assessment and risk management. Pages 121-132 in P. A. Oomen and H. M. Thompson (editors). Hazards of Pesticides to Bees. 10th International Symposium of the ICP. BM Bee Protection Group, Bucharest (Romania), October 8-9, 2008. Julius Kuhn Archiv 422.~~

~~Code of Federal Regulations 40, 2012. Protection of the Environment, Part 158 (Data Requirements for Pesticides- Subpart G- (Ecological Effects)- 6-158.430 (Terrestrial and aquatic non-target species data requirements table).~~

~~[HYPERLINK "http://ecfr.gpoaccess.gov/cgi/t/text/text-idx?c=ecfr&sid=e2fa3dd8d45333e0e4427f3d5556e30f9&tpl=/ecfrbrowse/Title40/40ecfr158_main_02.tpl"]~~

~~EU Directive 91/414: [HYPERLINK "http://www.uksup.sk/download/oso/20030409-smernica_rady_91_414_eee.pdf"]~~

~~SANCO/10329/rev 2 final, 2002: [HYPERLINK "http://ec.europa.eu/food/plant/protection/evaluation/guidance/wrkdir09_en.pdf"]~~

~~EPPO, EPPO standards PP1/170-Test methods for evaluating the side effects of plant protection products on honeybees. Bull OEPP/EPPO Bull 31: 323-330 (2011).~~

~~OECD. 2007. Guidance document on the honey bee (*Apis mellifera* L.) brood test under semi-field conditions. Series on Testing and Assessment No. 75. ENV/JM/MONO(2007)22 (2007).~~

~~EPPO, 2010. Environmental risk assessment scheme for plant protection products, Chapter 10. Risk assessment to honey bees, PP 3/10 (3), OEPP/EPPO, Bulletin OEPP/EPPO Bulletin 40, 1-9.~~

Formatted: Normal
Formatted: Strikethrough
Formatted: Normal
Formatted: Font: Italic, Strikethrough
Formatted: Strikethrough
Formatted: Font: Times New Roman, 10 pt, Strikethrough
Formatted: Strikethrough
Formatted: Strikethrough
Formatted: Font: 10 pt, Strikethrough
Formatted: Normal
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough

4558	EC No 1107/2009: [HYPERLINK "http://eur-lex.europa.eu/LexUriServ/LexUriServ.do?uri=OJ:L:2009:309:0001:0050:EN:PDF"] ₅₅	Formatted: No underline, Font color: Auto, Strikethrough
4559		Formatted: No underline, Font color: Auto, Strikethrough
4560		Formatted: Strikethrough
4561	EPPO. 2010. Efficacy Evaluation of Plant Protection Products: Side-effects on Honey bees. PP 1/170 (4).	Formatted: No underline, Font color: Auto, Strikethrough
4562	OEPP/EPPO Bulletin 40: 313–319 ₅₆	Formatted: Strikethrough
4563		Formatted: No underline, Font color: Auto, Strikethrough
4564	OECD/OECD. 1998b. OECD Guidelines for the Testing of Chemicals Honeybees, Acute Oral Toxicity Test. [HYPERLINK "http://www.oecd-ilibrary.org/docserver/download/fulltext/9721301e.pdf?expires=1333215348&id=id&accname=freeContent&checksum=959BEB86B48777CDD914B00E36AA67F0"] ₅₇	Formatted: No underline, Font color: Auto, Strikethrough
4565		Formatted: Strikethrough
4566		Formatted: No underline, Font color: Auto, Strikethrough
4567		Formatted: Strikethrough
4568	OECD/OCDE. 1998a. OECD Guidelines for the Testing of Chemicals Honeybees, Acute Contact Toxicity Test. [HYPERLINK "http://www.oecd-ilibrary.org/docserver/download/fulltext/9721401e.pdf?expires=1333215085&id=id&accname=freeContent&checksum=39EF34D70EBB775A1FAE80D4FA4953EB"] ₅₈	Formatted: No underline, Font color: Auto, Strikethrough
4569		Formatted: No underline, Font color: Auto, Strikethrough
4570		Formatted: Strikethrough
4571	Gomen, P.A., A. De Ruijter and J. Van Der Steen. 1992. Method for honeybee brood feeding tests with insect growth regulating insecticides. Bulletin OEPP/EPPO Bulletin 22: 613–616 ₅₉	Formatted: No underline, Font color: Auto, Strikethrough
4572		Formatted: Strikethrough
4573	OECD. 2007. Series on Testing and Assessment Number 75. Guidance Document on the Honey Bee (<i>Apis mellifera</i>) Brood Test Under Semi-field Conditions. ENV/JM/Mono(2007)22 ₆₀	Formatted: No underline, Font color: Auto, Strikethrough
4574		Formatted: Strikethrough
4575	Pistorius, J., G. Biehoff, U. Hombach and M. Stühler. 2009. Bee poisoning incidents in Germany in spring 2008 caused by absorption of active substances from treated seeds during sowing of maize. Pages 118–123 in P. A. Gaxien and H. M. Thompson (editions). Hazards of Pesticides to Bees 10 th International Symposium of the ICP-RR Bee Protection Group. Bucharest (Romania), October 8–9, 2008. Julius-Kühn Archiv 423 ₆₁	Formatted: No underline, Font color: Auto, Strikethrough
4576		Formatted: Strikethrough
4577		Formatted: No underline, Font color: Auto, Strikethrough
4578		Formatted: Strikethrough
4579		Formatted: Font: (Default) Times New Roman, 10 pt, Not Bold, No underline, Font color: Auto, Strikethrough
4580		Formatted: No underline, Font color: Auto, Strikethrough
4581		Formatted: Strikethrough
4582		Formatted: No underline, Font color: Auto, Strikethrough
4583		Formatted: Strikethrough
4584		Formatted: No underline, Font color: Auto, Strikethrough
4585		Formatted: Strikethrough
4586	EPPO. 2010. Efficacy Evaluation of Plant Protection Products: Side-effects on Honey bees. PP 1/170 (4).	Formatted: No underline, Font color: Auto, Strikethrough
4587	OEPP/EPPO Bulletin 40: 313–319 ₆₂	Formatted: Strikethrough
4588		Formatted: No underline, Font color: Auto, Strikethrough
4589		Formatted: Strikethrough
4590	Code of Federal Regulations 40. 2012. Protection of the Environment. Part 158 (Data Requirements for Pesticides. Subpart G (Ecological Effects). § 158.630 (Terrestrial and aquatic nontarget organism data requirements table) ₆₃	Formatted: No underline, Font color: Auto, Strikethrough
4591		Formatted: Strikethrough
4592		Formatted: No underline, Font color: Auto, Strikethrough
4593	[HYPERLINK "http://ecfr.gpoaccess.gov/cgi/t/text/textidx?c=ecfr&cid=e2fa3dd8d45333e0e4427b3d556e30f9&tpl=/ecfrbrowse/titled40/40ecfr158_main_02.tpl"] ₆₄	Formatted: Strikethrough
4594		Formatted: No underline, Font color: Auto, Strikethrough
4595		Formatted: Strikethrough
4596	USEPA. 2012a. Ecological Effects Test Guidelines. OCSPP 850.3020 Honey Bee Acute Contact Toxicity. EPA 712-C-019. January 2012. [HYPERLINK "http://www.regulations.gov/" \! "documentDetail;D=EPA-HQ-OPPT-2009-0154-0016"] ₆₅	Formatted: No underline, Font color: Auto, Strikethrough
4597		Formatted: No underline, Font color: Auto, Strikethrough
4598		Formatted: Strikethrough
4599		Formatted: No underline, Font color: Auto, Strikethrough
4600	USEPA. 2012b. Ecological Effects Test Guidelines OCSPP 850.3030 Honey Bee Toxicity of Residues on Foliage. EPA 712-C-018. January 2012. [HYPERLINK "http://www.regulations.gov/" \! "documentDetail;D=EPA-HQ-OPPT-2009-0154-0017"] ₆₆	Formatted: No underline, Font color: Auto, Strikethrough
4601		Formatted: No underline, Font color: Auto, Strikethrough
4602		Formatted: Strikethrough
4603		Formatted: No underline, Font color: Auto, Strikethrough
4604	USEPA. 2012c. Ecological Effects Test Guidelines OCSPP 850.3040. Field Testing for Pollinators. EPA 712-C-017. Jan., 2012: [HYPERLINK "http://www.regulations.gov/" \! "documentDetail;D=EPA-HQ-OPPT-2009-0154-0018"] ₆₇	Formatted: No underline, Font color: Auto, Strikethrough
4605		Formatted: Strikethrough
4606		Formatted: No underline, Font color: Auto, Strikethrough
4607		Formatted: Strikethrough
4608	Johansen, C. et al. 1977. Bee Research Investigations. Dept. of Entomology, Washington State University, unpublished, 22 pp. ₆₈	Formatted: No underline, Font color: Auto, Strikethrough
4609		Formatted: Strikethrough

4610		
4611	Lagier, R.F. <i>et al.</i> 1974. Adjuvants Decrease Insecticide Hazard to Honey Bees. College of Agriculture	Formatted: No underline, Font color: Auto, Strikethrough
4612	Research Center, Washington State University Bulletin 801, 7 pp.	Formatted: Strikethrough
4613		
4614	Candolfi, M., K. Barrett, P. Campbell, R. Forster, N. Grandy, M.C. Huet, G. Lewis, P. Oomen, R.	Formatted: No underline, Font color: Auto, Strikethrough
4615	Schmuck, and H. Vogt. 2000. Guidance document on regulatory testing procedures for pesticides with non-	
4616	target arthropods. <i>ESCORT Workgroup, Wageningen, The Netherlands 2000. Society of Environmental</i>	
4617	<i>Toxicology And Chemistry – Europe (SETAC).</i>	Formatted: Strikethrough
4618		
4619	Suchail S., Guez D., Belzunces LP (2001) Discrepancy between acute and chronic toxicity induced by	Formatted: No underline, Font color: Auto, Strikethrough
4620	imidacloprid and its metabolites in <i>Apis mellifera</i> . <i>Environmental Toxicology and Chemistry</i> ; 20:2482–	
4621	2486.	Formatted: Strikethrough
4622		
4623	Monchaumont, F.D.; Decourtye, A.; Hanfier, C.H.; Pons, O.; Pham Deleoue, M. (2003) Statistical analysis	Formatted: No underline, Font color: Auto, Strikethrough
4624	of honeybee survival after chronic exposure to insecticides” <i>Environ Toxicol Chem</i> 22 (12): 3088–94.	Formatted: Strikethrough
4625		
4626	Ladurner E., Bosch, J., Maini, S., and Kemp, W.P. (2003) A method to feed individual bees (<i>Hymenoptera:</i>	Formatted: No underline, Font color: Auto, Strikethrough
4627	<i>Apiformes</i>) known amounts of pesticides. <i>Apidologie</i> 34 597–602.	Formatted: Strikethrough
4628		
4629	Ladurner, E., Bosch, J., Kemp, W.P., and Maini, S. (2005) Assessing delayed and acute toxicity of five	Formatted: No underline, Font color: Auto, Strikethrough
4630	formulated fungicides to <i>Osmia lignaria</i> Say and <i>Apis mellifera</i> . <i>Apidologie</i> 36 449–460.	Formatted: Strikethrough
4631		
4632	Huntzinger, C.I., James, R.R., Bosch, J., and Kemp, W.P. (2008) Fungicide tests on adult alfalfa leafcutter	Formatted: No underline, Font color: Auto, Strikethrough
4633	bees (<i>Hymenoptera: Megachilidae</i>) <i>J Econ Entomol</i> 101 (4) 1088–1094.	Formatted: Strikethrough
4634		
4635	Scott-Dupree, C.D., Conrol, L., Harris, C.R., (2009) Impact of currently used or potentially useful	Formatted: No underline, Font color: Auto, Strikethrough
4636	insecticides for canola–agroecosystems on <i>Bombus impatiens</i> , (<i>Hymenoptera: Apidae</i>), <i>Megachile</i>	
4637	<i>rotundata</i> (<i>Hymenoptera: Megachilidae</i>) and <i>Osmia lignaria</i> (<i>Hymenoptera: Megachilidae</i>). <i>J Econ</i>	Formatted: Strikethrough
4638	<i>Entomol</i> 102 (1) 177–182.	
4639		
4640	Mayer, D.F., Kovacs, G., and Lunden J.D. (1998) Field and laboratory tests on the effects of cyhalothrin on	Formatted: No underline, Font color: Auto, Strikethrough
4641	adults of <i>Apis mellifera</i> , <i>Megachile rotundata</i> and <i>Nomia melanderi</i> . <i>J Apic Res</i> 37 (1) 33–37.	Formatted: Strikethrough
4642		
4643	Johansen, C.A., Mayer, D.F., Eves, J.D., and Kious C.W. (1983) Pesticides and Bees <i>Environ Entomol</i> . 12:	Formatted: No underline, Font color: Auto, Strikethrough
4644	1513–1518.	Formatted: Strikethrough
4645		
4646	Tasei, J.N., Carre, S., Moscatelli, B., and Grondeau C (1988) Recherche de la D.L. 50 de la deltamethrine	Formatted: No underline, Font color: Auto, Strikethrough
4647	(Deeis) chez <i>Megachile rotundata</i> F. Abeille pollinisatrice de la lucerne (<i>Medicago sativa</i> L.) et des effets	
4648	de doses infralethales sure les adultes et les larves. <i>Apidologie</i> 19 (3) 291–306.	Formatted: Strikethrough
4649		
4650	Thompson H.M. (2001) Assessing the exposure and toxicity of pesticides to bumblebees (<i>Bombus</i> sp.)	Formatted: No underline, Font color: Auto, Strikethrough
4651	<i>Apidologie</i> 32 305–321.	Formatted: Strikethrough
4652		
4653	Abbott, V.A., Nadeau, J.L., Higo, H.A., Winston, M.L. (2008) Lethal and sublethal effects of imidacloprid	Formatted: No underline, Font color: Auto, Strikethrough
4654	on <i>Osmia lignaria</i> and clothianidin on <i>Megachile rotundata</i> (<i>Hymenoptera: Megachilidae</i>) <i>J Econ Entomol</i>	
4655	101 (3) 784–796.	Formatted: Strikethrough
4656		
4657	Tesoriero, D., Maccagnani, B., Santi, F., and Celli, G., (2003) Toxicity of three pesticides on larval instars	Formatted: No underline, Font color: Auto, Strikethrough
4658	of <i>Osmia cornuta</i> : preliminary results. <i>Bulletin of Insectology</i> 56 (1) 169–171.	Formatted: Strikethrough
4659		
4660	Peach, M.L., Alson, D.G., and Tepedino, V.J. (1995) Sublethal effects of carbaryl bran bait on nesting	Formatted: No underline, Font color: Auto, Strikethrough
4661	performance, parental investment and offspring size and sex ratio of the alfalfa leafcutting bee	
4662	(<i>Hymenoptera: Megachilidae</i>) <i>Environ Entomol</i> 24 (1) 34–39.	Formatted: Strikethrough

4663	Gretenkord, C., and Drescher, W. (1996) Laboratory and cage test methods for the evaluation of insect growth regulators (Insegar, Dimilin) on the brood of <i>Bombus terrestris</i> L. Proceedings of the 6th ICP-BR Symposium, on Hazards of Pesticides to Bees, Braunschweig, Germany.	Formatted: No underline, Font color: Auto, Strikethrough
4664		
4665		Formatted: Strikethrough
4666		
4667		
4668	Desneux N, Decourtye A, Delpuech JM (2007) The sublethal effects of pesticides on beneficial arthropods. Annu Rev Entomol; 52:81-106.	Formatted: No underline, Font color: Auto, Strikethrough
4669		Formatted: Strikethrough
4670		
4671	Menzel R, Greggers U, Hammer M (1993) Functional organization of appetitive learning and memory in a generalist pollinator, the honey bee. In: Papaj DR, Lewis AC eds. Insect learning, Chapman Hall, New York, pp. 79-125.	Formatted: No underline, Font color: Auto, Strikethrough
4672		Formatted: Strikethrough
4673		
4674		
4675	Decourtye, A., Pham-Delegue, M-H., Kaiser, L., Devillers, J., Behavioral methods to assess the effect of pesticides on honey bees. Apidologie 33 (2002) 425-432.	Formatted: No underline, Font color: Auto, Strikethrough
4676		Formatted: Strikethrough
4677	Weick, J., and R.S. Thorn. 2002. Effects of acute sublethal exposure to coumaphos or diazinon on acquisition and discrimination of odor stimuli in the honey bee (Hymenoptera: Apidae). J. Econ. Entomol. 9: 227-236.	Formatted: No underline, Font color: Auto, Strikethrough
4678		Formatted: Strikethrough
4679		
4680	Abramson, C.L., J. Squire, A. Sheridan, P.G. Mulder. 2004. The effect of insecticides considered harmless to honey bees (<i>Apis mellifera</i>): proboscis-conditioning studies by using the insect growth regulators tebufenozide and diflubenzuron. Environmental Entomology 33: 378-388.	Formatted: No underline, Font color: Auto, Strikethrough
4681		Formatted: Strikethrough
4682		
4683		
4684	Decourtye A, Armengaud C, Renou M, et al. (2004) Imidacloprid impairs memory and brain metabolism in the honey bee (<i>Apis mellifera</i> L.). Pestic Biochem Physiol; 78(2):83-92.	Formatted: No underline, Font color: Auto, Strikethrough
4685		Formatted: Strikethrough
4686		
4687	El Hassani AK, Dacher M, Gary V, et al. (2008) Effects of sublethal doses of acetamiprid and thiamethoxam on the behavior of the honeybee (<i>Apis mellifera</i>). Arch Environ Contam Toxicol; 54:653-661.	Formatted: No underline, Font color: Auto, Strikethrough
4688		Formatted: Strikethrough
4689		Formatted: No underline, Font color: Auto, Strikethrough
4690	Aliouane Y, El Hassani AK, Gary V, et al. (2009) Subchronic exposure of honeybees to sublethal doses of pesticides: effects on behaviour. Environ Toxicol Chem; 28(1):113-122.	Formatted: No underline, Font color: Auto, Strikethrough
4691		Formatted: Strikethrough
4692	Schricker B, Stephen WP (1970) The effects of sublethal doses of parathion on honeybee behaviour. I. Oral administration and the communication dance. J Apicult Res 9:141-153.	Formatted: No underline, Font color: Auto, Strikethrough
4693		Formatted: Strikethrough
4694		
4695	Cox R. L. and W. T Wilson (1984) Effects of permethrin on the behavior of individually tagged honey bees, <i>Apis mellifera</i> L. (Hymenoptera: Apidae). Environ Entomol; 13:375-378.	Formatted: No underline, Font color: Auto, Strikethrough
4696		Formatted: Strikethrough
4697		
4698	Bortolotti L, Montanari R, Marcelino J, Medrzycki P, Maini S, Porrini C (2003) Effects of sub-lethal imidacloprid doses on the homing rate and foraging activity of honey bees. Bull Insectol; 56:63-67.	Formatted: No underline, Font color: Auto, Strikethrough
4699		Formatted: Strikethrough
4700		
4701	Riley JR, Smith AD (2002) Design considerations for a harmonic radar to investigate the flight of insects at low altitude. Comput Electron Agric 35:151-169.	Formatted: No underline, Font color: Auto, Strikethrough
4702		Formatted: Strikethrough
4703		
4704	Streit S, Bock F, Pirk CWW, Tautz J (2003) Automatic life long monitoring of individual insect behaviour now possible. Zoology 106:169-171.	Formatted: No underline, Font color: Auto, Strikethrough
4705		Formatted: Strikethrough
4706		Formatted: No underline, Font color: Auto, Strikethrough
4707	Decourtye A, Devillers J, Aupinel P, Brun F, Bagnis C, Fourrier J, Gauthier M (2011). Honeybee tracking with microchips: a new methodology to measure the effects of pesticides. Ecotoxicology; 20:429-437.	Formatted: No underline, Font color: Auto, Strikethrough
4708		Formatted: Strikethrough
4709		
4710	Foster R. 2009. Bee poisoning caused by insecticidal seed treatment of maize in Germany in 2008. Pages 126-130 in P. A. Goman and H. M. Thompson (editors) Hazards of Pesticides to Bees 10th	Formatted: Font: (Default) Times New Roman, Not Bold, Italic, No underline, Font color: Auto, Strikethrough
4711		Formatted: No underline, Font color: Auto, Strikethrough

International Symposium of the ICP-RR Bee Protection Group, Bucharest (Romania), October 8–9, 2008.
Jahres-Kolloid-Archiv 423.

Schmuck R. 2004. Effects of a Chronic Dietary Exposure of the Honeybee *Apis mellifera* (Hymenoptera: Apidae) to Imidacloprid. Arch. Environ. Contam. Toxicol. 47: 471–478.

SETAC (1995). Procedures for Assessing the Environmental Fate and Ecotoxicity of Pesticides. Edited by Dr. Mark R. Lynch. Published by SETAC-Europe, Belgium. March 1995.

Zhang, S. W., Bartsch, K. and Srinivasan, M. V. (1996). Maze learning by honeybee. Neurobiol. Learn. Mem. 66, 267–282.

Stute, K. (1991). Auswirkungen von Pflanzenschutzmitteln auf die Honigbiene. Richtlinien für die Prüfung von Pflanzenschutzmitteln im Zulassungsverfahren, Teil VI, 23–1.

Biologische Bundesanstalt für Land- und Forstwirtschaft (BBA), Braunschweig, Germany.

Yang EC, Chuang YC, Chen YL, and Chang LH. 2008. Abnormal Foraging Behavior Induced by Sublethal Dosage of Imidacloprid in the Honey Bee (Hymenoptera: Apidae). J Econ Entomol, 101(6):1743–1748.

Decourtaye A, Lefort S, Devillers J, Gauthier M, Aupinel P, Tisseur M. 2009. Sublethal effects of fipronil on the ability of honeybees (*Apis mellifera* L.) to orientate in a complex maze. In: Oomen PA, Thompson HM, editors. Hazards of pesticides to bees. Berlin: Arno Brynda GmbH; 2009. pp. 75–83.

Decourtaye A, Devillers J, Genecque E, Monach K, Budzinski H, Cluzeau S, Pham-Delègue MH. Comparative sublethal toxicity of nine pesticides on olfactory learning performances of the honeybee *Apis mellifera*. Arch Environ Contam Toxicol. 2005;48:242–250.

Decourtaye A, Lacassie E, Pham-Delegue M-N. 2003. Learning performances of honeybees (*Apis mellifera* L.) are differentially affected by imidacloprid according to the season. Pest Manag Sci 59:269–278.

Rembold H, Lackner B. (1981) Rearing of honeybee larvae *in vitro*: Effect of yeast extract on queen differentiation. J. Apic. Res. 20, 165–171.

Wittmann D, Engels W. (1981) Development of test procedures for insecticide induced brood damage in honeybees. Mitt. Dtsch. Ges. Allg. Angew. Entomol. 3, 187–190.

Aupinel P, Fortini D, Dufour H, Tasei J-N, Michaud B, Odoux J-F, Pham-Delègue M-H. (2005) Improvement of artificial feeding in a standard *in vitro* method for rearing *Apis mellifera* larvae. Bull. Insect. 58, 107–111.

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Font color: Auto, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Strikethrough

Formatted: Font: Italic, No underline, Strikethrough

Formatted: No underline, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Strikethrough

Formatted: Strikethrough

Formatted: No underline, Strikethrough

Formatted: Font: Italic, No underline, Strikethrough

Formatted: No underline, Strikethrough

CHAPTER 9 ASSESSING EFFECTS THROUGH SEMI-FIELD AND FIELD TOXICITY TESTING

Pettis, J., Tornier, I., Clook, M., Wallner, K., Vaissiere, B., Stadler, T., Hou, W., Maynard, G., Becker, R., Coulson, M., Rogers, D., Jourdan, P., and, Kasina, M.

Introduction

Semi-field and field studies may be conducted for regulatory purposes if lower tier assessments trigger further evaluation of a chemical's potential to cause adverse effects. For example, a regulatory trigger value may have been breached in the lower tier assessment that in turn means that a protection goal may not be met based on the findings at that level. One way to ensure that a protection goal is met is to modify the use of the subject compound such that it may no longer pose an unacceptable risk to the honey bees *Apis mellifera*¹¹ and/or non-*Apis* bees¹². However, modifying or restricting the use of a compound may be undesirable or unnecessary if further information is obtained from either a semi-field or field study that demonstrate otherwise. Such a study or studies should provide greater insight into whether adverse effects to *Apis* and/or non-*Apis* bees are likely to occur under real-world field use of the pesticide in question. As such, the objective of the regulatory study(ies) may be to try to indicate, both quantitatively and qualitatively, what the possible effects may be under more environmentally realistic or relevant conditions. Such studies should be predicated on well developed problem formulation that builds on lower-tier studies as well as the associated risk assessment.

As part of the problem formulation there should be clear idea of the regulatory concern, identification of protection goals, assessment endpoints and related measurement endpoints on which to base judgments. For the purpose of developing guidance relative to higher tier tests, the participants of the Workshop assumed the protection goals stated at the outset of the conference, which include:

¹¹ It should be noted that when referring to *Apis mellifera*, we are referring to the approximately 17 subspecies that originated in Europe.

¹² Non-*Apis* bees are highly varied in terms of social and solitary lives, the duration of their activity in the field, the amount of pollen and nectar they store, and where they nest. For details, see Chapter 3 and Chapter 8.

1. Protection of managed pollination in agricultural/horticultural-based crops (*i.e.*,
Apis and non-*Apis* species);
2. Protection of honey production and other hive-products; and,
3. Protection of biodiversity (primarily non-*Apis* bees)

This chapter provides an overview of what to consider when planning or assessing either a semi-field or field study. As regards the honey bee, much use has been made of EPPO 170 (EPPO 2010) and OECD 75 (OECD 2007). Participants during the SETAC 2011 Workshop used their collective practical and regulatory experience to provide further information on how a study should be conducted. Therefore, the following is seen as a development of both EPPO 170 and OECD 75 based on the experience of the experts present at the workshop. If the risk assessor indicates the need for either a semi-field or field study, then it is recommended that this Chapter along with information provided in EPPO 170 and OECD 75 be consulted. The information in these references may also be consulted when such studies are being evaluated for regulatory purposes.

Definition of Semi-field and Field Studies

Elements in the design of semi-field and field studies encompass the study's objectives, the test organism, a study site, methods, endpoints, sample design, quality assurance/quality control standards and the statistical analysis of the data. In discussing the elements of a semi-field study, the participants of the Workshop defined a semi-field study as the following:

A **semi-field study** is designed to measure exposure and/or effects and is performed on a crop that is grown outdoors in an enclosed test system with controlled or confined exposure. The crop is subject to good agricultural practices (*i.e.*, grower standard practices), and therefore, there will or could be weeds present but the predominant plant, and thus the source of nectar/pollen, will be the crop. The test system could nevertheless be designed to reflect a desired exposure system and specific foraging environments, *e.g.*, a mixture of crop and

weeds, or flowering margins, *etc.* The details of the test design (such as application parameters, or measurement endpoints) will depend upon the regulatory question(s) being asked. However, semi-field studies generally attempt to maximize exposure by confining bees to a particular source of treated nectar/pollen.

Formatted: Font: (Default) Times New Roman, 12 pt, Not Bold, Italic, No underline, Font color: Auto

For species (both non-*Apis* and *Apis* species) that are used to pollinate plants grown in greenhouses it may also be necessary to carry out a higher tier study. A semi-field study will be enclosed with controlled or confined exposure but will be of reduced size compared to a commercial glasshouse. Size of the test environment is related to the species being studied, and the questions or issues being investigated.

A semi-field study, therefore, provides for a potentially worst-case exposure scenario (see Section 1.4.4 for further information on this point).

A **field study** is designed to measure exposure and/or effects and is performed on a crop that is grown outdoors with no enclosure. The crop is established and maintained following good agricultural practices. While the bees are free-flying and able to seek out alternative food sources, alternative sources of pollen and nectar should be minimized (see below for further details). The study design elements (*e.g.*, selection of crop, duration of the study, or environmental conditions) will depend upon the question(s) being asked. A field study for a greenhouse situation should be conducted in a commercial greenhouse.

Design of a Semi-field Study

When deciding whether a semi-field study is appropriate, it is necessary to consider various strengths and weaknesses of this type of study to ascertain whether it is the most appropriate way to refine the understanding of the potential risks from the use of a

4841 compound. Outlined below in Tables 9-1 and 9-2 are strengths and weaknesses of semi-
4842 field studies for *Apis* and non-*Apis* bees.

4843 **Table 9-1. Strengths and Weakneses of Semi-field Tests with *Apis-mellifera***
4844

Strengths	
	Exposure is known since the bees are challenged and there is usually a toxic reference standard treatment group, i.e., the toxic reference standard is a reference chemical treatment (using chemical of known toxicity to bees) is used to confirm that the bees are exposed to the treatment and to calibrate the ability of study to detect toxic effects known to be associated with the reference chemical.
	Provides realistic exposure both inside and outside the hive, i.e., to both material available at the target crop as well as concentrations in the hive.
	The test system can also be designed to determine the residual toxicity. Weathering of the applied material and natural exposure of honey bees are inherent in the design.
	Irrigation of the crop (via drip irrigation to avoid wash-off) is possible, hence potentially reducing the likelihood of the study being adversely affected by drought.
	In contrast to laboratory studies, semi-field studies present a more realistic scenario of interaction between the bees and the environment.
	Due to their smaller size and shorter duration semi-field studies are less affected by fluctuations in ecological variables.
	Potential for sub-lethal effects can be observed more easily than in either laboratory or field studies.
	Brood can be considered in specifically designed semi-field studies (see OECD 75).
	Semi-field tests are relatively quick and easy to perform.
	Semi-field environments are smaller-scale in operation than field studies, making it

Formatted: Font: Times New Roman, 12 pt, Not Bold, Italic,
No underline, Font color: Auto

feasible to test greater numbers of replicates, which in turn should allow for more robust statistical designs.
As the bees are enclosed and have no alternative foraging environment, the exposure is potentially a "worst-case" scenario.
Certain exposure scenarios that are difficult to study under real field conditions, <i>e.g.</i> aphid honeydew, can be studied under semi-field conditions.
Weaknesses
Experience with performing these studies has shown that it is difficult to keep colonies in an enclosed structure for long periods and, as a result there is a limited amount of time that a colony of <i>Apis mellifera</i> can survive in the enclosure. The correct stage of crop bloom is critical to the study and, as a result it is only appropriate to assess the effect of short-term exposure including potential effects on brood (see OECD 75). Where exposure is either repeated over a sustained period (<i>e.g.</i> where there are repeat applications of the pesticide), or where exposure is continuous (<i>e.g.</i> , from the use of systemic seed treatment), semi-field studies may be of limited usefulness in determining long-term effects.
Semi-field studies tend to use colonies with only 3,000 – 5,000 bees (EPPO 170), which is smaller than a full size [managed] colony. Due to the current state of knowledge, it is not possible to determine whether an observed effect in a semi-field study will result in either an effect in a standard full size colony or no effect under field conditions. Hence, extrapolation of adverse effects to a full size unenclosed colony under more realistic field conditions, may not be possible.
Due to the small size of the colony, it is not as easy to assess pollen and nectar storage and hive weight development; therefore, it is difficult to assess potential effects on honey production (<i>i.e.</i> , a potential protection goal identified at the Workshop) when adverse effects are observed on other parameters.
Because the size of the colonies used in semi-field studies prohibit their ability to successfully overwinter, these studies may not provide information on overwintering success.
Due to the nature of the enclosed test design, not all crop scenarios are possible to test, (<i>e.g.</i> , size of plants, area required, and nutritional value of crop to bees)

There is potentially limited foraging area; therefore, care is needed to ensure that sufficient nutrition (i.e., enclosed crop area) is available.

There is a possible stress on bees due to enclosed nature of the study, i.e., bees have a desire to escape, consequently reducing their foraging activity on the crop. However, balance of tent size/crop field size and colony size should ensure foraging and exposure (see EPPO 170).

Table 9-2. Strengths and Weakneses of Semi-field Tests with non- *Apis* Bee Species

Strengths
Individual colonies, or aggregations of individual solitary bees (such as <i>Meloponini</i> or <i>Bombus</i>) can be used and thus the pesticide effects are readily interpreted. Increased replications are possible and readily performed so statistical analysis may be easier.
Product use on a wide range of crops, including those that are not readily pollinated by honey bees (e.g., eggplant), can be assessed.
Some social non- <i>Apis</i> bees amenable to these test, such as <i>Meloponini</i> (stingless bees) and <i>Bombus</i> , are easier to handle than <i>Apis</i> as they are reluctant to sting. Additionally, many of the solitary non- <i>Apis</i> bees, although capable, are reluctant to sting. Solitary bee species amenable to semi-field studies (e.g., <i>Osmia</i> and <i>Megachile</i> species) will not sting.
The area of the enclosure of a semi-field study can support full colonies of non- <i>Apis</i> species (<i>Bombus</i> or <i>Meloponini</i>) or a collection of independent individuals (solitary bees), hence an extended study can be done. These bees have a complete life cycle in three to six weeks (solitary bees) or one season (<i>Bombus</i>) in temperate climate.
Individual solitary bees typically provision nests over a three - six week period, thus allowing for a complete (or at least almost complete) life-cycle study for solitary bees if the forage crop flowers for more than three weeks.
It is possible to do larval exposure tests with solitary bees because pollen/nectar is brought straight to a cell and an egg is laid on the nest. This behavior leads to a potentially conservative assessment since the progeny has direct exposure, dermal and

oral, with food resources that potentially contain the test pesticide.
Non- <i>Apis</i> bees can be used and maintained efficiently in small enclosures.
Non- <i>Apis</i> bees will forage under less optimal conditions in terms of temperature, relative humidity, and wind. This is especially true for <i>Osmia</i> and <i>Bombus</i> spp., which are quite hardy.
In solitary species such as those in Megachilidae, the larvae are in direct contact with nectar and pollen, and so there is the possibility of contact and oral exposure. This is not the case with <i>Apis</i> larvae that require a special larval test to ensure adequate exposure of larvae to a given pesticide and route of exposure.
Weaknesses
Resource supplements may be needed for crops that do not provide both pollen and nectar, which may reduce bee activity.
In temperate areas, the annual life cycle of solitary bees limits the window in which adult or larval testing may be conducted.
There is significant uncertainty as to how representative the current commercially available non- <i>Apis</i> bees are for other non- <i>Apis</i> species. For all non- <i>Apis</i> bees, there is enormous variation in use of resources, behaviour, habitat requirements, life cycles, etc.

4849
4850

4851 **When would a semi-field study be appropriate?**

4852

4853 Consistent with the tiered approach to toxicity testing and risk assessment, semi-field
4854 studies may be triggered when lower tier assessments (relying on laboratory results)
4855 indicate potential risk that are inconsistent with protection goals. In such cases, higher
4856 tier tests may provide information that reduces the uncertainty about risk, allowing for a
4857 more informed decision. Outlined below are scenarios when a semi-field study may be
4858 appropriate; and, when a semi-field study may not be an appropriate option.

4859

- If, as a result of the initial laboratory assessment, acute mortality and/or sub-lethal effects are considered to be the main concern, then a semi-field study may be appropriate.
- If repellency or an impact on foraging activity is predicted, either on the basis of efficacy data (*e.g.*, a compound is known to act via an anti-feedant effect) or from any observations, laboratory or any other relevant studies, then a semi-field study may give the risk assessor useful information on the potential short-term effects the compound may exert on foraging behavior. Due to the confined nature of the study, it can be concluded that no effects in a semi-field study is indicative of no short-term effects under field situations. However, if a potentially significant adverse effect on foraging behavior is observed, then there could be long-term effects and it may be necessary to extend the semi-field study (see 1.6.1) or conduct a full field study.
- A semi-field test may be used to validate or test a safe re-entry time for bees. Based on information gathered from a foliar residue toxicity study (see Chapter 8), a semi-field test can be used to provide additional information on the residual toxicity of a compound under more environmentally relevant conditions. For example, a semi-field study may provide information on the test compound residues, (*i.e.*, when residues are dry and therefore “safe” for bees). This information can be applied to risk mitigation
- If a pesticide is systemic and intended to be used as either a seed treatment, solid formulation (*e.g.*, granule or pellet), or soil treatment, then a semi-field study can provide detailed information regarding exposure levels both in the target crop and in the hive associated with the specific application parameters. Care is required in selecting of a study site to ensure that environmental conditions (*e.g.*, soil conditions (moisture, pH), duration from soil treatment to drilling and flowering) are appropriately representative of the proposed use. The study can also provide an indication of the likelihood of initial mortality and initial behavioral effects

Formatted: Font: (Default) Times New Roman, 12 pt, Not Bold, Italic, No underline, Font color: Auto

Formatted: Font: (Default) Times New Roman, 12 pt, Not Bold, Italic, No underline, Font color: Auto

following exposure. Since confinement may affect bee behavior *per se*, it is necessary to compare effects seen in treatment groups with those observed in the control. If there is a possibility of long-term effects resulting from this type of exposure, then it may be possible to modify this study appropriately (see 1.6.1) or alternatively it may be preferable to conduct a field study. It is also important to target the exposure position of the study (*i.e.*, the portion when the colonies are confined under an enclosure) with the time when the test plant is flowering and the highest expected residues are present in pollen and nectar.

- If the compound is an insect growth regulator, or exhibits insect growth regulatory characteristics, then a test according to Oomen *et al.* (1992) or a semi-field study over a 28-day period (OECD 75) can provide information on the potential effects on growth or development.

One of the advantages of a semi-field study, in comparison to a field study, is that it allows for the inclusion of a toxic standard (*i.e.*, one replicate is run with a test material that is known to elicit adverse effects to the test organism). However, since there are occasions where where it is not possible to use a toxic ~~reference chemical standard~~ (e.g., systemic seed treatments¹³), the absence of a toxic ~~reference standard~~ does not greatly compromise the utility of the test. When testing seed treatment scenarios, the residues on treated seed should be determined as well as residues in pollen and nectar; exposure to the bees is assumed as the test system is closed and exposure is cannot be avoided.

- Semi-field studies are also useful studies for non-*Apis* species such as *Megachile rotundata* as they may provide information on alternative routes of exposure, *i.e.*, leaves which are used for nest building, in addition to conventional routes of exposure such as nectar and pollen.

¹³ The lack of a toxic standard for a systemic seed treatment or solid formulation is due to the lack of a compound that causes known effects.

- It is possible to determine colony effects in a semi-field study over an extended period (e.g., for three months or longer) with species such as stingless bee and bumble bee colonies. For example, a bumblebee colony may be housed in a box with two connected chambers (one chamber for the colony's nest, and one chamber from which the colony may be fed (Kearns and Thompson 2001). The nest box may be opened and the colony allowed to forage outside in a semi-field enclosure. After this exposure period, the nest may be closed and the colony fed in the nest box's feeding chamber for a month or two to look at delayed lethal or sub-lethal effects on reproduction and colony growth. After a couple of months bumble bee colonies will switch from raising workers to raising drones and [REDACTED]. Similarly, one can expose foragers from a stingless bee colony for several days in a semi-field enclosure and then close up the nest box. The colonies in this case can then be fed by placing food (sugar water and vitamins) at regular intervals into the nest box. Stingless bees have perennial colonies (much like honey bees) and may be fed *en situ* for many months.

As noted above, semi-field studies address mortality from short-term exposure as well as short-term behavioral effects. However, there is a concern whether they are able to address, (i) long-term effects from either short-term/sub-lethal exposure or, (ii) long-term effects from long-term/continual (*i.e.*, via hive products) exposure or long-term chronic exposure.

Outline of a semi-field study for *Apis* and non-*Apis* bees

Design of a semi-field study for *Apis* bees

The following section is based largely on EPP0 170 (2010) and OECD 75 and should be seen as an extension of both guidance documents, and considered along with the details

of these guidances. In developing the elements of this chapter, the Workshop Participants relied upon their experience as well as information included in EPPO 170 and OECD 75. The aim of the following section is to highlight further issues to consider when planning and carrying out a semi-field study as well as issues that should be considered when evaluating a semi-field study for risk assessment purposes.

It is important that the aims of any semi-field study are clearly determined prior to the conduct of these studies. Clear problem formulation is required to ensure that the study is appropriately designed and focused to address the regulatory question(s) being asked. All semi-field studies should be designed to address specific concerns highlighted at lower tiers. EPPO 170 and OECD 75 are relatively flexible guidance documents and consequently allow studies to be designed to address specific issues. The considerations of the participants of the workshop, and of this chapter, do not remove or reduce that flexibility of the referenced EPPO or OECD documents, rather they highlight areas or elements that are thought to be important considerations for incorporation into a semi-field study.

Size of Semi-field Study

The minimum size of a semi-field study enclosure according to EPPO 170 is 40 m². Recommendations in this section are based on professional experience and are considered appropriate in terms of practicality of conducting the study and for determining effects of mortality and behaviour. However, this area is only appropriate in terms of certain field crops (*e.g. Phacelia*, oilseed rape/canola, mustard). For other crops (*e.g. melons, apples*) the area (40 m²) may need to be amended due to issues such as the number, density and attractiveness of flowers, availability of nectar and pollen or the size of the plants. The area of the test enclosure may also need to be amended depending upon the size of the colonies being used.

It should be noted that when studying bee brood, an increased [enclosed] crop area ($> 60 \text{ m}^2$) may be preferable to ensure the colony has access to adequate floral resources. However, the precise area depends on colony size, crop, and duration of confinement; 40 m^2 (OEDC 75) may be acceptable for a small colony that is confined for no more than 10 days.

Crop

The standard crops (*i.e.*, oilseed rape/canola, mustard and *Phacelia*) are easy to cultivate and manage but more importantly are highly attractive to honey bees. *Phacelia* has an open flower that it is highly attractive. The openness of its flower will mean that bee-relevant parts of the flower will be fully exposed to the spray application; hence, honey bees foraging after the spray application will be exposed to residues. Oilseed rape and mustard are both highly attractive to honey bees so a high level of exposure can be ensured. Results from studies carried out on these crops can be extrapolated to other crops, provided that the application parameters in terms of application rate, timing of applications and number of applications used on the surrogate crop(s) are comparable (ideally identical) to that of the subject product. If effects are observed on these standard crops then it may be possible to further refine the assessment by using the target crop species.

When considering systemic soil or seed treatments, it is preferable to use the actual/relevant crop. A crop other than the target crop needs to be justified on the basis of exposure (*e.g.*, it may be appropriate to select a crop that is attractive and has high residues in nectar and pollen as a 'model' crop rather than the actual crop of concern).

Size of Colony

Each tunnel/cage/tent should include one, healthy queenright (*i.e.*, a fertile, laying queen) colony per cage. Precise size of the colony used will depend upon the study design; EPPO recommends a size of 3,000 – 5,000 bees.

It is important to have sufficient nutritional resources within an enclosure to ensure that the bees do not starve. Generally feeding will not be necessary, however, if there is concern regarding the attractiveness of a specific crop/situation, then supplemental feeding may be needed. For example, if testing maize, then additional food will be required as maize produces no nectar.

Test Treatment

Sprays Only

Test treatment and water (negative) controls are required. Ideally, a positive control (e.g., a known toxicant standard) is also required. It is customary to test the proposed field rate only. If, however, a model crop is used, *e.g.*, *Phacelia*, then it may be appropriate to have more than one treatment rate. This may enable the data to be extrapolated to other crops and other application rates. Additional tunnels/cages could be used to address different application rates as well as effects from treating at different times of the day. However, at a minimum, a study at the maximum proposed rate should be carried out.

A positive (reference toxicant) control provides: (i) an indication of the sensitivity of the test system; (ii) demonstrates exposure; and, (iii) indicates the magnitude of response to a known toxin. However, positive controls kill bees unnecessarily and can add to the cost and complexity of study design; therefore, their use should be considered carefully. Positive control compounds are useful if it is unclear if any dose of the tested pesticide will have effects. If a positive control is used, it is necessary to select a compound whose toxicity profile is known and consistent with that under consideration, *e.g.*, for assessment of a potential acutely toxic

compound, then there is a need to use a similar compound. Historically, dimethoate has been used as a reference chemical when studying acutely toxic compounds on adult forage bees. If insect growth regulatory effects are expected, then a known insect growth regulator with similar effects should be used. When a positive control is used, there should always be clear effects. There should not be sustained mortality at high levels in the water control. There should be an appropriate number of replicates for the treatment group(s) to provide sufficient power to discriminate treatment effects with a level of precision.

For systemic solid formulation/seed treatments/soil treatments

While there is a need to have both a treatment and a water negative control, it is not possible at this time to identify a suitable positive (reference standard toxicant) control for oral systemic solid formulation seed treatments.

Pre-application

Sprays Only

Healthy colonies should be used and transferred to the test site a minimum of 2-3 days prior to treatment. This is due to mortality that inevitably occurs when a colony is moved and subsequently confined. If the hive is moved during the day, the hive will tend to acclimate more quickly. There should be a measurement of mortality over the acclimation period; the greater number of measurements of mortality will provide greater confidence that effects after treatment are attributable to the treatment rather than due to the hive acclimation. It is likely that there will be variability between colonies and every effort should be made to ensure that they are as consistent as possible. This can be partly be achieved by moving the colonies at the same time. Attempts should be made to make sure that the colonies are as similar as possible, in terms of number of bees, at the start of

the study. Excessive variation at the start of the study will make the study difficult to interpret and hence potentially limit its usefulness.

Further work is required to determine the range of background levels of mortality once the colony(ies) are situated at the test location in order to establish acceptable levels or ranges of mortality. These background levels could be used to help interpret whether the level of mortality observed in the treatment is treatment-related or not, providing an indication as to the overall reliability of the study.

With spray treatments the colony is placed in the semi-field setting when the crop is just about, or at flowering. The effects of the pesticide to honey bees foraging that crop are then determined. With systemic chemistries, there is a potential for exposure to occur over a longer period of time therefore, the honey bees should be present during the whole flowering period of the plant. Acclimation as outlined above is, therefore, not possible as exposure of the bees to the pesticide will occur as soon as they are introduced in to the treatment area. However, a consideration of mortality due to moving the colony is still required. One potential way around this problem is to compare the mortality that occurs with the untreated crop to that with the treated crop. Nevertheless, the significance should be determined statistically. Semi-field studies may be most effective for determining acute effects related to systemic chemistries. If sublethal effects are predicted, then a modified semi-field designed to ascertain any long-term effects, or simply a full-field test may be more appropriate (see below for details).

Post-treatment assessments

Assessments of mortality via the placement of dead bee traps, sheets, or tarps at the front of the hive and within the enclosure should ideally be carried out daily but at least on days 0, 1, 2, 4 and 7 post-treatment. This frequency is not

appropriate for in-hive assessments as the disturbance could cause significant effects.

Sub-lethal Behavioral Tests

There is a need to standardize and refine the number and type of tests or observations that can be made to document potential behavioral changes due to sub-lethal pesticide exposure. In these tests is typical to report whether abnormal behavior in foraging, or other behaviors occur during the test; but, definitive and meaningful quantifiable measures are often lacking. Rather than making general observations on bee behavior, it is proposed that more detailed measurements be made in addition to the general observations used to date. Of these perhaps the most obvious is in measuring foraging activity.

When measuring foraging activity, the number of returning foragers should be counted pre-treatment and at regular intervals post-treatment. The number of returning foragers with pollen loads should constitute a separate count from those returning without pollen (nectar and water foragers). Observations should last for 1 – 3 minutes. The observation periods should be equally divided across all test groups so that measurements are taken at approximately the same time with the controls as with treatments.

A second observation that could be quantitatively measured in a semi-field test is the average flower handling time. This measure is made by recording the time taken for the bee to work a flower (*i.e.*, to remove pollen and/or nectar). The observer simply records the total flower handling time for bees collecting pollen and nectar. If flower type is such that distinct pollen and nectar foraging is possible then these forager types should be kept separate. The exact number of required measurements should be determined or justified statistically. The time of day measurements are taken should be randomized between plots to avoid time of day and or weather bias. As with previous studies of this type, general

observations of any unusual bee behavior should be noted and quantified if possible (*e.g.*, 30 bees were seen twitching and exhibiting excessive grooming on the landing board during the 1-3-minute foraging counts). In addition, it may be possible to determine foraging behaviour in front of the hive.

Due to the confined nature of semi-field studies, it was the consensus of the Workshop Participants that an adverse effect on behavior compared to the control should be interpreted with caution and should trigger additional consideration. The relevance of an effect, or lack thereof, in a semi-field study may not be assumed to be directly translated to the field scale. Interpretation of effects, or lack thereof, must be done with care. Additional information could be obtained to aid interpretation of any effects seen. This information could come from a variety of sources, however the Workshop Participants considered that field studies were the most appropriate source to validate any effects or lack of effects that are considered significant.

Depending upon the regulatory question being asked, it may be necessary to determine residues in fresh pollen, stored pollen, nectar, honey, and wax. The type(s) of samples to be collected depends on the study and the questions to be answered. Residues in foraging honey bees may also be ascertained and this information could be used in interpreting potential incidents.

Results

Traditionally when determining if a study is acceptable, there is consideration of whether it has met various quality criteria, such as adequate controls, or chain of custody. In addition, there should be consideration as to how the study compares to the above guidance. The use of a toxic standard (reference chemical) can help meet the need for quality assurance measures, however, it is not essential for the reasons stated above.

Based upon the study objectives, key outputs from a standard semi-field study could be:

- Mortality in the crop: use of sheets or tarps in the crop.
- Mortality at the hive: use of dead bee traps or sheets in front of the hives.
- Foraging activity and other behavior: see discussion above.
- Measures of exposure: residues in pollen, nectar, pollen pellets, and dead bees.
- Pollination deficit: it may be possible to determine if there is a difference in the degree of pollination success (*e.g.* via fruit set) of the treated versus untreated crop.
- Assessment of the brood, including an estimate of adults, the area containing cells, larvae and capped cells, (if this is a key area then methods outlined in OECD 75 should be followed).

Design of a Semi-field Study for Non-*Apis*

At present there is no equivalent EPPO 170 or OECD 75 guideline for using non-*Apis* bees in semi-field or field studies. As a result, the Workshop participants suggest that if there is a regulatory question regarding a pesticide that requires the inclusion of a non-*Apis* species as a result of triggers activated by laboratory effects bioassays, the study design should be developed on a case-by-case basis with consideration of the specific endpoints described for semi-field honey bee studies and the overall regulatory question. Care should be taken when evaluating and interpreting results from these studies until protocols are sufficiently vetted through ring-testing.

When selecting non-*Apis* species to be used for semi-field studies, attention needs to be paid to their availability, ease of handling and survival under experimental conditions. Therefore, it is recommended that the species used are those that are either commercially available or can be readily reared under laboratory conditions.

Semi-Field Studies - Solitary Bees

Three solitary non-social bee species are recommended for use in semi-field studies in temperate zones: *Osmia lignaria*, *O. bicornis* and *Megachile rotundata* (Johansen *et al.* 1984; Tasei *et al.* 1988; Ladurner *et al.* 2008; Konrad *et al.* 2009). *Megachile rotundata* will be used as the descriptive species in this section.

Megachile rotundata, the alfalfa leaf-cutting bee, is a non-social Eurasian bee species that is widely managed as a pollinator of alfalfa for seed production in the U.S. and Canada, and is occasionally deployed for the pollination of other specialty crops (e.g., canola, carrot – for seed, blueberries). Dormant alfalfa leaf cutting pre-pupae are sold as loose cells in 4 L (gallon) increments (approximately 10,000 individual cells).

Due to standard field production cycles, dormant loose cells are usually only available from late fall through early winter. Cells should be maintained at 1.7 to 4.4°C and 50% relative humidity (RH) until natural emergence during early summer in most of the northern hemisphere. Bees maintained in cold storage beyond this point begin to deplete stored energy reserves and may fail to emerge upon incubation (210 total days is the general upper limit for diapause before viability declines significantly). Cells should be stored in open or ventilated containers and tumbled periodically to reduce the growth of molds. Bees can be incubated to adulthood with as few as 150 days of cold storage diapause. Careful control of temperature (*i.e.*, 29°C) and humidity (70% RH) will cause most of the incubated bees to emerge from their cocoons at approximately the same time (50% emergence in 23 days and complete emergence after 32 days).

Few release rates (density rates) exist for crops with the exception of alfalfa, where 74,000 to 100,000 bees per hectare are recommended, and canola and blueberries, where 50,000 bees per hectare (Mader *et al.* 2010a) are recommended. Release rates will vary based on size of enclosure and crop to be

utilized in the semi-field study but could be as few as 200-500 solitary bees per tunnel site of 40 m².

Site selection for the study should use the same criteria as those for semi-field *Apis* studies. Once an enclosure is ready, a wooden nest shelter containing enough styrofoam nesting boards to accommodate all the *M. rotundata* to be released for the study should be placed in the test enclosure (2 to 3 nest tunnels per bee), facing the morning sun, 3-4 days in advance of the initiation of the study (*i.e.*, before the pesticide is to be sprayed in the semi-field enclosure). Bees ready to emerge or already emerged should be placed in front of the nest shelter and left to orient to the nest. Bees should not require supplemental feed as long as there is sufficient crop in bloom. These bees do not require a water source so long as enough flowers or a nectar feeder is available. However, if mason bees (*Osmia lignaria*) are used, a drip bucket and excavated damp mud pit are needed inside a test enclosure (*i.e.*, tunnel) cage. The mud pit should be excavated so the bees can access the soil profile layer with the best clay-water content. Nectar is not sufficient for wetting mud.

Key Outputs

- Mortality in the crop: same as for *Apis*.
- Mortality in the hive/nest shelter: use of a tarp placed on the ground in front of the nest shelter may allow some assessment of *M. rotundata* mortality. However, solitary bees may die within the nest material, making mortality assessment more difficult. Assessment schedule should be the same as those for *A. mellifera*.
- Foraging activity: same as for *Apis*.

- Reproductive success (colony health): once it is known that the released female *M. rotundata* have successfully mated and started to provision cells (*i.e.*, individual cells/eggs are present or tunnels are sealed) assessments on increasing brood nest (*e.g.*, brood development) can begin. Nest boxes can be monitored on the first day once cell provisioning has commenced and continued on a weekly or bi-weekly basis. Count and mark completed tunnels. Observation nests (grooved boards with clear acetate or glass covering the grooves) can be used to observe nest, cell, and brood development without disturbing the bees. At 15.6°C (60°F) eggs of *M. rotundata* take 15 days to hatch and then an additional 35 days are required for the larvae to reach the prepupal stage. At 35°C (95°F) it takes 2-3 days for the eggs to hatch and 11 days for the larvae to reach the prepupal stage (Mader *et al.* 2010a). Therefore, if flowering of the study crop ends prior to either 14 days at 35°C or 50 days at 15.6°C, then the nest box needs to be removed from the study site and placed in a growth chamber that simulates the average temperatures experienced by the bees while they were in the enclosure. Once the prepupal stage has been reached, a segment of the styrofoam nest needs to be dismantled, and cells per tunnel counted and weighed, and then dissected to determine the number of cells with prepupae and those that are provisioned but with no larvae present. If there are no larvae present (*i.e.*, these cells are called “pollen balls”), it indicates that larvae have died in the first or second larval instar, which may be related to exposure to extreme temperatures (cold and hot) during that stage in development (Mader *et al.* 2010a). The remaining styrofoam nest sections can be dismantled, cells counted and then placed in storage at 2-5°C (35-40°F) at 50%RH until the following spring. At that time, the diapause can be broken and the number of emerged adults can be counted and compared to the total number of cells. This allows for determination of mortality in progeny (sub-lethal effects).

Semi-Field Studies – Social Non-*Apis* Bees

Bombus sp. will be used as the descriptive species in this section.

Bumble bee colonies are readily available from commercial sources¹⁴. [REDACTED]
[REDACTED]
[REDACTED] (Morandin *et al.* 2001) of tomatoes, yet should also perform as well as a honey bee nucleus hive in a smaller enclosure (40m² to 60m²). The 40 m² to 60 m² foraging area, and considerations for supplying alternative forage (*e.g.*, nectar or pollen) are relevant considerations for bumble bees, as they are for honey bees. In addition, feeding bumble bee colonies can be done in a much more controlled way than *Apis*. When *Bombus* are commercially reared they are fed in the nest, and the same could be done for colonies used in a semi-field test. Colonies should be provided with identical amounts of supplemental pollen and/or nectar, helping to minimize differences between treatments. Also, when changing food stores, the pollen or nectar that was not consumed can be removed and weighed in order to determine how much the colony consumed. A colony population of at least 100 workers and a queen should be used for semi-field studies, and exposure duration should be ten days followed by supplemental feeding. If the colony is movable, then it may be appropriate to move it to a non-agricultural and pesticide-free landscape to continue development outside the tunnel, rather than keep them inside the tunnel with artificial food.

When extracting bees for sampling, or for mark and release, it is necessary to distinguish the queen (usually the largest bee) from the workers. Harm to the queen is likely to result in defensive behavior on the part of the workers and a rapid reduction in colony lifespan. Similarly, it may be desirable to distinguish between male bees and female workers. In general, male bumble bees have larger

¹⁴ Worldwide, different bumblebee or alternative social non-*Apis* species are commercially reared for pollination purposes and, therefore, in most regions will not require import procedures (Mader *et al.* 2010b).

Formatted: Font: (Default) Times New Roman, 12 pt, Not Bold, Italic, No underline, Font color: Auto

eyes, longer antennae, no pollen baskets (corbiculae), and, depending on the species, may have a notable patch of yellow hair on the front of their face.

bees to each colony should be approximately equal and workers per colony should be equal to the semi-field study enclosure with entrances closed in the morning. Each colony should be placed on a concrete block with the entrance facing the morning sun. This should be done 2-3 days prior to the initiation of the study.

Key Outputs:

- Mortality in the crop: same as for *Apis*.
- Mortality at the hive: same as for *Apis*. A small tarp can be placed under the colony extending outward from the entrance so that any dead adults or drone larvae discarded by the colony can be counted over time. The tarp should be cleaned of all discarded adults and drone larvae after each assessment. Endpoints such as discarded dead adults and drone larvae are indicators of colony condition.
- Foraging activity: same as for *Apis*.
- Reproductive success (colony health). Prior to placing colonies in the semi-field enclosure a (close-up) photograph should be taken of the brood nest and food stores through the plastic inner cover at night when most of the bees are back in the nest. The photograph should be labeled with date and time and assessed for presence of brood in all phases of development by marking the cells with a marker on the photograph.

Semi-Field Studies – Stingless Species

The stingless bees Meliponini consist of approximately 24 genera of bees with around 400 species (the number is not clear as many species still remain to be described). They are important social bees in the subtropics and tropics (Nogueira-Neto, 1997). Meliponini occur mainly in Neotropical America, Australia, Indonesia, Malaysia, India and Africa (Proní, 2000). These bees are and have been important cultural components of many communities in the tropics and they are managed for their pollination services and honey production.

Stingless bees have varied nesting sites, from aerial parts of trees to underground. They differ from *Apis* spp. in that their combs/cells are arranged horizontally and are mass provisioned by the nurse bees with nectar, hypopharyngeal gland secretions and pollen before the queen lays the egg after which the cell is closed. Full development to the adult takes place within these cells without any further input by the nurse bees; hence each cell is representative of the conditions that existed during the construction and provisioning of the cells. A newly emerged bee destroys its cell immediately. Honey and pollen stocks are usually stored at the periphery of the nest with the brood in the middle of the colony. However, the arrangement of the brood and storage pots varies between species and for many species these details remain unknown. It is believed that the adult workers have a similar life span to that of *Apis mellifera*, that is, they live 30 to 40 days.

Meliponini range in length from 1.8 to 13.8 mm (Michener, 2007) and, because of this, the choice of the species is important for risk assessment tests. ~~One of the easier species to be managed and rear in a laboratory is *Melipona scutellaris* (Uruçu ??? year of publication). For example, in the past few years, *Melipona scutellaris* has been tested in greenhouses on tomato plants. In tropical areas some species such as *Trigona carbonaria* live and/or are managed in semi-domesticated situations.~~

Formatted: Strikethrough

Individual bees or the inner colony are easily accessed for testing. Individual bees can be chilled for several minutes in a freezer to slow their movement for ease of handling (the entire hive box should not be chilled). Heard (1999) and others have developed various hive box systems that can be used to manage these bees. See Table 3-1 for a list for a list of species and references for non-apis species that have been employed in laboratory and/or field tests.

As regard to size of semi-field study, it is proposed that the approach used for the honey bee be adopted for the stingless non-*Apis* species.

Key Outputs: Details are similar to *Bombus* above.

Interpretation of Effects in Semi-Field Studies

As stated at the outset of this chapter, the interpretation of effects (*i.e.*, a statistically and/or biologically significant difference from the control) is linked to the protection goals and, in particular, whether the results indicate that protection goals are likely to be met or not.

If the protection goal is pollination activity and/or function, then a semi-field study with measurements of foraging activity is capable of determining whether pollination activity is related to treatment. If there is an adverse effect on foraging activity in the semi-field study, then further information is required to determine whether the effects are realized at the field level. It was the view of the Workshop Participants that this would be best addressed via a field study. Alternatively, consideration of risk mitigation may be elements of consideration in determining how to proceed.

If the protection goal is honey production, then the results from a semi-field study can be interpreted as follows:

- If effects are clearly *not seen* on any parameters then it can be inferred that there will be no impact on honey production at the field scale when full-sized colonies are exposed. This assumes that long-term effects from short-term exposure are not an issue.
- If effects *are seen* or observed, *e.g.*, mortality or reduction in foraging or behavioral effects, then it may not immediately be assumed that honey production will be adversely impacted at the full-field scale. Since the semi-field test is potentially a worst case exposure scenario, the assessor needs to determine whether similar or any effect(s) would be realized at the full-field level and hence whether honey production could be impacted.

If the protection goal is maintenance of biodiversity in terms of the ecosystem service of pollination by other non-*Apis* bees, then no negative impact on populations is the protection goal. Semi-field studies showing statistically significant effects that are expected to result in high levels of mortality should be considered for more refined field studies¹⁵.

Assessment of the Variability and Uncertainty in an *Apis* Semi-field Study

As with any experimental testing, there are sources of variability and uncertainties associated with the studies. Confining organisms to a restricted study environment can confound efforts aimed at reflecting more environmentally realistic conditions. In Table 9-3, some of the sources of variability and uncertainty are discussed. To the extent that researchers can recognize and limit these potential confounding effects, the data

¹⁵ In determining whether the protection goal of maintaining biodiversity has been met, it is necessary to determine whether it is possible to extrapolate from studies on one non-*Apis* species and conclude whether the pollination services (and any other services) that are supplied by non-*Apis* bees have been adversely affected. Further work is required to develop an appropriate risk assessment scheme around those goals and hence address issues such as the potential to extrapolate from one non-*Apis* species to others.

5432 generated from semi-field studies will likely improve, as well as their utility in regulatory
5433 decision making.

5434

5435

5436 **Table 9-3. Variability and Uncertainty in Semi-field Studies with *Apis mellifera***

Parameter	Discussion of uncertainty
Enclosed population of bees	<p>Under natural conditions, bees are free flying; enclosing them introduces a stressor that could lead to uncertainty in interpreting the results from a semi-field study.</p> <p>Enclosing bees in a semi-field setting causes two main issues, which may raise uncertainty when interpreting the results – (i) effects on behavior and (ii) availability of food and therefore, on foraging activity.</p> <p>Food availability and foraging issues can be addressed through design considerations to ensure sufficient food is available. This can be achieved by balancing the size of the colony with the size of the enclosed crop. Details regarding possible colony size and area of crop combinations are discussed above. Providing a study designed to ensure that ample food is readily available and that there are comparable controls should account for this potential confounding variable.</p> <p>Enclosing the bees in a semi-field setting could translate into behavioral effects, which could reduce exposure. For example, some bees will try to forage outside and as a result remain on the tent/cage wall rather than in the treated crop. It is not known what proportion of bees will exhibit this behavior. If the compound does not exhibit repellency effects on bees, it is thought that the same proportion of bees will potentially exhibit this characteristic in the controls as in</p>

Parameter	Discussion of uncertainty
	<p>the test groups. As there will be a proportion of bees that will not be exposed then this could potentially <i>underestimate</i> the risk. However, it is also not known what proportions of bees in the field are not exposed to the pesticide, <i>i.e.</i>, the proportion that will forage elsewhere. Provided that the population size is measured as a parameter, significant differences in comparison to controls indicate whether it is treatment related or not. It is considered that on the one hand exposure is confined and controlled; however, there will be a proportion of bees that try to forage elsewhere. Overall, participants of the Workshop believe that this parameter is likely to over-estimate potential risk, <i>i.e.</i>, it will be worst case.</p>
Size of colony	<p>The colony of bees that is used in semi-field studies is small compared with those used in the field; and the way that a small colony reacts is different than the way full-size colonies react. Extrapolating effects related to mortality and sub-lethal behavior from a small colony to a standard colony is uncertain and should be approached with caution. Due to this uncertainty, if any effects are noted then further studies should be considered.</p>
Measure of mortality	<p>Due to the confined nature of the study it is likely that a semi-field study will yield a relatively accurate assessment of mortality. This is in contrast to the field, where detecting an accurate level of mortality within the crop is more difficult.</p>
Density of bees in the treated crop	<p>It is likely that the density of bees will be higher in a semi-field study compared to the field study. Due to the potential higher density of bees in a semi-field study compared to the field situation where alternative sources of food will be available, it is considered that bees are likely to have a higher level of exposure in a semi-field study, and therefore a semi-field test potentially over-estimates any effect.</p>
Representativeness	<p>It is unlikely that there will be a study to represent every crop and</p>

Parameter	Discussion of uncertainty
of the study site, agricultural practices and conditions	geographical and agricultural combination being considered in the specific regulatory context. Hence, there will be uncertainty regarding the representativeness of the selected study site in comparison with possible combinations under regulatory consideration. Ideally the study site, in terms of weather, flower availability and forage, should be designed to ensure that the bees are exposed. Uncertainty regarding the representativeness of the crop will be reduced if a surrogate is chosen that ensures that bees are suitably exposed. Addressing uncertainty based on agricultural and geographical variability is more problematic.
Residues in pollen and nectar	For pollen and nectar residue sampled from the plants, there is no reason to believe that these should vary any more or less than what would occur under field conditions, with the exception of no or limited exposure to rain (wash-off), wind or dew. Typically, semi-field studies have some latitude to make applications during periods of good weather. If poor weather is anticipated, then applications may be delayed several days provided the colonies are not already in the enclosure. However, semi-field studies are intended to reflect real world conditions, and if it rains, then such studies can still provide useful information. Typically, residue studies are conducted on the treated plants and in pollen/nectar to ensure that some level of exposure is achieved and the results are expressed relative to these residues.
Collected nectar, pollen pellets, bee bread and dead bees	Regarding nectar, there may be a high turnover rate (foragers) in a semi-field study and therefore there may be difficulties in extrapolating this information to the field situation. Pollen and associated residues should be representative of what is likely to occur in the field and therefore the uncertainty associated with this parameter is low. Beebread is difficult to collect in a semi-field study and the study has to be managed to ensure that this occurs.

Parameter	Discussion of uncertainty
	There is, therefore, some uncertainty regarding this parameter compared to what would happen in the field. Uncertainty exists if the study is extrapolated to other crops, for example if one crop produces pollen and nectar whereas another species produces only pollen.
Assessment of the brood	This is possible only via OECD 75 and associated procedures.
Overall	Due to the confined nature of the semi field study, there is high confidence that exposure will occur compared to a full-field study. It is also likely that any adverse behavioral effects will be seen. Therefore, if either increased mortality compared to the control or behavioral effects are not observed then it is considered highly likely that these will not occur in the field. Uncertainty exists regarding the potential effects on brood development; however, it is considered that this will lead to potential overestimation of the risk. Due to the duration of the exposure in the semi-field study, determination of long-term effects requires special consideration.

5437

5438

5439 Design of a Field Study

5440

5441 When would a field study be appropriate?

5442

5443 Field trials may be carried out if an acceptable risk is not estimated by either lower tier
5444 tests or the proposed risk mitigation is undesirable. Questions to be answered from a
5445 field test should be based on the results of lower-tier studies, whether laboratory or semi-
5446 field. For example, if behavioral effects are observed in a semi-field study, it may be
5447 desirable to see if these are observed under more realistic field conditions. It may also be
5448 more appropriate to conduct a field study where a semi-field study is not considered to be
5449 appropriate (*i.e.*, it is not necessary always to follow the tiered approach). For example, it

may be relevant when there is the likelihood of long-term effects following short-term exposure. As with any test involving animals, the need for and intent of the study should be clearly articulated. This is particularly true for field pollinator studies given the number of variables that must be managed, and the considerable resources they require both on the part of the regulated community to conduct the study as well as the regulatory authority tasked with reviewing the study.

Outline of a Field Study for *Apis* and Non-*Apis* Species

Design of a Field Study for *Apis mellifera*

Field trials can be used to address a range of exposure scenarios and effects. The results can be used by the risk assessor to determine whether significant uncertainties have been sufficiently addressed and if the protection goals may be met. However, there are various strengths and weaknesses of field studies that need to be considered before they are used in risk assessments intended for use in a regulatory context. In Table 9-4, the strengths and weaknesses of the field study are listed. Qualities of the field study, with respect to either *Apis* or non-*Apis* bee species, are relatively generic and so are listed together in one table.

Table 9-4. Strengths and Weaknesses of Field Studies for Both *Apis* and non-*Apis* Bee Species

Strengths
Provides a realistic exposure scenario of bees foraging on a crop, provided test plot size is sufficient
The realistic exposure scenario is likely to allow realistic behavior of the bees
Can be designed to be consistent with good agricultural practice/grower standard practice.
Can be designed and used to assess longer-term exposure and effects (see below)

Ecologically (field level effects) and biologically (standard size colonies) more relevant than lower-tier studies
Measurement of certain protection goals can only be, or are more accurately, determined in field studies (e.g., pollination deficit or honey production) assuming that lower tier studies are insufficient to this end.
Weaknesses
Difficulty in finding appropriate sites, <i>i.e.</i> , there are practical issues in finding a site that is sufficiently isolated from other potentially attractive crops/pesticide treatments.
Because field studies are open, controlling nutritional sources may be difficult as bees may not forage exclusively within the treated field.
Expensive to establish treatment area of a size suitable for indicating "worst case" exposure. Field studies are logistically complex and are expensive since so many factors must be accounted for.
Potential difficulty related to background levels of pesticides in the foraging area.
Difficult to use toxic standard which in turn potentially raises concerns regarding sensitivity of the test system.
Potential high level of variability including weather, mortality away from the hive, replication and interpretation of results

5471

5472

5473

5474 **Study Design Considerations**

5475

5476 *For all types of application (i.e., spray, systemic solid formulation/seed*

5477 *treatments/soil treatments applications)*

5478

The study should use colonies with a minimum of 10,000-15,000 foraging bees. Colonies should consist of 10-12 frames and include 5-6 brood frames. If colonies are of a different size then they should be evenly distributed between treatments. According to EPPO 170 an area of 2,500 – 10,000 m² (0.25 - 1 ha) is recommended with a larger area proposed if the crop is not particularly attractive (e.g., 0.25 ha for *Phacelia* and 1 ha for mustard and oilseed rape). EPPO 170 also recommends that there should be a minimum of 4 colonies per field. It may be appropriate or necessary depending upon the regulatory question being asked, to consider the use of larger field sizes as this may provide a greater degree of realism when compared to the eventual use of the product. If larger fields are used, then more colonies may be required, depending upon the attractiveness of the crop. It is important to determine, from scientific literature, the proper colony loading rates based on crop and size of field. In determining the size of individual fields, consideration must be given to the total number of treatments (*i.e.*, the treated crop) and replicates per treatment (*i.e.*, colonies per treated field).

While it is potentially desirable to use a positive control in a semi-field study, it is discouraged in a full-field study. This recommendation is based on extensive discussion among the ICPBR and EPPO. A negative control, however, is always required.

Participants of the Workshop agree that bees generally tend to forage on sources close to the colony, but that some bees will forage further afield and these individuals could bring additional residues into the colony. Consequently, in order to ensure adequate isolation from other sources of pollen and nectar, the site should be located at least 2-3 km from alternative cultivated agricultural sources of pollen and nectar, including pollen and nectar from orchard trees. As regards confirming exposure, the following measurements should be considered:

- Bees/m² – at least five bees per m² on *Phacelia* spp. or 2-3 bees per m² on oilseed rape and mustard (EPPO 170). These are potentially only relevant

for these crops and EU conditions and should be used with caution in other regions. It should also be noted that these densities are related to the number of colonies and size of treated area.

- Pollen identification – it is recommended to have additional colonies with pollen traps fitted. Identification of pollen can be difficult and sometimes identification only is possible to family level.

If appropriate, there should be an assessment of the degree of flowering, *i.e.*, the proportion of the crop actually in flower at any one time *e.g.*, BBCH 60 onward for oilseed rape (see [[HYPERLINK "http://pub.jki.bund.de/index.php/BBCH/article/viewFile/470/420"](http://pub.jki.bund.de/index.php/BBCH/article/viewFile/470/420)] for further details). This is particularly relevant for crops such as melons. Under certain conditions, it may be possible to manage the crop to prolong flowering so that a longer exposure period could result.

For systemic compounds, it is not possible to identify a suitable positive (reference) standard. In addition, similar to considerations with systemic compounds under a semi-field design, exposure will occur over a longer time. Therefore, the honey bees should be present during the whole flowering period of the plant. Acclimation to the pesticide will occur as soon as they are introduced in to the treatment area. However, a consideration of mortality due to moving the colony is still required. One potential way around this is to compare the mortality that occurs on the untreated crop to that in the treated crop.

Pre-application

For all application types. pre-application considerations are similar to that for semi-field studies. Refer to these sections above.

Post-treatment assessments

All types of application (i.e., spray, systemic solid formulation/seed treatments/soil treatments applications)

Depending upon the regulatory question being asked, it may be necessary to assess behavioral effects in the field. Mortality, however, should always be determined. While this may be done via the use of dead bee traps, these may not always be appropriate, in which case sheets or tarps outside the hive should be used.

A key issue with field studies is ensuring that sufficient exposure occurs. If possible, studies should be designed to minimize alternative forage. However it is inevitable that there will be some alternative sources present. In order to determine whether exposure has occurred, there is a need to monitor the activity of bees within the treated crop. This can be done in several ways.

- Measuring forage activity:

- See previous discussion on measuring foraging activity, (See similar discussion under the semi-field section)

- Measuring flight activity: aided through the use of marked bees

- Identifying pollen from outside the colony
- Measuring residues in pollen and nectar in bees and inside the colony.
(Closely related to this point is whether the exposure that has occurred will be representative of the wide-scale use of the pesticide.

Results

The following measurement endpoints and outputs are possible from a field study:

- Colony strength: ascertained through measurements of foraging activity, flight activity and number of dead bees.

- 5571 ○ Weight of the hive
- 5572 ○ Pollen, honey and nectar stores: ascertained through measurement of
- 5573 percent comb coverage.
- 5574 ○ Mortality at the hive: ascertained through measurements with dead bee
- 5575 traps or collecting sheets
- 5576 ○ Mortality of drones and pupae: ascertained through visual inspection of
- 5577 frames
- 5578 ○ Mortality in the crop: ascertained through collection sheets in the
- 5579 treatment site.
- 5580 ○ Presence of the same queen
- 5581 ○ Foraging activity in the crop: measured in the test crop, or at the hive
- 5582 entrance where it can be recorded automatically
- 5583 ○ Returning foraging bees: can be counted automatically at the hive entrance
- 5584 ○ Behavioral abnormalities
- 5585 ○ Measurement of residues in pollen/nectar, or via pollen pellets, as well as
- 5586 in wax, beebread and dead bees: measurements of exposure inform
- 5587 assessment of risk.
- 5588 ○ Assessment of the brood: see EPPO 75; this measurement may also
- 5589 include an estimate of the number of adults, the area containing cells,
- 5590 eggs, larvae and/or the capped cells
- 5591 ○ Disease and/or pest levels
- 5592

5593 **Long-term Risk to Honey Bees from Short-term Exposure**
5594

5595 If potential overwinter effects are identified during the problem formulation step,
5596 then it is proposed that the field study be modified in order to examine
5597 measurement endpoints that will address this uncertainty. (Generally, field
5598 studies are more appropriate to assess the impact of overwintering than extended
5599 semi-field studies.)
5600

If a field study is to be conducted to determine whether the use of a product has any adverse effects on overwintering survival, then it is proposed that in addition to the considerations discussed above, the following points are also considered:

Following the exposure phase, the colonies (treatment and controls) should be re-located to an area that has limited, or no agricultural crops but an abundance of natural vegetation. This is necessary to ensure that exposure to additional pesticides does not occur.

At the end of the winter period, it is proposed that the following assessment endpoints should be determined, (the exact endpoints however, will depend upon the issues highlighted in the problem formulation).

- Condition of the colonies/colony strength,
- Brood development,
- Brood assessment, including:
 - Number/density/pattern of brood
 - Presence of healthy egg-laying queen
 - Estimate of pollen and nectar storage areas
 - Estimate of areas containing eggs, larvae and capped cells
- Analysis for disease, (*e.g.*, *Nosema apis*, *Varroa destructor*, American foulbrood, bee viruses)
- Weight of the colonies
- Residue samples from the hive (*e.g.*, pollen, wax, honey, bees)

Interpretation of Effects

As for semi-field studies, the interpretation of effects is linked to the protection goals. It should be noted that while a full-field test is the highest tier of testing it is important that final determination of potential risk and whether the use of the

compound is consistent with protection goals should be based on the entire body of evidence across all tiers.

If the protection goal is pollination activity or pollination function, then the full-field study is capable of determining whether this is achieved via use of measurements on (i) foraging (which can include foraging for nectar and pollen), (ii) behavior and, (iii) mortality. If no effect is observed on any of these parameters then the protection goal will be met. If effects are seen on any of these parameters, it may be unlikely that the protection goal will be met. Risk mitigation measures may enable the protection goal to be met; it is, however, essential to ensure that an assessment of the appropriateness and practicality of the risk mitigation measure(s) can be made, and that the protection goal is met. (It should be noted that none of the measurement endpoints directly measure pollination activity *per se*, but are surrogate measures and indicative of pollination activity. That is, in using foraging activity it is assumed that a decrease in foraging activity will result in a decrease in pollination *e.g.* decreased fruit set.)

If the protection goal is honey production by the colony, then this study can provide useful information. For example, if there are clearly no effects (either biologically or statistically) then it can be inferred that there will be no impact on honey production. If significant effects are observed over the course of the study, then it may be appropriate to explore risk mitigation measures to determine whether the protection goal of honey production can be met.

Design of a Field Study for Non-*Apis* Bees

Given the lack of investigation into a field level test for non-*Apis* species, it is assumed that all non-*Apis* bee testing will be in conjunction with field studies that are designed primarily for *Apis* bees.

Outlined below are draft protocols that could form the basis of field studies conducted to address specific regulatory questions.

Field Studies - Solitary Bees:

Megachile rotundata will be used as the descriptive species in this section. It is also important to note that *M. rotundata* and *Osmia* sp. have a very restricted foraging range (approximately 300 m) compared to that of *Apis mellifera* (2-3 km); therefore, it is much easier to ensure that their foraging will be restricted to the crop at the study sites.

Preparation of *M. rotundata* for these studies should be undertaken using the same maintenance and handling protocols described for *M. rotundata* in the semi-field study.

Key outputs include mortality (in the crop and at the hive/nest) foraging activity, and reproductive success (as a measure of colony health). Assessment of these endpoints is similar to that for *Apis* tests (see above).

Field Studies – Social Non-*Apis* Species

Bombus sp. will be used as the descriptive species in this section. It also is important to note that *Bombus* sp. have a much more restricted foraging range (400-750 m) (Knight *et al.* 2005) than *A. mellifera* (2-3 km) so it is much easier to assure that their foraging will be restricted to the crop at the study sites. Preparation of *Bombus* sp. for these studies should be undertaken using the same maintenance and handling protocols described for this species group in the semi-field study.

Key Outputs

Key outputs include mortality (in the crop and at the hive) foraging activity, and reproductive success (as a measure of colony health). Assessment of these endpoints is similar to that for *Apis* tests (see above).

5692

5693 **Field Studies –Stingless Species**

5694

5695 Stingless bees (Meliponini) have a social life similar to the honey bees albeit in much
5696 smaller colonies. There is an increasing body of literature (Heard 1999, Amano 2004)
5697 showing the value of stingless bees in pollination of crops in tropical and temperate
5698 countries. The stingless bees are native to tropical and subtropical areas, and more than
5699 400 species having been recorded from these regions. The ease of handling these species
5700 (small colony sizes, and hesitance to sting) makes them ideal candidates for pollination in
5701 greenhouse conditions. However, in terms of their use for pesticide tests, there is very
5702 little information and thus the information below should be taken as a guide with
5703 allowances for improvement. It is expected that this guidance document will create
5704 interests among the practitioners to develop and validate methods and create a forum for
5705 revisions in the future, if required.

5706

5707 **Hives**

5708

5709 Hives for stingless bees are box-shaped (commercial units) but smaller compared to those
5710 of honey bees. They do not have frames but rather are hollow, containing the whole
5711 colony component. Opening the hive therefore should be done gently to avoid
5712 damaging/destroying the nest structure. (Honey and pollen are stored in pots made of
5713 beeswax. The pots are typically arranged around a central set of horizontal brood combs.)
5714 When the young worker bees emerge from their cells, they tend to remain inside the hive,
5715 performing different jobs. As workers age, they become guards or foragers. Unlike the
5716 larvae of honey bees, meliponine larvae are not fed directly. The pollen and nectar are
5717 placed in a cell, an egg is laid, and the cell is sealed until the adult bee emerges after
5718 pupation (*i.e.*, mass provisioning). At any one time, hives can contain 300-80,000
5719 workers, depending on species.

5720

5721 Stingless bee colonies can be purchased from beekeepers that specialize in stingless bee
5722 production and management. Stingless bees that are currently commercially available in

tropical countries include, but are not limited to: *Melipona beechei*; *M. quadrifasciata*;
Trigona carbonari; *Tetragonula fuscobalteata*; *Scaptotrigona bipunctata*; *Tetragonisca*
angustula; *Meliponula ferrugenea*; *Hypotrigona gribodo*; and, *Meliponula bocandei*.
See Non-*Apis* chapter (Chapter 3) for details on which species are appropriate for specific
countries.

Care should be taken to acquire strong colonies with sufficient workers, each with about
10,000 healthy foragers; however, this will depend upon the species used. Up to eight
colonies per ha may be used. Stingless bee hives can be placed at strategic positions
similar to operating with honey bees (*e.g.*, either in the middle or edge of the field); and,
hives should be sheltered with a wooden cover placed on top of the hive to avoid direct
rainfall on the hive.

Stingless bees have a wide foraging range, foraging up to 2.1 km (Kuhn-Neto *et al.*
2009), but on average they restrict their activity to within 1 km of the colony. The
isolation distance from other forage sources recommended for honey bees (2-3 km) can
thus be used.

The number of individuals per hive and per unit area recommended for honey bees can
also be applied to the stingless bees. However, noting that there have been no field tests
of this kind done for stingless bees, there is a research need to validate the protocol.

Treatment Application, Sampling, Data Analysis and Interpretation:

Same as for *Apis*

Key Outputs:

The end points for the stingless bees in the field tests are similar to the honey bees and
include:

- Colony strength

- 5753 • Hive weight
- 5754 • Pollen, honey and nectar stores
- 5755 • Mortality at the hive (via the use of dead bee traps or collecting sheets)
- 5756 • Mortality of drones and pupae
- 5757 • Mortality in the crop
- 5758 • Presence of the same queen
- 5759 • Foraging activity in the crop
- 5760 • Returning foraging bees
- 5761 • Behavior
- 5762 • Residues in pollen, nectar, pollen pellets, wax, bee bread and dead bees
- 5763 (i.e., measures of exposure)
- 5764 • Assessment of the brood (including an estimate of adults, the area
- 5765 containing cells, eggs, larvae and capped cells)
- 5766

5767 **Assessment of the Uncertainty in a Field Study**

5768

5769 Unlike lower-tier studies with insect pollinators, environmental conditions are far less
 5770 easy to control in full field studies. Additionally, although sources of variability and
 5771 uncertainty may exist, there may be fewer options available for researchers to address
 5772 these issues under full field conditions. While many of the options available for semi-
 5773 field studies may apply to full field studies, the logistics of stratifying designs and
 5774 increasing the number of replicates become logistically difficult to implement. Table 9-5
 5775 highlights uncertainties associated with field level studies with both *Apis* and non-*Apis*
 5776 bee species.

5777

5778 **Table 9-5. Variability and Uncertainty in Field Studies with *Apis* and non-*Apis* Bee**
 5779 **Species.**

Parameter	Discussion of uncertainty
Exposure	Uncertainty of exposure should be minimized by proper location of the site in relation to other foraging sites, ensuring that the target

Parameter	Discussion of uncertainty
	crop is maximally attractive to bees. Determination of exposure can be made through measurements (as discussed above for <i>Apis</i> species). As with <i>Apis</i> tests, it is essential that there is information on the degree of exposure in determining the usefulness of the study.
Location of site(s)	The location should be relevant for the crop and environmental conditions (climatic, botanical and edaphic) both when and where the study is conducted. The likely reality is that tests cannot be conducted for all crop/formulation/geographic combinations and so there may be uncertainty when extrapolating the results. The uncertainty could over- or under-estimate the risk depending upon the actual study in question and the uses/situations to which it is being extrapolated.
Difference between the treatment areas and the controls	It is possible that the control and the treatment areas may differ both in terms of climate and edaphic conditions. Any differences in the testing environment (<i>i.e.</i> , vegetative surroundings, climatic, or soil conditions) should be minimized.
Extrapolation between different varieties and sub-species of bee	Only one bee species or subspecies will be tested in one study. Uncertainty will exist when extrapolating inter-species, but may also exist when extrapolating intra-species. For example, while there is information indicating that effects on <i>Apis mellifera mellifera</i> and <i>Apis mellifera carnica</i> are minimal, <i>i.e.</i> , they are of relatively similar sensitivities, the differences in sensitivity between <i>Apis mellifera scutellata</i> and subspecies of European honey bee are unknown, and <i>Apis mellifera scutellata</i> may be more or less sensitive than the European honey bee.
Mortality away from the hive	Measurement of mortality away from the hive will be difficult and therefore there will be much uncertainty in this parameter. It would not be reasonable to expect that any measurement endpoint can be thoroughly documented and in most cases, the best the study can do is detect relative differences between control and treated colonies.

Parameter	Discussion of uncertainty
	Dead bee traps are likely prone to the same biases in control and treated fields. It might be argued that predatory/scavenger insects may be reduced in treated fields relative to untreated fields and that there is a lower likelihood that dead bees may be removed from traps whereas in control fields greater scavenging may occur, making it appear as though mortality was lower in the untreated field. This underscores the need to calibrate dead bee traps to determine the efficiency of recovery. This parameter will potentially underestimate any level of mortality. However, other measurements, <i>e.g.</i> , colony health (strength and weight), will provide an indirect measure of mortality (<i>i.e.</i> , if much mortality occurs away from the colony then it is likely that the overall hive health/colony development etc will be adverse affected.)
Overall	A field study is an assessment of the potential effects on the colonies under more realistic climatic, botanical and growing conditions. There are uncertainties regarding the degree to which bees are exposed, although the resulting exposure is likely to represent more normal conditions than those in a semi-field studies. There are uncertainties regarding the sensitivity of the bees tested as well as extrapolating the study to other sites, situations and crops; however, these should be assessed on a case-by-case basis.

5780

5781

5782 **Role of Monitoring and Incident Reporting**

5783

5784 Some countries have incident monitoring schemes aimed at providing information that
5785 can inform regulatory decisions. These schemes provide some feedback on the quality
5786 and accuracy of regulatory decisions and, therefore, by association elements of that
5787 decision such as measurement endpoints, assessment endpoints, up through protection
5788 goals. In addition, some regulatory authorities require monitoring of bee colonies as a

condition of registration where there is uncertainty whether the risk, or the risk mitigation meets the protection goals.

Monitoring schemes, for example the UK Wildlife Incident Investigation Scheme (WIIS), rely on incidents being reported to a central organisation. This scheme has provided much information on incidents associated with correct use, accidental incorrect or misuse, as well as abuse of pesticide products. These data, along with usage data, have been useful to determine the appropriateness of various regulatory restrictions as well as to provide information on the appropriateness of the regulatory trigger values (see Aldridge and Hart, 1993, and Mineau *et al.*, 2008). In North America (under the USEPA system) pesticide registrants are required to report [adverse] incidents or adverse impacts from the use of their compound/product(s) when they become aware of them. Other stakeholders may also report incidents to the USEPA.

These schemes do, however, have limitations in that they rely on the public to both find an incident and to report it. This can potentially lead to under-reporting if the beekeepers fear retribution, or the citizen is unaware of the process of reporting. The conditions of commercial agriculture versus that of native wildlife bias reporting toward *Apis mellifera*. Consequently, incidents involving non-*Apis* bee species may be under recorded. Nonetheless, monitoring schemes are a useful tool to the regulator to better understand the use and effects of pesticide compounds. Cost-effective reporting schemes need to be developed that provide incentives to applicators to help increase reporting of experiences from the field. This is critical for improving risk assessment and mitigation.

Summary

Semi-field and field studies for *Apis mellifera* are key components of the risk assessment process. They permit a further, more realistic and representative assessment of the potential risk and impacts from the use of pesticides. Due to the fact that these studies are higher tier, there are no standard guidelines available as there are for lower tier studies (e.g. the OECD acute oral toxicity 213). Each should be designed to address the

concerns highlighted in the risk assessment. Currently in pesticide registration, semi-field and field studies tend to be conducted according to EPPO 170 or OECD 75. This chapter has built on the information in these guidance documents and provides further information and improvements regarding the conduct of semi-field and field studies. Information is also provided regarding how these studies can be interpreted and hence linked in a qualitative manner to protection goals. [REDACTED]

[REDACTED]
[REDACTED]
[REDACTED]
[REDACTED]
[REDACTED]

Information is provided in this chapter on the design of semi-field and field studies for non-*Apis* bees. Due to the state of knowledge, these are not as well developed and are not currently incorporated into regulatory risk assessment. However, information in this chapter provides a useful starting point regarding what species can be tested under semi-field and field conditions and the design of such studies.

References

- Johansen C.A., Rincker, C.M., George, D.A., Mayer, D.F. Kious, C.W. 1984. Effects of aldicarb and its biologically active metabolites on bees Environ Entomol 13:1386-1398.
- Tasei, JN, Moscatelli, CB, Grondeau, C. 1988. Recherche de la D L 50 de la deltamethrine (Decis) chez *Megachile rotundata* f. Abeille pollinistratrice de la luzerne (*Medicago sativa* L) et des effets de doses infralethales sur les adultes et les larves Apidologie 19 (3): 291-306.
- Ladurner, E., Bosch J., Kemp, W.P. Maini S. 2008. Foraging and nesting behavior of *Osmia lignaria* (Hymenoptera: Megachilidae) in the presence of fungicides: cage studies. J Econ. Entomol. 101: (3) 647-653.
- Konrad R., N. Ferry, AMR Gatehouse and D. Babendrier. 2009. Potential effects of oilseed rape expressing oryzacystatin-1 (OC-1) and purified insecticidal proteins on larvae of the solitary bee *Osmia bicornis*. PlosOne 3(7):e2664. doi:10.1371/journal.pone.0002664.
- Mader, E, M. Spivak and E. Evans. 2010a. Ch. 7 The Alfalfa Leafcutter Bee pg. 75-93 in Managing Alternative Pollinators – A Handbook for Beekeepers, Growers, and Conservationists. USDA Sustainable Agriculture, Research and Education (SARE) Program.

5858 Mader, E, M. Spivak and E. Evans. 2010b. Ch. 5 Bumble Bees pg. 43-52 in Managing Alternative
5859 Pollinators – A Handbook for Beekeepers, Growers, and Conservationists. USDA Sustainable Agriculture,
5860 Research and Education (SARE) Program.
5861
5862 Morandin, L. A., T. M. Lavery, and P. G. Kevan. 2001a. Bumble bee (Hymenoptera: Apidae) activity and
5863 pollination levels in commercial tomato glasshouses. *Journal of Economic Entomology* 94: 462-467.
5864
5865 Knight, ME, AP Martin, S Bishop, J Osborne, R Hale, R Sanderson and D Goulson. 2005. An interspecific
5866 comparison of foraging range and nest density of four bumblebee (*Bombus*) species. *Mol. Ecol.* 14(6):
5867 1811-1820.
5868
5869 Amano, K (2004) Attempts to introduce stingless bees for the pollination of crops under glasshouse
5870 conditions in Japan. Food & Fertilizer Technology Center [online]
5871 <http://www.ffc.agnet.org/library/article/tb167.html>. (accessed on Jan 22, 2011)
5872
5873 Delfinado-Baker M, Baker EW, Phoon ACG (1989) Mites (Acari) associated with bees (Apidae) in Asia,
5874 with description of a new species. *Am. Bee J.* 129:609-613
5875
5876 Heard TA (1999) The role of stingless bees in crop pollination. *Annu. Rev. Entomol.* 44: 183-206
5877
5878 Kuhn-Neto B, Contrera FAL, Castro MS, Nieh JC (2009) Long distance foraging and recruitment by a
5879 stingless bee, *Melipona mandacaia*. *Apidologie* 40 : 472-480.
5880
5881 Schur, A., I. Tornier, D. Brasse, W. Muhlen, W. Von der Ohe, K Waller and M. Wehling. 2003. Honey bee
5882 brood ring-test in 2002: method for the assessment of side effects of plant protection products on the honey
5883 bee brood under semi-field conditions. *Bull Insect* 56(1): 91 – 96
5884
5885 Oomen, P. A. A. DeRuijter and J. Van der Steen. 1992. Method for honey bee brood feeding tests with
5886 insect growth-regulating insecticides. *Bul OEPP/EPPO Bulletin* 22: 613 – 616.
5887
5888 Babendreier D, Karlberger N, Romes J, Fluri P, Bigler F. 2004. Pollen consumption in honey bee larvae: a
5889 step forward in risk assessment of transgenic plants. *Apidologie*. 35: 293-300.
5890
5891 Mineau P, Harding K.M., Whiteside M., Fletcher M.H., Garthwaite D., Knopper L.D. 2008. Using reports
5892 of bee mortality in the field to calibrate laboratory-derived pesticide risk indices. *Environmental*
5893 *Entomology*, 37(2): 546-554.
5894
5895 Stadler, T., D. Martinez Gines, M. Buteler, 2003. Long-term toxicity assessment of imidacloprid to evaluate
5896 side effects on honey bees exposed to treated sunflower in Argentina.
5897

CHAPTER 10 OVERVIEW OF A PROPOSED ECOLOGICAL RISK ASSESSMENT PROCESS FOR HONEY BEES (*APIS MELLIFERA*) AND NON-*APIS* BEES

Alix, A., Steeger, T., Brittain, C., Fischer, D., Johnson, R., Moriarty, T., Johansen, E.,
Streissel, F., Fischer, R., Miles, M., Lee-Steere, C., and, Fry, M.

Introduction

Ecological risk assessments are intended to evaluate the likelihood that adverse
ecological effects may occur as a result of exposure to one or more stressors (USEPA
1992¹⁶). Typically, at the first tiers, risks are evaluated for individual taxonomic groups
(e.g., freshwater fish, upland game birds or terrestrial plants) using surrogate species. At
higher levels of refinement, risks to individual taxa may be further integrated to
determine whether there are effects to the community. However, risk assessments are
typically conducted at the taxon level (USEPA 2004). The intent of this chapter is to
describe a proposed method for estimating risk to honey bees (*Apis mellifera*) and non-*Apis*
bees from pesticides that are applied via sprays (acting on contact) and via seed/soil
treatments and tree trunk injections (acting systemically).

In general, a pesticide risk assessment process is used for evaluating new compounds or
new products entering the market or those compounds undergoing re-evaluation, as in the
10-year process of re-evaluation in the EU or in North America where chemicals are re-
evaluated every 15 years. As with risk assessments for other taxonomic groups, the
proposed risk assessment method described in this document makes use of surrogate
species. The ecological risk assessment process described consists of a series of steps or
phases, which are intended to be iterative where information gathered at each step is
evaluated against the protection goals. The risk assessment process consists of a *problem*
formulation (Phase 1), *analysis* (Phase 2) and *risk characterization* (Phase 3). This
generic process is depicted in Figure 10-1. In Phase 1, *problem formulation*,

¹⁶ U.S. Environmental Protection Agency. 1992. Framework for ecological risk assessment. Washington,
DC: Risk Assessment Forum, U. S. Environmental Protection Agency. EPA/630/R-92/001.

measurement endpoints are identified in relation to protection goals and corresponding assessment endpoints, a conceptual model is prepared and an analysis plan is developed. Based on the conceptual model and its associated risk hypothesis, the analysis plan articulates how the risk hypothesis will be tested. In Phase 2, *analysis*, available measures of exposure and measures of effect are evaluated. Through environmental fate data, the movement of a stressor (*i.e.*, the pesticide and relevant transformation and breakdown products) in the environment is characterized; this is frequently termed the exposure characterization or exposure profile. Similarly, the potential acute and chronic effects of a chemical are characterized in what is frequently termed the stressor-response profile. Additionally, the proposed and/or existing uses of a compound are characterized and, based on these uses and the environmental fate of the compound, predicted/estimated environmental concentrations (PEC or EEC) are derived.

Once effects and exposure are characterized, the risk assessment proceeds to Phase 3, *risk characterization*. Typically, the risk characterization consists of two steps, *i.e.*, risk estimation and risk discussion (evaluation). In the risk estimation step, the measures of exposure (*e.g.*, EECs or PECs) and measures of effect are integrated to develop risk estimates. These risk estimates may be based on point estimates of exposure and a point estimate of effect, *e.g.*, for tier 1, exposure is based on application parameters assumed to result in the highest exposure for a particular use, and point estimates of effect, *e.g.* the acute median lethal dose to 50% of the species tested (LD₅₀). If initial values for potential exposure and effects result in risk estimates that exceed regulatory triggers, then these point estimates can be refined through higher tier testing with regard to both potential exposure and/or potential effects. Possible refinements in exposure estimates are discussed in Chapter 7 while possible refinements in effects are discussed in Chapter 8 (laboratory studies) and Chapter 9 (semi-field/full field studies). As ecological risk assessment methodologies evolve, refined estimates could be based on distribution-based estimates of either exposure (*e.g.* residue concentrations in pollen from field monitoring studies based on application rate reflecting the worst case for a particular use), or effects (*e.g.*, species sensitivity distribution using LD₅₀ values for non-*Apis* species).

Regardless of whether point estimates or distribution-based estimates are used, the integration of exposure and effects data is typically expressed as a ratio (quotient), and it is this ratio is that considered to be the "risk estimate". If point estimates of exposure and effects are used as inputs, the risk quotient is a deterministic point estimate of risk. If the exposure and/or effects inputs are probability distributions of possible values, the risk estimate is itself a "joint" probability distribution and represents a probabilistic estimate. Deterministic estimates of risk, based on point estimates of exposure and effects, do not typically provide information on the magnitude and likelihood of adverse effects. This uncertainty is in most cases accounted for with the use of assessment factors. In refining the risk assessment on the basis of distribution-based estimates of either or both exposure and effects, probability distributions and particularly joint-probability distributions allow the estimation of both the likelihood (probability) and magnitude of an adverse effect (e.g., estimates of a 40% chance that 60% of the species will be affected). The decision to move from point-estimate based approaches to distribution-based approaches¹⁷ that may also be spatially and temporally specific is predicated on the risk manager's need for additional information to support their decision and the availability of data to support such approaches.

The second part of *risk characterization* is risk evaluation, where quantitative estimates of risk are, when necessary, further described using qualitative data. Multiple lines of evidence are used to more fully describe what is known about potential adverse effects resulting from the use of a pesticide. Risk evaluations include additional discussion about the variability associated with the measured endpoints along with associated uncertainties, *i.e.*, attempts to characterize what is not known. When necessary or possible, the intended effects of relevant mitigation measures may also be discussed. Any incident data, *i.e.*, adverse effects reported involving the actual use of the compound in the field, are also discussed to further characterize potential effects.

¹⁷ Species sensitivity distributions are an option to refine the evaluation of effects for risk assessment performed for a group of organisms and not at the level of a species, *e.g.*, the honey bee.

Although the risk assessment process is depicted as three distinct phases, each phase is intended to be iterative. As more information (data) becomes available, the outcome of the process should evolve to accommodate the data. The risk assessment process is therefore intended to take advantage of multiple lines of evidence and the problem formulation with its conceptual model and risk hypothesis may be refined as more information becomes available. A critical component to this iterative process is clear communication between the risk assessor and the risk manager to insure that protection goals are adequately articulated and that the relevant mitigation measures on risk estimates may be implemented and potentially evaluated within the risk assessment.

Consistent with the iterative nature of the risk assessment process, regulatory authorities typically rely on a tiered process for conducting ecological risk assessments; the preliminary, or screening-level (Tier 1) assessments are intended to screen substances for which a potential risk cannot be excluded. Higher tiers attempt to refine risk estimates to: (i) identify whether a potential risk will likely be encountered under more realistic assessment conditions, *i.e.*, using less conservative assumptions regarding potential exposure and effects; (ii) determine the conditions under which potential risks may occur; and, (iii) identify the spatial and temporal characteristics of risks. The tiered risk assessment process identifies those chemicals for which a higher level of resources should be devoted to support more refined and detailed assessments. It should be noted though, that while probabilistic tools can be used to refine estimates of exposure and effects, and to quantify spatial and temporal characteristics of risks, they are not typically applicable to determining the conditions of occurrence for risk. Additionally, such refinements are typically focused on specific uses which have exceeded trigger values and which require a more detailed understanding of the potential magnitude, likelihood and/or duration of a particular effect.

Decision criteria are used within a tiered framework as a basis for discriminating potential risk(s) among substances. Screening-level risk assessments may have predetermined decision criteria to answer whether potential risks exist, as for example in the EU where decision-making criteria are defined for all groups of organisms (EC,

2001). Conversely, higher tier risk assessments may not have predetermined and/or uniformly defined decision criteria since the management decision may change from yes/no to questions regarding "what, where, and how great is the risk", as for example in the US (USEPA 1998¹⁸) and may also be associated with restrictions/conditions intended to limit risk (which is the case in both the EU and US).




Figure 10-1. Diagram of Ecological Risk Assessment Process employed by US EPA

In the following sections, the risk assessment process for honey bees and non-*Apis* bees is described. Consistent with the tiered process discussed in the preceding sections, the following sections propose risk assessment flowcharts discussed during the workshop and are intended to illustrate the different steps mentioned above. Each step of these risk assessment processes are then discussed in greater detail, starting with screening-level

¹⁸ U.S. Environmental Protection Agency. 1998. Guidelines for Ecological Risk Assessment. . Washington, DC: Risk Assessment Forum, U. S. Environmental Protection Agency. EPA/630/R-95/002F

assessments (Tier 1) and proposed refinements that incorporate additional data on potential exposure and effects to both *Apis* and non-*Apis* bees. The proposed process is delineated for pesticides that are applied foliarly and act on contact with or ingestion by insects. A different risk assessment process is articulated for pesticides that are applied to soil or as a seed treatment. For soil and seed treatments that are systemic, the chemical is taken up by the plant and distributed either through xylem (*i.e.*, translocation through the plant in the direction of xylem flow (acropetal¹⁹) or through plant phloem (*i.e.*, translocation through the plant in the direction of phloem stream (basipetal²⁰ and acropetal). The route of exposure to systemic compounds applied as soil, seed or tree trunk injections is primarily through ingestion of residues in pollen and/or nectar.

Protection goals, assessment and measurement endpoints, trigger values for transitioning to higher levels of refinement and risk assessment terminology

As previously discussed, the initial phase of a risk assessment process is problem formulation. The problem formulation articulates the intent of the risk assessment and is predicated on particular protection goals for which the regulatory authority is responsible. In order to build a proposed risk assessment process for pollinators, the participants of the Workshop identified plausible, surrogate protection goals, these included:

- (i) protection of pollination services provided by *Apis* and non-*Apis* species'
- (ii) protection of honey production and other hive products; and,
- (iii) protection of pollinator biodiversity,

In order to structure an assessment that allows addressing risk management concerns, *i.e.*, realize protection goals, it is important to define assessment endpoints. Assessment endpoints are intended to be explicit expressions of the actual environmental value that is to be protected and are operationally defined by an ecological entity and its attributes (USEPA 1998). For assessing potential risks to *Apis* and non-*Apis* bees the ecological

¹⁹ Acropetal refers to the direction of movement and is typically intended to denote movement from the base of a plant (*e.g.*, roots) toward its apex.

²⁰ Basipetal refers to the direction of movement and is typically intended to denote movement from the apex of a plant toward its base.

entities would be the organisms themselves (*e.g.*, larval and adult honey bees and bumble bees) and potential attributes would consist of survival, development and reproduction. The ability of assessment endpoints to support risk management decisions depends on the extent to which they target susceptible ecological entities and measurable ecosystem characteristics (USEPA 1998). Protection of the growth, reproduction and survival at the colony/population level of these species will conserve pollination services, biodiversity contributed by pollinators, and availability of hive products (*e.g.*, honey production). The conventional assessment endpoints of survival, development and reproduction can be articulated for *Apis* and non-*Apis* bees to include colony size and survival for honey bees, and population size and survival for non-*Apis* bees.

Assessment endpoints are further defined by measurement endpoints. Measurement endpoints are attributes that are examined at the study level which, taken either individually or together, are indicative of an assessment endpoint. In initial [screening level] laboratory studies, it is practical to measure endpoints such as individual survival, toxicity to and developmental effects on larvae (brood), and behavioral effects (*e.g.*, effects that become manifest in adults due to exposure as larvae). These measurement endpoints are relevant because if severely impacted, they can result in effects at the colony/population level and can be indicative of the ability of a colony to grow, reproduce, or survive. In higher tier tests, it may be possible to directly measure effects on colony/population size and viability. However, as noted in previous chapters, further research is required to ascertain which, and at what level [sublethal] effects is indicative of a colony-level, or population-level effect. The linkage between protection goals, assessment endpoints and possible measurement endpoints are presented in **Table 10-1**.

Table 10-1. Linkage of protection goals, assessment endpoints, and measurement endpoints for social bees (including *Apis*) and solitary (non-*Apis*) bees. Initials (L) and (F) designate endpoints most applicable to laboratory (L) studies and field (F)

Protection Goal	Assessment Endpoints	Measurement Endpoints Population Level or higher	Measurement Endpoints Individual Level
Pollination services	Population size and health on the crop/in the boundaries	Social bees: Colony survival (F), colony strength (F) Solitary bees: Population size (F) and persistence (F) over time	Social bees: Individual survival (L, F), fecundity (F), brood success (L, F), behavior (L, F) Solitary bees: Individual survival (L, F), reproduction (F), behavior (L, F)
Hive products (honey, etc.)	Production of hive products	Production of hive products (F)	Individual survival (L, F), brood success (L, F), behavior (L, F)
Pollinator biodiversity	Species richness and abundance on the crop/in the boundaries	colony survival (F), colony strength (F), brood success (F), behavior (F) Species richness and abundance (F)	individual survival (L, F), brood success (L, F), behavior (L, F)

Table 10-1. Linkage of protection goals, assessment endpoints, and measurement endpoints for social bees (including *Apis*) and solitary (non-*Apis*) bees. Initials (L) and (F) designate endpoints most applicable to laboratory (L) studies and field (F) studies, respectively.

The terminology of risk assessment can be confusing due to the differences amongst regulatory authorities. Many parts of the processes outlined in this document make reference to the European EPPO methodology, and the testing methods for non-target terrestrial arthropods thereof. Table 10-2 presents the different risk expressions used herein.

Formatted: Font: 10 pt

Formatted: Caption, Keep with next

Formatted: Font: 10 pt

Formatted Table

Table 10-2. Risk estimates and their components used by regulatory authorities.

Ecological Risk Estimate	Effects Component	Exposure Component	Comment	Where/How it is Used
Hazard Quotient (HQ): Effects/Exposure	LD ₅₀ measured as ug/bee	Dermal exposure concentration or oral dosing concentration as g/ha	Numerator and denominator are expressed in dissimilar measurement units	Used in European assessments Used in Tier 1 analysis
Risk Quotient (RQ): Exposure/Effects	LD ₅₀ measured as ug/bee	Contact exposure concentration, or oral dose concentration	Numerator and denominator are expressed in same measurement units	Used in North American assessments Used in Tier 1 analysis
	No Observed Adverse Effect Level (NOAEL) measured as ug/bee	Oral feeding concentration (solution) or dietary intake (pollen or nectar)	Numerator and denominator are expressed in same measurement units	Used in North American assessments Can be used in Tier 1, and Tier 2, analysis
Toxicity Exposure Ratio (TER): Exposure/Effects	LD ₅₀ or the No Observed Adverse Effect Level (NOAEL) measured as ug/bee	Oral feeding concentration (solution) or dietary intake (pollen or nectar)	Numerator and denominator are expressed in same measurement units	Used in Tier 1 analysis (for larvae) and Tier 2 analysis

Note that in Tier 3 analysis, where a field study is performed, neither an HQ or RQ nor a TER is calculated. Rather, effects are characterized, statistically significant or not, in the context of actual exposure conditions and in the context of whole hive biology.

6121
6122

6123 **Risk Assessment Flowcharts** 6124

6125 This section illustrates the proposed risk assessment process identified by the participants
6126 of the 2011 SETAC Workshop on Pesticide Risk Assessment for Pollinators. The
6127 decision process is described and depicted in flowcharts to better highlight the
6128 progression of events through the tiers. Risk assessment starts with a preliminary
6129 verification that a risk assessment is warranted by first describing routes of exposure that
6130 are considered likely and will trigger further evaluation. This leads to screening steps
6131 intended to exclude situations where the potential for adverse effects is considered low
6132 and with a sufficient margin of safety to conclude no further analysis is necessary. The
6133 process then focuses on uses for which further characterization of the risks is necessary
6134 and guides the assessor in efforts to identify the necessary data to enable the estimation of
6135 effects and exposure levels needed to assess potential risks from these scenarios.

6136
6137 An overview of each step in the problem formulation and risk assessment process, *i.e.*,
6138 screening-level assessment to more refined evaluation of effects and exposure based on
6139 laboratory data, to higher tiered assessments involving semi-field and field studies can be
6140 found in Chapters 5 and 6. Efforts to refine risk estimates are typically predicated on
6141 refining estimates of potential exposure and effects. For detailed descriptions of the
6142 studies to be undertaken to generate these data, refer to Chapter 7 (assessing exposure),
6143 Chapter 8 (laboratory-based effect studies) and Chapter 9 (field-based effect studies).

6144
6145 The flowcharts below are used to depict a generic risk assessment process that was
6146 developed during the workshop. Two proposed processes distinguish between
6147 compounds applied as spray for which the worst case exposure may be expected through
6148 direct contact of pollinators with spray droplets during the flowering period (Figures 10-2
6149 and 10-3) and, products used as soil or seed treatments for which an exposure may occur
6150 as a result of the systemic properties of the compound or its degradates (Figures 10-4 and
6151 10-5). It is important to note that contact exposure to a systemic compound is also

possible if it is applied as a spray application around or during the flowering period, *e.g.*, in the case of pre-bloom application. In this case, the reader may also find useful recommendations in the flowchart for soil/seed treatments.)

Each box of these flowcharts is numbered and the nature of the data and reasoning behind each step of the process is provided below. As noted earlier, suitable LOC values (*i.e.*, trigger values) for transitioning to higher levels of refinement are linked to risk management decisions and protection goals of individual regulatory authorities. The trigger values depicted in Figures 10-2 through 10-5 are generic. However, the more detailed but related risk assessment scheme in Appendix 6, which modifies the EPPO guidance (EPPO, 2010), contains some trigger values currently used in the European regulatory process (EC, 2010). As stated in other parts of this document, it is not the intent of this document, or SETAC, to recommend and/or support any particular trigger criteria but rather to emphasize the role that these values play in an efficient risk assessment process.

Spray Applications

Figures 10-2 and 10-3 depict the risk assessment process for insect pollinators following the use of spray products. Each step (box) depicted in the flow chart is numbered and arrows depict the direction that should be followed in response to a “yes” or “no” answer. More detail regarding each of the steps is provided below.

The risk assessment process begins by asking whether exposure is possible (**Box 2a**); if exposure is not possible, then there is a presumption of minimal risk (**Box 6**). For sprayed applications, the screening level considers the worse case exposure assumption of a direct overspray to plants where bees are actively foraging. Potential effects of the chemical thus result from the overall effects of the direct spray on foraging bees. As depicted in the left-hand side of Figure 10-2, at the screening level, potential risk to adult honey bees from spray applications is assessed through calculation of an HQ (**Box**

3a). The assessor calculates an HQ by dividing the theoretical exposure, that is, the application rate expressed in terms of weight per unit area (*e.g.*, grams active ingredient/hectare) by the most sensitive acute median lethal dose to 50% of the organisms tested, *i.e.*, the [contact] LD₅₀ value, derived from laboratory studies. If the HQ value passes a regulatory trigger value, then there may be a presumption of minimal risk to adult honey bees and the reviewer proceeds to assess possible impacts to non-*Apis* adults (**Box 4a**).

To evaluate potential risk to *larval* honey bees, the assessor calculates a TER by dividing the most sensitive No Observed Effect level (NOEL) from the honey bee larval toxicity test by the theoretical maximum concentration in pollen and nectar (**Box 3b**). While several test designs currently exist to assess effects to larvae, adoption of this step in a formal, regulatory process would require standardization of a particular test design. Possible test designs for lower-tier laboratory-based studies with larvae are discussed in Chapter 8. If the TER value passes the trigger value, then a presumption of minimal risk to larval honey bees can be made and the reviewer proceeds to evaluate possible impacts on non-*Apis* larvae (**Box 4b**).

Default Exposure Estimates for Screening Level Analysis for Apis Larvae:

Although a theoretical maximum concentration has been established by some regulatory authorities for systemic products (*e.g.*, 1 mg/kg or ppm, EPPO 2010) no such exposure model or theoretical maximum concentration level has been formally set for sprayed products. Pesticide residues resulting from direct overspray on food items for birds and mammals can be estimated using a residue per unit dose (RUD) approach favored by Hoerger and Kenaga, (1972). The EPA terrestrial exposure model (T-REX)²¹ has been revised to include insect residue data that could represent reasonably conservative screening values. In the most recent guidance produced by the European Food Safety Authority (EFSA) (EFSA

²¹USEPA. 2012e. User's guide for T-REX version 1.5 (Terrestrial Residue EXposure model). United States Environmental Protection Agency, Office of Pesticide Programs, Environmental Fate and Effects Division. Available online at: [[HYPERLINK](http://www.epa.gov/oppefed1/models/terrestrial/trex/t_rex_user_guide.htm) "http://www.epa.gov/oppefed1/models/terrestrial/trex/t_rex_user_guide.htm"]

2009²²), a range of RUD values have been developed for different crops and food sources. Furthermore, the EPA toxicity of residues on foliage test²³ may provide insight on the magnitude of residues on foliage following a particular application rate and the period of time these residues remain toxic. Further research is necessary to both validate current screening exposure values used by regulatory authorities, as well as to develop RUD values, or other [screening] exposure models specific to pollinators.

The proposed risk assessment scheme also considers potential risks to non-*Apis* bees. At the screening level, risk to non-*Apis* bees is evaluated by employing effects data from honey bee acute oral/contact (LD₅₀) studies (**Box 4a** depicting the calculation of an HQ for non-*Apis* adults), and chronic larval honey bee toxicity (NOEL) test data (**Box 4b** depicting the calculation of a TER for non-*Apis* larvae). In cases where Tier 1 (screening-level) data on *Apis* bees are not sufficient to conclude low risks to non-*Apis* bees (*i.e.*, using a trigger value for *Apis* species modified with an appropriate safety factor to account for inter-species variation), then it may be concluded that the substance does not pass the screening step. In this case, data from non-target arthropods (NTA), typically required in the European registration process, could be considered (**Box 4a and 4b**) as they may provide useful information on the choice of non-*Apis* species to be further tested if potential risk cannot be excluded upon examination of the available NTA data. Participants in the Workshop agreed that NTA data could be utilized as it typically includes toxicity estimates for the predatory mite (*Typhlodromus pyri*) and the parasitic wasp (*Aphidius rhopalosiphii*). Refined risk estimates for non-*Apis* bees would then require development of adult oral and/or contact LD₅₀ values for the relevant non-*Apis* species and an HQ (*i.e.*, application rate/LD₅₀) developed for adult bees (**Box 5a**). Similarly, where risk estimates do not meet trigger criteria for non-*Apis* bee larvae, then a NOEL for relevant non-*Apis* bees is necessary (**Box 5 b**) to calculate a TER. As with

²² European Food Safety Authority; Guidance Document on Risk Assessment for Birds & Mammals on request from EFSA. EFSA Journal 2009; 7(12):1438. doi:10.2903/j.efsa.2009.1438. Available online: www.efsa.europa.eu

²³ U.S. Environmental Protection Agency. 1996. Ecological Effects Test Guidelines. OPPTS 850.3030 Honey Bee Toxicity of Residues on Foliage. EPA 712-C-96-148. April 1996. [HYPERLINK "http://www.epa.gov/ocspp/pubs/frs/publications/OPPTS_Harmonized/850_Ecological_Effects_Test_Guidelines/Drafts/850-3030.pdf"]

toxicity estimates for adult non-*Apis* bees, toxicity test methods would have to be developed for larvae of relevant non-*Apis* bees. If risk estimates for either adult and/or larval non-*Apis* bees are within regulatory criteria, then minimal risk is presumed (**Box 6**); however, if not, then the reviewer should proceed to higher-tier (refined) assessment methods depicted in Figure 10-3 or consider risk mitigation measures intended to reduce exposure (**Box 7**). As depicted in Figure 10-2, where risk mitigation measures are imposed, the reviewer should then re-evaluate whether exposure to adults (**Box 2a**) and/or larvae (**Box 2b**) has been sufficiently reduced to presume minimal risk. Again, if minimal risk cannot be presumed, the reviewer should proceed through the screen using the revised exposure numbers based on the proposed mitigation.

The proposed refined risk assessment for sprayed products depicted in Figure 10-3 begins by asking whether higher tier risk assessment is needed for honey bees (**Box 8a**) or for non-*Apis* bees (**Box 8b**). The screening level risk assessment is typically based on effects data on individual bees collected through laboratory studies. However, in refined risk assessments, the reviewer considers the results of semi-field and full field tests, which are typically conducted at the colony level rather than at the level of the individual bee. The refined risk assessment process therefore attempts to capture more realistic effects data as well as incorporating more refined estimates of exposure. For honey bees, effect estimates from semi-field studies (**Box 9**) or full field studies (**Box 10**) are used to determine whether maximum application rates result in effects. If minimal risk cannot be presumed from the results of semi-field studies, then the reviewer should consider full field studies where such studies can determine effects under more realistic test conditions (**Box 10**). In cases where full field studies do not result in risk estimates that are consistent with protection goals, then the reviewer should conduct an analysis of uncertainties associated with the review process and determine whether possible mitigation specific to honey bees has been adequately considered (**Box 11**). As in the screening-level assessment, the impact of mitigation measures should be considered through the refined risk assessment process to ensure that their result is inconsistent with protection goals. After such an analysis, if risk estimates still do not meet regulatory criteria, then there is a presumption of significant risks (**Box 17**).

6268

6269 In the case of non-*Apis* bees, the reviewer assesses potential risks via data on non-target
6270 arthropods (**Box 12**) and determines whether there are actual significant routes of
6271 exposure which are not accounted for by the higher tier tests conducted using honey bees
6272 (**Box 13**) such as from contaminated nest material. If risk concerns to non-*Apis* bees
6273 cannot be minimized, higher tier effects testing discussed in Chapter 9 using non-*Apis*
6274 bees relevant to the specific potential route of exposure are then considered, possibly first
6275 through a semi-field test (**Box 14**) with the option to extend the investigation to the full
6276 field level (**Box 15**). As with honey bees, the process and underlying
6277 assumptions/uncertainties associated with risk estimates should be carefully analyzed
6278 (**Box 16**) and the reviewer should consider possible mitigation measures specific to non-
6279 *Apis* bees. The potential effects of mitigation options must be considered at each of the
6280 steps within the refined process whether it is an *Apis* or non-*Apis* analysis. If after this
6281 analysis, estimates are considered reasonable and potential mitigation measures cannot
6282 reduce potential exposure and potential risks, then the reviewer must presume significant
6283 risk to the non-*Apis* species, under the proposed conditions of use.




Figure 10-2. Insect pollinator screening-level risk assessment process for foliar applied pesticides.




Figure 10-3. Higher-tier (refined) risk assessment process for foliarly applied pesticides.

Soil and Seed Treatment Applications for Systemic Substances

Figures 10-4 and 10-5 depict the screening-level and refined risk assessment processes, respectively, for soil and seed treatment applied pesticides that are systemic in nature. Each step (box) depicted in the flow chart is numbered and arrows depict the direction that should be followed in response to a yes or no answer. More detail regarding each of the steps is provided below.

When evaluating potential acute risk to adult honey bees from soil or seed treatments²⁴ with systemic compounds, the assessor first asks whether exposure is possible to the adult (**Box 2a**) or immature stages (**Box 2b**) via systemic translocation of residues in plant material. If exposure to honey bee adults is considered likely, the review calculates a TER (**Box 3a**) using either an acute oral or contact LD₅₀ value for honey bee adults. In Europe, a tier 1 TER is estimated by dividing a screening exposure estimate by the screening level hazard value. Currently, EPPO has a proposed conservative default exposure value of 1 mg a.i./kg, relies on the default maximum concentration estimated in pollen and/or nectar from residues in whole plants, which for use with soil and seed treatments. If the risk estimate for the adult honey bees does not meet the regulatory criterion for low risk, then the reviewer should proceed to higher tier risk assessment (options to proceed with a 10-day adult test (**Box 4a**), or more refined studies) or consider risk mitigation measures and reassess (**Box 8**). If the TER value for the adult honey bee meets the regulatory criterion for low risk, then the reviewer proceeds to evaluate potential impacts on non-*Apis* adults (**Box 5a**). Here the assessor may consider data on non-target arthropods. Where risk assessments for non-*Apis* bees do not meet the regulatory criterion for low risk (i.e., meets the regulatory criterion for low risk to *Apis* by a wide margin), then acute oral/contact LD₅₀ values should be developed for non-*Apis* bees and a TER calculated (**Box 6a**). As with honey bees, if the risk estimate does meet the regulatory criterion for low risk, then the reviewer should proceed to higher tier (refined) risk assessment (semi-field or field study) or consider risk mitigation measures and reassess (**Box 8**).

²⁴ Although not specifically discussed at the workshop, treatments with systemic compounds can include tree trunk injections as well.

6320

6321 For larval assessments, the same process as that discussed for spray applications is
6322 followed (Boxes **3b**, **4b**, and **5b** of Figure 10-4). Additionally, the same process for
6323 higher tier (refined) risk assessment is used as discussed for spray applications.
6324 Participants of the Workshop noted the lack of information on potential exposure (nectar
6325 and pollen) related to trunk injection; and that further data are needed in this area (see
6326 Chapter 13). In the meantime, participants of the Workshop recommended that potential
6327 [screening] risks from trunk injection be estimated in the same manner as soil and seed
6328 scenarios.

6329 As discussed previously, risk assessment is intended to be an iterative process. At a
6330 screening level, when risk estimates do not meet decision criteria, (*i.e.*, where a
6331 presumption of minimal risk cannot be made), the conditions under which the estimated
6332 risks occur should be more closely examined. More detailed fate considerations (such as
6333 degradation), or use considerations (such as timing of application, or application
6334 intervals) should be considered before additional testing is required.

6335




Figure 10-4. Insect pollinator screening-level risk assessment process for soil and seed treatment of systemic pesticides. Note that this flow chart may apply for trunk injection as well, as modalities of exposure of pollinators are similar as for soil/seed treatments. For trunk injection however, further data are needed to appropriately describe the range of expected residue concentrations in nectar and pollen. As a consequence no default value is currently available for a quantification of the risk (Boxes 3a and 3b). A compilation of available data could be made, with a particular attention to the corresponding injection protocols as it varies with the active substance involved and the tree.




Figure 10-5. Higher-tier (refined) risk assessment process for soil and seed treatment applied systemic pesticides.

Screening-Level Risk Assessments (Tier 1)

As noted, ecological risk assessments typically follow a tiered process (depicted in Figure 10-1). Substances move through lower tiers to higher tiers when the information indicates potential risk cannot be excluded. The first tier of that process is the screening-level assessment, which is intended to effectively and rapidly:

- exclude substances of low risk concern from entering into resource intensive higher tier risk assessment; and,
- identify substances for which a potential risk to bees cannot be excluded and for which a higher tier risk assessment is needed.

The screening-level assessment should allow for the most efficient allocation of resources and minimize the number of substances forwarded for higher tier evaluation while still identifying substances of potential risk to bees. An efficient screening step in the risk assessment process is essential as it optimizes the success in achieving protection goals. At a screening-level, the intent is then to use an appropriately sensitive species that is suitable to ensure that protection goals will be met. In this context, in designing the risk assessment process, participants proposed the *honey bee* as a reasonable surrogate for both *Apis* and non-*Apis* bees at a screening level for evaluating acute toxicity to adults. The reasons for this are:

- the biology and availability of *A. mellifera* makes it well-suited and lends itself to testing and analysis;
- the relative sensitivity of the honey bee compared to non-*Apis* species (based upon available data)
- tiered toxicity test guidelines are widely available for *A. mellifera*; and,
- conducting and interpreting the results of these tests does not require specialized backgrounds and/or conditions.

As illustrated in the flow chart depicted in Figure 10-1, the screening step most often relies on the calculation of risk estimates, termed Risk Quotients (RQ), Hazard Quotient (HQ) or Toxicity Exposure Ratios (TER). These risk estimates are compared to numerical regulatory decision criteria, termed a “Level of Concern” (LOC) or “trigger criterion”. A LOC is a value against which a risk estimate is compared. It is intended to be protective in that it typically accounts for uncertainties related to intra- and inter-species variation in sensitivity, extrapolation of short-term toxicity to long-term effects, and extrapolation of laboratory results to the field.

Depending upon the type of risk estimate used (RQ or TER), if the estimate is above or below the LOC, then a determination of minimal risk is presumed, or whether additional refinements are necessary. For example, if screening-level risk estimate results in a TER (where the effects estimate is divided by the exposure estimate) that exceeds the LOC, then minimal risk is presumed (*i.e.*, if $TER > LOC$ = minimal risk is presumed); conversely, if the TER does not exceed the trigger value, then minimal risk cannot be presumed, and a higher tier risk assessment may be needed. The RQ is the reciprocal of the TER in that the exposure estimate is divided by the effects estimate; therefore, the RQ value is interpreted opposite to the way in which the TER is interpreted, *i.e.*, if the RQ exceeds a trigger value, then minimal risk is not presumed and a higher tiered risk assessment may be needed. If the RQ value is greater than the LOC (or trigger value), then minimal risk cannot be presumed.

Factors limiting certainty in the screening step

Screening-level assessments are typically based on conservative assumptions regarding both exposure and effects. For example, at a screening level assessment for honey bees, the EPPO system does not account for good practices such as avoiding spray application during foraging times but conversely, not all routes of potential exposure are reflected. Given all the potential variables to consider, the Participants of the Workshop believed

that the proposed screening level analysis is conservative and protective for other potential routes of exposure.

Similarly, although mortality is the primary effect reported and used to generate LD₅₀ values in acute toxicity tests, adverse effects on behavior are also reported. As discussed in earlier chapters, the extent to which sublethal effects occur and whether they ultimately affect assessment endpoints such as impaired survival, growth and reproduction at the colony level remains an uncertainty for many compounds. However, since effects on behavior are frequently, but not exclusively associated with insecticides or acaricides which will also potentially affect acute survival, the majority of these compounds will be subject to higher tier risk assessment where the sublethal effects will be more thoroughly evaluated. In addition, other information presented in the data profile of a compound (such as mode of action, route of uptake, toxicity and effects on other types of terrestrial arthropods) should always be examined (EPPO, 2010), and integrated with the findings of the screening step as part of the overall risk assessment for honey and non-*Apis* bees.

The capacity of the screening-level assessment to properly screen substances of low likelihood of adverse effects from substances for which further assessment is necessary has been evaluated through a review of the honey bee kill incidents recorded in the United Kingdom survey network WIIS (Mineau *et al.*, 2008). The Mineau *et al.* 2008 analysis supports the utility and efficacy of the tier 1 screening methodology, provided that considerations on the mode of action and use patterns are also kept in mind, as for any risk assessment process.

Refinement Options for the Risk Assessment

If the results of a screening-level assessment indicate that a minimal risk cannot be concluded, the process moves to a series of refinements in exposure and/or effects data (see Figures 10-2 through 10-5). There are a number of options to further refine a risk assessment through a more in-depth description/characterization of exposure and/or of

effects. These options are described, regarding their possible methodologies, in previous chapters. As refinements progress, different TERs and RQs are developed.

In the deterministic risk assessment approach, the primary outcome of the [Tier 1] risk characterization is the calculation of the risk quotient (RQ), or the Toxicity Exposure Ratio (TER) depending on the country/region where the assessment is being performed. Both the RQ and the TER are single number (point) risk estimates. In reality, risk is more complex and therefore, a single point estimate can be misleading. As a consequence, the assessor should characterize the RQ or TER with a description of the uncertainties, assumptions, strengths and limitations associated with the risk estimate. These sources of variability and uncertainty should be discussed during characterization of the exposure and effects and should include refinement options used in ultimately determining the RQ or TER. At the higher levels of refinement (*e.g.*, semi-field and field tests), the level of impact is directly measured in experiments that are intended to reproduce the operational conditions of the subject pesticide product. In this case, TER and RQ values are no longer calculated.

Exposure is the first component of the risk to be examined to determine whether a risk assessment is needed, and the first to be explored to refine a potential risk. As a guide for proceeding through the levels of refinement, Table 10-3 provides a summary of the relative importance of different exposure routes for *Apis* and non-*Apis* bees. The main exposure routes identified for evaluation in the screening-level assessment are oral intake of nectar and pollen, and contact exposure. While not all exposure routes are included in the screening-level (Tier 1) risk assessment (*e.g.*, wax and drinking water are not evaluated at Tier 1); and, direct overspray is considered as the worst case (high-end) exposure, it is important for the assessor to consider additional exposure routes for higher tier risk assessment purposes (Table 10-3 presents potential exposure routes for different bees).

Table 10-3. Likelihood of exposure to *Apis* and non-*Apis* bees from various routes.

Exposure	<i>Apis</i>		<i>Non-Apis</i>	
	Adult	Larvae	Adults	Larvae
Nectar	+++ ¹	+	+ to +++	+
Pollen	+ to +++	++ ²	+ to +++	++ to +++
Water ³	+ to ++	+ ²	+	+
Nesting Maternal	++ ⁴	++ ⁴	+ to +++ ^{4,5}	+ to +++ ^{6,7,8}
Exposure to Soil	+/+	::	- to +++	- to +++
Foliar Residues (contact and direct spray)	+++	::	+++	- to +++
Direct spray	+++ ⁸	::	+++ ⁵	::

¹ Collect water for cooling (evaporative cooling; take up into crop, regurgitate it and flap wings to distribute) and honey production; ² particularly for nurse bees; ³ bee bread; ⁴ provided by nurse bees; ⁵ wax; ⁶ leaves and soil for cement; ⁷ leafcutting bees; ⁸ soil used to cap cells; ⁹ at flowering; ¹⁰ exposure to soil

Other insects may experience these exposure routes and testing methods are available for these species and field data may be available. As an example, parasitoid species also feed on nectar, such as the predatory mite *Typhlodromus pyri*, or the ladybird beetle *Coccinella septempunctata* feeds on pollen. The predatory and parasitoid coleopteran *Aleochara bilineata* is a soil dweller at the adult stage. Therefore, review of these data when available may be useful in determining the major exposure routes to be investigated in a risk assessment for pollinators.

Table 10-3. Likelihood of exposure to *Apis* and non-*Apis* bees from various routes.

Exposure	<i>Apis</i>		<i>Non-Apis</i>	
	Adult	Larvae	Adults	Larvae

Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough
Formatted: No underline, Font color: Auto, Strikethrough
Formatted: Strikethrough

6482 ^aCollect water for cooling (evaporative cooling; take up into crop, regurgitate it and flap wings to
6483 distribute) and honey production; ⁴expected for parasitoid; ²particularly for nurse bees; ²bee bread; ⁴
6484 predatory wasp (red); ⁵provided by nurse bees; ⁶wax; ⁷leaves and soil for cement; ⁸leafcutting
6485 bees; ⁹soil used to cap cells; ¹⁰at flowerings; ¹¹exposure to soil

6487
6488

6489
6490

6491 If the HQ for adult *Apis* exceeds the level of concern in the screening-level (Tier 1)
6492 assessment, then further information is required. Refinements can be made for exposure
6493 and/or effects, depending upon the profile of the active substance and its residues.

For spray application, an option for refining exposure estimates is to move from the screening-level default values to product-specific field modeling or measurement data to better quantify exposure. If an application during flowering cannot be excluded, this option may have several levels of refinement such as consideration of the interval between application and flowering and the expected level of residues to which bees could be exposed, for either modeled or measured estimates of refined exposure.

Measurements of actual exposure may be achieved by use of the existing residue data, *e.g.*, magnitude of residue, or by implementing tunnel and/or field residue studies to estimate the level of exposure in treated crops and considering different modalities for the period of treatment.

While most semi- and full-field toxicity tests generate data on both exposure and effects, they may also be pursued with an exclusive aim of providing realistic exposure estimates. In this case, it is important that data generated from the field test is recorded so that it may be directly compared to the ecotoxicity data (*i.e.*, the results and endpoints are expressed in the same units and represent comparable measures of exposure).

With respect to residue concentrations in nectar, pollen (or foliage where appropriate) the reviewer should consider the 90th percentile of measured concentrations as a conservative measure of exposure. However the decision to use a 90th percentile or other value ultimately depends on the data set. If data are derived from only a single test on one crop, then a specified percentile, *e.g.*, 90th percentile, should be sufficiently vetted to reflect the uncertainty and variability as is frequently done in support of probabilistic approaches. If several trials have been undertaken, or data are derived for several crops, then a mean or a lower percentile may be more appropriate and would achieve the same level of protection. The selection of a particular crop for the evaluation of residues must consider whether the resulting data are sufficiently conservative to enable those data to serve as a surrogate for other uses.

The initial test(s) to measure the effect of a compound is a lethality test consistent with relevant life stage and exposure route (*e.g.*, oral LD₅₀, or larval toxicity test). As effects tests become more refined, they incorporate more environmentally realistic conditions and begin to reflect both intrinsic toxicity and potential enhancing/compensatory effects, related to environmental conditions.

To further refine the toxicity endpoint, additional *Apis* studies that could be relevant for the adult life stage include:

- 6529 • 10-day feeding study (adult survival);
- 6530 • toxicity of residues on foliage study;
- 6531 • semi-field data ; and,
- 6532 • field data.

6533 A description of the studies that may be appropriate is found in Chapter 9; these studies
6534 are discussed briefly below.

6535 The 10-day adult study is an extension of the standard laboratory oral exposure method
6536 (OECD 215). The test exposes adult bees for a period of 10 days and measures lethal
6537 effects after ingestion of product over the entire test duration. A NOEL is derived that
6538 may be used similarly as a LD₅₀ in RQ calculations. Because this test only addresses oral
6539 exposure, it is not sufficient to address the uncertainties associated with sprayed
6540 compounds and is actually considered to be useful when refining estimates of effects for
6541 systemic soil/seed treatments. Currently there is no internationally recognized guideline
6542 for the 10-day feeding study nor for the larval toxicity testing in the laboratory; ~~therefore,~~
6543 ~~these tests~~ need to be developed and validated before formal inclusion in to a regulatory
6544 risk assessment scheme. The endpoint from a 10-day feeding study could be compared to
6545 either the default (screening-level) exposure concentration, or to refined exposure
6546 concentrations based on field measurements, both expressed in mg a.i./kg.

6547 The EPA foliar residue toxicity study is more representative of the conditions of exposure
6548 for bees after a spray event. This study is designed to evaluate the effects from exposure
6549 to dry and aged residues (3, 6 and 24 hours) and thus provide information on the level of
6550 bioavailability and length of residual hazard of the substance.

6551 As discussed in Chapter 9, semi-field, and field studies reproduce more closely the
6552 conditions of exposure of bees in a treated crop. The test provides information on colony
6553 health based on bee survival and development related to actual field application
6554 parameters. Semi-field and field tests can be undertaken with pollinator-attractive crops
6555 treated at flowering (*e.g., Phacelia*), and/or pursued with the actual target crop when a
6556 treatment at flowering cannot be excluded. Semi-field and field tests can also provide

additional information to refine an assessment such as information on potential exposure outside the flowering period of the crop, or through spray drift onto flowers in vegetated areas, or onto flowering weeds within the crop (*e.g.*, in orchards). Finally semi-field and field tests may allow the evaluation of the efficacy of certain risk mitigation measures to limit exposure such as reduced application rates, or modifying application intervals.

Refinement Options – *Apis* Larvae

As for the adults, an option for refinement of exposure is to move from the screening-level default values (*e.g.*, application rate or default consumption rate), to product-specific field modeling or actual measured residues (*e.g.*, in pollen and nectar, honey or beebread) to better quantify exposure of larvae. The same considerations with regard to the generation and use of these data apply.

Additional *Apis* studies that could be relevant for the larval or immature life stages include:

- brood feeding studies (brood development²⁵);
- semi-field studies; and,
- field studies.

The brood feeding study aims at evaluating the effects on the development of the honey bee to derive a NOEC. This NOEC can then be compared to either default (screening-level) concentration estimates or to refined concentrations based on field measurements.

The semi-field and field tests are similar with respect to measurement of effects on adults and both can provide information on colony health and brood development. As discussed elsewhere, field studies typically do not lend themselves to producing a dose/response

²⁵ For example the method of Oomen PA, de Ruijter, A, and Van der Steen J (1992) EPPO Bulletin, 22, 613 - 616.

relationship (*i.e.*, a NOEC or LOEC) due to scale and logistical reasons. Consequently, the assessor must evaluate whether the study results indicate that a minimum level of risk exists (for example, no significant (or limited) difference between test and control plots). Increased levels of refinement toward characterizing effects beyond the laboratory and semi-field may involve assessing impacts of the formulated product in full field tests. Further discussion and guidance on semi-field, and field tests can be found in Chapter 9, and discussion and guidance on brood tests can be found in Chapter 8.

Refinement Options – Non-*Apis* adults

Non-*Apis* bees may differ from honey bees in their exposure and sensitivity to plant protection products. Most non-*Apis* bees are solitary, with single females that forage for pollen and nectar to feed their offspring, construct their nests, and lay eggs (see introduction to non-*Apis* biology). The death of a foraging female implies the cessation of her reproduction (Tasei 2002). In comparison, when a [honey bee] colony loses female workers, the loss may be compensated by the colony, *e.g.*, by engaging inactive workers (Robinson 1992) or through reduced foraging age (Winston and Fergusson 1985), so the colony may continue to develop as a viable unit. For bumble bees some colony recovery is also possible (Schmid-Hempel and Heeb 1991). However, the death of the bumble bee queen in the spring signifies the death of the potential colony that would be formed (Thompson and Hunt 1999).

In comparison to honey bees, the life-history traits of non-*Apis* bees such as sociality and nesting behavior result in a greater importance of certain exposure routes. For example alfalfa leafcutting bees (*Megachile rotundata*) may be more exposed to foliar residues (George and Rinker 1982), ground-nesting bees to soil residues and larvae to pollen residues. These differences mean that representatives of the main non-*Apis* groups for which we have sufficient knowledge should be considered for higher tier testing of a plant protection product for bees when a risk cannot be excluded. Where non-*Apis* species are chosen for higher tier evaluation they should be amenable to experimentation, provide reliable and reproducible results and the methods should comply with

internationally recognized and validated guidelines (e.g., OECD test guidelines). The exact choice of species may be based on the proposed use of the product and on regional [species] considerations; however, it should be possible to extrapolate from “standard” species (e.g., *Bombus* sp.) to reduce the need for unnecessary testing.

Participants of the Workshop proposed that higher tier testing could be conducted with social non-*Apis* bees from the tribes Bombini and Meliponini and solitary bees that are ground-nesting and cavity-nesting (Table 10-5). While techniques exist for both laboratory and field/semi-field tests for *Bombini* spp. (*B. terrestris* and *B. impatiens*) standardization is needed (for review on *Bombus* spp. see van der Steen 2001). Similar tests are in development for [REDACTED]. Sufficient knowledge exists of the ecology of the Bombini and Meliponini tribes to be able to predict the main exposure routes (see Chapter 7, Exposure). For cavity -nesting solitary bees (*Osmia lignaria* and *Megachile rotundata*), laboratory and field/semi-field tests have already been successfully developed (Abbott *et al.* 1998; Alston *et al.* 2007; Ladurner *et al.* 2008). For ground-nesting bees, while primary exposure routes can be predicted, there are not yet the techniques to perform standardized tests on them in the laboratory or the field. Until such techniques are available, the solitary cavity-nesting bees may sufficiently represent “solitary non-*Apis*” as a group, taking into account that for ground-nesting species, soil residues may play a more important route of exposure. Note however, that even for [REDACTED] tribes no validated or internationally recognised test protocols exist which currently limits their inclusion into a risk assessment scheme at this point in time and further research is needed.

Exposure

Similar to the refinement process for adult honey bees, the option for refinement of exposure to adult non-*Apis* bees is to move from the screening-level default values to product-specific field modelling or measurement data to better quantify exposure of non-*Apis* larvae. Table 10-3 provides further guidance on the specific conditions of exposure for non-*Apis* species. The same consideration-s with regard to the generation and use of these data apply (see Section 2.1.1.1).

Effects

As discussed previously, at a screening level in the proposed risk assessment scheme, the adult *A. mellifera* is used as a surrogate for non-*Apis* species. To take into account interspecies variation and the different life-history characteristics a safety factor may be built into the level of concern (LOC) for *Apis* to non-*Apis* (participants of the Workshop considered a 10x factor conservative). Then, as illustrated in the flow chart, if the HQ is less than the adjusted non-*Apis* LOC, then risk is presumed to be low for non-*Apis* species; and, where it is not, further refinement of the ecotoxicity data may be undertaken.

When available, non-target arthropod data may be considered at this stage, as it may provide relevant information on effects (and route specific exposure) to non-*Apis* species see **Table 10-4**.

The nectar feeding parasitoid *Aphidius rhopalosiphi* and the soil-dwelling beetle *Aleochara bilineata* are among the most sensitive of the non-target arthropods tested under the European ESCORT scheme (Candolfi *et al.*, 2001). Adult parasitoids such as *Aphidius* also feed on nectar, which makes it a good non-target arthropod representative for exposure conditions of pollinating species. Similarly, approximately 70% of non-*Apis* bees are ground-nesting (Michener 2000) and the ground-dwelling beetle *Aleochara bilineata*, is tested for sensitivity to plant protection products through sand/soil under the European ESCORT scheme, such that data from its contact toxicity tests may be considered informative for ground nesting bees. In the cases where a refined risk assessment has been triggered for non-*Apis* adults, the data set developed in the European process may contain information on up to 8-10 species in the laboratory and more when semi-field/field testing have to be undertaken for refined risk assessment purposes (Candolfi *et al.*, 2001) (Table 10-4). In these cases, inventories of the species identified in the crops tested may also be useful information in evaluating whether a particular concern is raised for non-*Apis* species which would need to be investigated further. Additional work is needed to understand the relative sensitivity of non-target arthropods typically used in toxicity testing to non-*Apis* bees for which they may be used as surrogates.

6670 **Table 10-4:** Testing Methodologies Developed for the Risk Assessment to Non-Target Arthropods
6671 Developed in the European Process of Evaluation of Pesticides (Candolfi *et al.*, 2001)

Testing scale	Species (and stages tested)
Tier I Laboratory: artificial substrate	<i>Aphidius rhopalosiphi</i> (adults + life cycle ^a) <i>Typhlodromus pyri</i> (protonymphs + life cycle ^a)
Tier II (extended) Laboratory: natural substrate	<i>Aleochara bilineata</i> (adults + life cycle ^a) <i>Aphidius rhopalosiphi</i> (adults + life cycle ^a) <i>Chrysoperla carnea</i> (larvae + life cycle ^a) <i>Coccinella septempunctata</i> (larvae + life cycle ^a) <i>Orius laevigatus</i> (nymphs + life cycle ^a) <i>Pardosa sp.</i> (adults) <i>Poecilus cupreus</i> (adults) <i>Trichogramma cacoeciae</i> (adults + life cycle ^a)
Semi-field	<i>e.g. Poecilus cupreus</i> (adults) Methods can be adapted for many species
Field	Arthropods (populations and communities)

Formatted: Font: Times New Roman Italic, Italic, No underline, Font color: Auto

6672 ^a studies purporting to examine the life cycle of species may focus on a particular aspect of the life cycle and may not
6673 include the entire life cycle.

If relevant NTA data cannot be found, then the assessor may consider selection of an appropriate non-*Apis* species for use in acute laboratory testing (Table 4, see Chapter 8, Hazard, Laboratory); and, data from residue studies and field measurements (*i.e.*, pollen, nectar, foliage and soil) can inform study design with respect to exposure for non-*Apis* (see also Chapter 7, Exposure). For example a plant protection product with high foliar residues would suggest that higher tier testing should be performed on alfalfa leafcutting bees (*Megachile rotundata*) if such bees will visit the crop to harvest nesting material and exposure may occur.

Alternatively, as shown in the flow charts (Figures 2-5), non-*Apis* specific test data for adult contact or oral toxicity can be generated. These data are likely to be in the form of an LD₅₀ (µg/bee), to be used in developing an HQ similar to that for adult *Apis*. For the assessment criteria to be met, the HQ must not exceed the LOC (trigger value), if it not exceed a concern, the assessment does not need to proceed further. Issues of LOC (triggers) and safety factors (such as intra- species variation) may be further discussed by respective regulatory authorities.

Refinement of effects data beyond the laboratory and semi-field/field may involve assessing impacts of the formulated product. Guidance on the type(s) of test(s) may be found in Chapter 8. The field or semi-field tests will monitor behavior and quantify bee mortality and fecundity of one or several selected non-*Apis* species likely to be encountered in the crops to be treated with the product. (see Chapter 8 Hazard, Field for methods and advantages of field tests on non-*Apis* bees). Table 10-5 at the end of this section highlights the availability of laboratory and field tests for representative groups of social and solitary non-*Apis* bees.

Risk Characterization (Estimation)

For both *Apis* and non-*Apis* assessments, when higher level field data are developed, the results are not expected to be applied in a TER and/or quotient context, but may be used directly in the risk assessment. Again, mitigation of potential risk remains as an important pathway to meeting protection goals whether at the screening or higher tier

steps of the analysis. Risk characterization will depend upon the data generated and refinements therein. Below is a brief discussion of refinements to input studies.

Refinement Options – Non-*Apis* Larvae Exposure

A general description of exposure sources for non-*Apis* species (immature stages) is provided in Table 10-3. Where honey bee larvae are exposed primarily in larval food (which is processed pollen) this should be considered when generating a refined [exposure] analysis for non-*Apis* species. For example, pollen sampled in the field or from loads taken at the hive entrance (pollen traps) or from forager bees directly may represent concentrations found in unprocessed food sources. Concentrations of residues from pollen sampled from within hive food stores or from larval cells could be more relevant to honey bee larvae.

Non-*Apis* larvae may also be exposed through contact with the pollen and nectar food provision in the nest. In addition the larvae of ground-nesting bees and cavity-nesting bees which separate their nest cells with soil (for example, *Osmia lignaria*) may come into contact with soil applied plant protection products. Similarly, the larvae of leafcutting bees may come into contact with a plant protection product through residues on the foliage used to construct its nest (see Chapter 7, Exposure). Non-*Apis* species thus have various sources of exposure (*e.g.*, treated soil, or nesting material). Refining potential exposure estimates to non-*Apis* bees to account for the different exposure sources would be difficult to achieve in a specific exposure test. In this case, it would be more appropriate to refine potential exposure and risk through a semi-field or field study (see Chapter 9).

Effects

As discussed earlier, honey bee larvae are proposed as a surrogate for non-*Apis* larvae as there is currently no formal guideline established for testing non-*Apis* larvae.

As the assessor moves through the proposed process, they may consider NTA data, if available, which may provide relevant information to refine potential risk to non-*Apis* species (Candolfi *et al.*, 2001). These tests measure a wide range of endpoints including juvenile and adult survival, fecundity or larval development depending on the species being tested (see Table 10-4). The NTA tests are frequently designed to detect relatively small changes in sublethal endpoints; therefore, an understanding of an application rate that may result in low impact on growth and/or fecundity or other sublethal parameter may be derived. Beyond laboratory tests, refining an understanding of potential effects to non-*Apis* larvae may involve field tests with formulated products (see Chapter 9). While field and semi-field tests have not been specifically developed for ground nesting bees, monitoring of cavity-nesting bees through field or semi-field tests may provide information on some of the larval exposure routes that are unique to non-*Apis* species. Table 10-5 at the end of this section highlights the availability of laboratory and field tests for representative groups of social and solitary non-*Apis* bees.

Risk Characterization (Estimation)

If effects data on non-*Apis* larvae have been generated and provide a NOEC, then this value could be used as in the TER calculation. Both default and refined exposure estimates may also be used in the TER calculation. As noted in the flow charts, should this assessment indicate risks that are not consistent with protection goals, then, either mitigation measures may be considered or the assessment may proceed to further refinement.

Again, when data are generated from field tests, it is not expected that the results are conveyed in a TER (quotient-based) context, but rather incorporated directly into a risk assessment.

Table 10-5. Available laboratory and field tests with representative groups of solitary and social non-*Apis* bees

Study Type	Solitary		Social	
	Tunnel-nesting (tube, wood)	Ground-nesting	Bombini (bumble bees)	Meliponini (stingless bees)
Laboratory	Adult zone: temperate north <i>Megachile rotundata</i> Huntzinger <i>et al.</i> 2008; Scott-Dupree <i>et al.</i> 2009 <i>Osmia lignaria</i> Ladurner <i>et al.</i> 2005; Scott-Dupree <i>et al.</i> 2009 zone: tropics <i>Xylocopa</i> spp. (tests in development)	zone: temperate north <i>Nomia melanderi</i> Johansen <i>et al.</i> 1984; Mayer <i>et al.</i> 1998	zone: temperate north <i>Bombus terrestris</i> Thompson 2001 <i>Bombus impatiens</i> Scott-Dupree <i>et al.</i> 2009; Gradish <i>et al.</i> 2011b ¹	zone: tropics several species, and tests in development Macieira & Hebling-Beraldo 1989; Valdovinos-Nunez <i>et al.</i> 2009
	Larva zone: temperate north <i>Megachile rotundata</i> Peach <i>et al.</i> 1995; Gradish <i>et al.</i> 2011a, Hodgson <i>et al.</i> 2011 <i>Osmia lignaria</i> Abbott <i>et al.</i> 2008 zone: tropics <i>Xylocopa</i> spp. tests in development		zone: temperate north <i>Bombus terrestris</i> Thompson 2001 <i>Bombus impatiens</i> Gradish <i>et al.</i> 2010; Gradish <i>et al.</i> 2011b ¹	zone: tropics tests in development

Formatted: Font: Not Italic, No underline, Font color: Auto

Field	Semi-field	zone: temperate north <i>Megachile rotundata</i> Johansen <i>et al.</i> 1984, Tasei <i>et al.</i> 1988, Mayer & Lunden 1999 <i>Osmia bicornis</i> Konrad <i>et al.</i> 2008, <i>Osmia lignaria</i> (Ladurner <i>et al.</i> 2008)		zone: temperate north <i>Bombus terrestris</i> Tasei <i>et al.</i> 2001 <i>Bombus impatiens</i> Gels <i>et al.</i> 2002	zone: tropics tests in development
	Field	zone: temperate north <i>Megachile rotundata</i> Torchio 1983, <i>Osmia lignaria</i>	Limited availability of tested species <i>Nomia melanderi</i> Mayer <i>et al.</i> 1998	zone :temperate north <i>Bombus terrestris</i> Tasei <i>et al.</i> 2001, <i>Bombus impatiens</i>	zone: tropics tests in development
	Exposure Pollen, nectar, foliar, soil	Can be developed for pollen provisions in the field see Abbott <i>et al.</i> 2008; for foliar residues see George & Rincker 1982		for pollen see Morandin <i>et al.</i> 2005	

¹ Needs standardized guidelines of currently used lab bioassay and microcolony assays.

Soil or Seed Treatment Application for Systemic Substances (also including trunk injection)

Exposure Characterization – *Apis* and *Non-Apis*

While there are differences in the screening-level assessment for calculation of HQs/TERs between sprayed pesticides and systemic substances, the general approach to refining the risk assessment for systemic applications is largely similar to that for spray applications. The primary difference is that for systemic chemistries, exposure levels via contact are largely below that which may be encountered via an oral route of exposure. Table 10-3 should be consulted for exposure routes specific to non-*Apis* bees. For

example, for systemic compounds, leafcutter bees may be exposed orally through the foliage used to build their nests. The most appropriate way to explore this further is through simulating exposure conditions in a semi-field or a field test (see Chapter 9).

As stated earlier, for trunk injection, further data are needed to appropriately describe the range of expected residue concentrations in nectar and pollen that may be used in a risk estimate for this application method. In the future, a compilation of available data could be made, with particular attention to the corresponding injection protocol as it varies with active ingredient and tree species.

Effect Characterization – Adult *Apis*

If risk cannot be excluded at the screening-level assessment, then a tier 2 assessment, based on the 10-d NOEL for young adult honey bees, can be conducted. The 10-day test is an appropriate measure to refine the acute effects endpoint employed in the tier 1 assessment (*i.e.*, oral LD₅₀). The 10-day test may be run based on the default maximum concentration estimated in pollen and/or nectar, or on refined measured values, if these are available (see Refinement Options for the Risk Assessment for more detail on the options). In this case if the TER value exceeds triggers, then one may reach a presumption of low risk to adult honey bees from soil/seed applications. If viable exposure routes exist for the immature stages of either honey bees or non-*Apis* species, (*e.g.*, through contaminated pollen or beebread), then the approaches for refinement to soil/seed scenarios are similar as that for spray treatments (See Chapter 9). For higher tier testing (semi-field and field testing) protocols may be adapted to reflect crops grown from coated seeds or to products applied on/to soil, or for trunk injection. These tests may include monitoring of effects at sowing if measurements from potential exposure via seed dust (if it cannot be excluded or mitigated), or measurements of potential exposure to non-*Apis* species that might frequent the soil.

6795

6796

6797 **Risk Characterization (Estimation)**

6798 Similar principles as for spray application do apply for soil/seed treatments and trunk
6799 injection.

6800

6801 **Conclusions on the Risks and Recommendations**

6802 Concluding a risk assessment is probably the step that best reflects how case-related the
6803 risk assessment process can be. Conclusions could be very brief and simply indicate that
6804 under the assessment that was conducted (*i.e.*, whether it was screening level or a higher-
6805 tiered assessment) the use of the product meets the protection goals of the respective
6806 regulatory authority. However, where a refined risk assessment was triggered, there is a
6807 need to clearly express the following information in the conclusions:

- 6808 ○ what concerns were identified at the screening step;
- 6809 ○ whether/what concerns were identified in higher tier assessments(s)
- 6810 ○ whether results of the higher tier assessment, addressed potential risk concerns;
- 6811 ○ whether/which mitigation measure were considered at different levels of analysis,
6812 and whether the mitigation measure(s) reduced potential risks to an acceptable
6813 level;
- 6814 ○ whether, despite higher tier analysis, all available lines of evidence, and
6815 consideration of mitigation measures, potential risks remain; and,
- 6816 ○ remaining uncertainties [if any] in the risk assessment.

6817 Risk assessment conclusions should give particular emphasis to the four following areas
6818 which are essential in providing appropriate information to risk managers for decision
6819 making. These are:

- 6820 ○ the appropriateness of the available data to assess potential risks posed by the
6821 subject compound, or product;
- 6822 ○ defining the use parameters required in order that the protection goals can be met;
- 6823 ○ characterization of any potential risks, including remaining uncertainties resulting
6824 from a lack of data or deficiencies in the existing data; and,
- 6825 ○ where refined risk analysis indicates risk, characterization should be provided
6826 regarding the growth, reproduction or survival of the organism
6827 (colony/population) and possible interaction(s) with plants and ultimately with
6828 stated protection goals.

6829

6830 Risk assessment conclusions should characterize the possibility of risk based upon the
6831 available lines of information (data, monitoring information, incidents, *etc.*).
6832 Characterization should include discussion of potential risk to any specific life stages or
6833 castes. In certain cases, exposure considerations should focus on gathering more refined
6834 data such as:

- 6835 ○ characterizing spray drift onto adjacent crops/vegetation that are attractive to
6836 bees; and,
- 6837 ○ characterizing exposure to residues that could reach pollen/nectar of the crop
6838 for pre-flowering applications of systemic compounds, and of mobilization of
6839 soil residues in rotational crops (where relevant).

6840

6841 The risk assessment should be able to address the meaning of effects, *e.g.*, a temporary
6842 increase in the mortality of foragers, avoidance of a treated crop over the first days post
6843 treatment, *etc.* Field and in some cases semi-field studies may allow for the monitoring
6844 of colonies/populations over long periods and measurement endpoints may be available
6845 to address these concerns. Unresolved issues regarding time scale (temporal) or spatial

scale could also be addressed through modeling tools when sufficiently developed²⁶. Where uncertainties are related to “borderline” or “minor” effects and do not strictly compromise the protection goals, they may be appropriately addressed by implementing a monitoring study. The advantage of monitoring in this respect is to verify that protection goals will be met under conditions of agricultural practice in the real environment without any effort to control other stress factors.

If a decision is made not to authorize a use, then it must be based on the evidence that protection goals for a particular product cannot be met. The inability to meet protection goals implies that, based upon the available lines of evidence and higher tiered analysis, neither exposure nor hazard can be reduced or avoided, and resulting risks may compromise protection goals. It is the responsibility of both the risk assessor and risk manager to discuss the conditions of the assessment and explore mitigation options, if these are warranted. Both the assessor and manager should consider whether information exists that would determine whether all option to refine or mitigate potential risks have been explored before a final decision is reached.

Recommending risk mitigation measures

Risk mitigation measures mainly aim at reducing the risks through a reduction of exposure. In principle, mitigation may be considered at any stage of the assessment process, such as prohibiting application during bloom. However, certain measures aiming at reducing the level of exposure/residues in relation to effect threshold (NOEL), are more effectively considered during higher tier testing, such as reduced application rates or increased application intervals. Dedicated field testing may be useful when dealing with the product specific measures. The decision to consider mitigation measures at any step of the process involves issues of product efficacy, as well as national policies. A fuller address of mitigation measures is found in Chapter 13.

²⁶ Modeling tools have been successfully developed in other areas of ecotoxicology for that purpose.

6875

6876 **Additional Tools in Support of Risk Assessment and to Inform Risk Management**
6877

6878 Tools that may help to better interpret data (*e.g.*, statistical and mathematical tools)
6879 should be used, particularly when higher tier data have been generated. In addition to
6880 these tools which now often enter into the usual package of risk assessment, modeling
6881 and landscape management approaches are possibly the most promising ones to further
6882 support both risk assessment and risk mitigation provided these tools are sufficiently
6883 vetted and validated against measured data.

6884

6885 **Modeling Tools**

6886 Modeling tools may provide insight on uncertainties identified in risk analyses that
6887 cannot be readily addressed by laboratory and/or field studies. Modeling population
6888 dynamics may be used to simulate the fate of the population or colony over years of
6889 exposure to the product, and/or at a wider scale than the field, and may have the potential
6890 to address generic questions such as colony-level implications from individual-level
6891 effects. Development of models for honey bees and non-*Apis* bees could thus address
6892 general questions such as:

- 6893 ○ What level of mortality or brood loss is of minimal consequence at the colony or
6894 population level?
- 6895 ○ What magnitude and frequency of effects on adult survival and brood success are
6896 required to put the viability of a honey bee colony at risk?
- 6897 ○ How do these thresholds vary according to season?

6898 Answers to these generic issues are of great interest in conducting and interpreting risk
6899 assessments but also in support of decision making. The potential usefulness of modeling
6900 tools is discussed in more detail in Chapter 11.

References

- Abbott, V.A., Nadeau, J.L., Higo, H.A. & Winston, M.L. (2008) Lethal and sublethal effects of imidacloprid on *Osmia lignaria* and clothianidin on *Megachile rotundata* (Hymenoptera: Megachilidae). *Journal of Economic Entomology*, 101, 784-796.
- Alix A., & Lewis G. (2010) Guidance for the assessment of risks to bees from the use of plant protection products under the framework of Council Directive 91/414 and Regulation 1107/2009. OEPP/EPPO, Bulletin OEPP/EPPO Bulletin 40, 196–203.
- Alix, A., Bakker, F., Katie Barrett, Brühl, C.A., Coulson, M., Hoy, S., Jansen, JP, Jepson, P., Lewis, Neumann, P., Süßenbach, D., & van Vliet, P. (2011) ESCORT 3 Linking Non-Target Arthropod Testing and Risk Assessment with Protection Goals. Proceedings of the European Standard Characteristics Of non-target arthropod Regulatory Testing workshop ESCORT 2, Zuiderduin,, the Netherlands, 21-23 March 2010. 8-11th March 2010. In press.
- Alston, D.G., Tepedino, V.J., Bradley, B.A., Toler, T.R., Griswold, T.L. & Messinger, S.M. (2007) Effects of the insecticide phosmet on solitary bee foraging and nesting in orchards of Capitol Reef National Park, Utah. *Environmental Entomology*, 36, 811-816.
- Barrett, K., Grandy N, Harrison EG, Hassan S, & Oomen P, editors. (1994) Guidance document on regulatory testing procedures for pesticides with non-target arthropods, in ESCORT workshop (European Standard Characteristics of non-target arthropod Regulatory Testing), Wageningen, The Netherlands. SETAC Publication. 53 pp.
- Candolfi, M.P., Barrett K.L., Campbell P.J., Forster R., Grandy N., Huet M.C., Lewis G., Oomen P.A., Schmuck R., & Vogt H. 2001. Guidance document on regulatory testing and risk assessment procedures for plant protection products with non-target arthropods, in ESCORT 2 workshop (European Standard Characteristics of non-target arthropod Regulatory Testing), Wageningen, The Netherlands. SETAC Publication, 46 pp.
- Devillers, J., Decourtye, A., Budzinski, H., Pham-Delègue, M.H., Cluzeau, S. & Maurin, G. (2003) Comparative toxicity and hazards of pesticides to *Apis* and non-*Apis* bees. A chemometrical study. SAR and QSAR in Environmental Research, 14, 389-403.
- EPPO. (2010) Environmental risk assessment scheme for plant protection products, Chapter 10. Risk assessment to honey bees, PP 3/10 (3), OEPP/EPPO, Bulletin OEPP/EPPO Bulletin 40, 1–9.
- Gels, J. A., Held, D. W. & Potter, D. A. 2002. Hazards of insecticides to the bumble bees *Bombus impatiens* (Hymenoptera : Apidae) foraging on flowering white clover in turf. *Journal of Economic Entomology*, 95, 722-728.
- George, D.A. & Rinker, C.M. (1982) Residues of commercially used insecticides in the environment of *Megachile rotundata*. *Journal of Economic Entomology*, 75, 319-323.
- Gradish, A. E., Scott-Dupree, C. D., & Cutler, G. C. 2011a. Susceptibility of *Megachile rotundata* to insecticides used in wild blueberry production in Atlantic Canada. Submitted to *Journal of Pest Science*. Submitted August 2011.
- Gradish, A. E., Scott-Dupree, C. D., Frewin, A. J., & Cutler, G. C. 2011b. Lethal and sub-lethal effects of some insecticides recommended for wild blueberry on the pollinator *Bombus impatiens*. *Canadian Entomologist*. Accepted July 2011.
- Gradish, A. E., Scott-Dupree, C. D., Shipp, L., Harris, C. R., & Ferguson G. 2010. Effect of reduced risk pesticides for use in greenhouse vegetable production on *Bombus impatiens* (Hymenoptera: Apidae). *Pest Management Science* 66(2): 142-146.

- Hoerger, F. & Kenaga, E.E. (1972) Pesticide Residues on Plants: Correlation of Representative Data as a Basis for Estimation of their Magnitude in the Environment. In F. Coulston and F. Korte, eds., Environmental Quality and Safety: Chemistry, Toxicology, and Technology, Georg Thieme Publ, Stuttgart, West Germany, pp. 9-28.
- Hogdson, E. W., Pitts-Singer, T. L., & Barbour, J. D. 2011. Effects of the insect growth regulator, novaluron on immature alfalfa leafcutting bees, *Megachile rotundata*. Journal of Insect Science, 11:43.
- Huntzinger, C., James, R. R., Bosch, J., & Kemp, W. P. 2008. Fungicide tests on adult alfalfa leafcutting bees *Megachile rotundata* (F.) (Hymenoptera: Megachilidae). Journal of Economic Entomology, 101, 1088-1094.
- Johansen, C. A., Rincker, C. M., George, D. A., Mayer, D. F., & Kious, C. W. 1984. Effects of aldicarb and its biologically-active metabolites on bees. Environmental Entomology, 13, 1386-1398.
- Konrad, R., Ferry, N., Gatehouse, A. M. R., & Babendrier, D. 2008. Potential effects of oilseed rape expressing oryzacystatin-1 (OC-1) and purified insecticidal proteins on larvae of the solitary bee *Osmia bicornis*. PloS ONE 3(7): e2664. Doi:10.1371/journal.pone.0002664
- Ladurner, E., Bosch, J., Kemp, W. P., & Maini, S. 2005. Assessing delayed and acute toxicity of five formulated fungicides to *Osmia lignaria* and *Apis mellifera*. Apidologie, 36, 449-460.
- Ladurner, E., Bosch, J., Kemp, W.P. & Maini, S. (2008) Foraging and nesting behavior of *Osmia lignaria* (Hymenoptera: Megachilidae) in the presence of fungicides: cage studies. Journal of Economic Entomology, 101, 647-653.
- Maciera, O. J. D., & Hebling-Beraldo, M. J. A. 1989. Laboratory toxicity of insecticides to workers of *Trigona spinipes* (F. 1793) (Hymenoptera: Apidae). Journal of Apicultural Research, 28, 3-6.
- Mayer, D. F., & Lunden, J. D. 1999. Field and laboratory tests of the effects of fipronil on adult female bees of *Apis mellifera*, *Megachile rotundata* and *Nomia melanderi*. Journal of Apicultural Research, 38, 191-197.
- Mayer, D. F., Kovacs, G., & Lunden, J. D. 1998. Field and laboratory tests on the effects of cyhalothrin on adults of *Apis mellifera*, *Megachile rotundata* and *Nomia melanderi*. Journal of Apicultural Research, 37, 33-37.
- Michener, C.D. (2000) The bees of the world. The John Hopkins University Press, Baltimore and London.
- Mineau P., Harding, K.M., Whiteside, M., Fletcher, M.R., Garthwaite, D., Knopper, L.D. (2008) Using reports of honey bee mortality in the field to calibrate laboratory derived pesticide risk indices Environ. Entomol. 37(2): 546-554.
- Miles M.J., and Alix A., 2011. Assessing the comparative risk of plant protection products to honey bees, non-target arthropods and non-Apis bees. Proceedings of the 11th ICPBR meeting, Wageningen, the Netherlands, November 2011. In press.
- Morandin, L. A., Winston, M. L., Franklin, M. T., & Abbott, V. A. 2005. Lethal and sub-lethal effects of spinosad on bumble bees (*Bombus impatiens* Cresson). Pest Management Science, 61, 619-626.
- Oomen PA, de Ruijter, A, and Van der Steen J (1992) EPPO Bulletin, 22, 613 - 616.
- Peach, M. L., Alston, D. G., & Tepedino, V. J. 1995. Sublethal effects of carbaryl bran bait on nesting performance, parental investment, and offspring size and sex ratio of the alfalfa leafcutting bee (Hymenoptera: Megachilidae). Environmental Entomology, 24, 34-39.
- Robinson, G.E. (1992) Regulation of division of labor in insect societies. Annual Review of Entomology, 37, 637-665.

- Schmid-Hempel, P. & Heeb, D. (1991) Worker mortality and colony development in bumblebees. *Bombus lucorum* (L.) (Hymenoptera, Apidae). Bulletin of the Swiss Entomological Society, 64, 93-108.
- Scott-Dupree, C. D., Conroy, L., & Harris, C. R. 2009. Impact of currently used or potentially useful insecticides for canola agroecosystems on *Bombus impatiens* (Hymenoptera: Apidae), *Megachile rotundata* (Hymenoptera: Megachilidae), and *Osmia lignaria* (Hymenoptera: Megachilidae). Journal of Economic Entomology, 102, 177-182.
- Tasei, J. N. (2002) Impact of agrochemicals on non-Apis bees. In J. Devillers and M.-H. Pham-Delegue [eds.], Honey bees: estimating the environmental impact of chemicals. Taylor & Francis, New York.
- Tasei, J. N., Carre S., Moscatelli, B., & Grondeau, C. 1988. Recherche de la D.L. 50 de la deltamethrine (Decis) chez *Megachile rotundata* F. Abeille pollinistrice de la luzerne (*Medicago sativa* L.) et des effets de doses infralethales sur les adultes et les larves. Apidologie 19 (3) 291-306.
- Tasei, J. N., Ripault, G., & Rivault, E. 2001. Hazards of imidacloprid seed coating to *Bombus terrestris* (Hymenoptera: Apidae) when applied to sunflower. Journal of Economic Entomology, 94, 623-627.
- Thompson, H. 2001. Assessing the exposure and toxicity of pesticides to bumblebees (*Bombus* sp.). Apidologie, 32, 305-321.
- Torchio, P. F. 1983. The effects of field applications of naled and trichlorfon on the alfalfa leafcutting bee, *Megachile rotundata* (Fabricius). Journal of the Kansas Entomological Society, 56, 62-68.
- U. S. Environmental Protection Agency. 2004. Overview of the Ecological Risk Assessment Process in the Office of Pesticide Programs, U. S. Environmental Protection Agency Endangered and Threatened Species Effects Determinations. Office of Chemical Safety and Pollution Prevention, Washington, DC. [HYPERLINK "<http://www.epa.gov/espp/consultation/ecorisk-overview.pdf>"]
- U.S. Environmental Protection Agency. 1992. Framework for ecological risk assessment. Washington, DC: Risk Assessment Forum, U. S. Environmental Protection Agency. EPA/630/R-92/001.
- U.S. Environmental Protection Agency. 1998. Guidelines for Ecological Risk Assessment. Washington, DC: Risk Assessment Forum, U. S. Environmental Protection Agency. EPA/630/R-95/002F
- Valdovinos-Nunez, G. R., Quezada-Euan, J. J. G., Ancona-Xiu, P., Moo-Valle, H., Carmona, A., & Sanchez, E. R. 2009. Comparative toxicity of pesticides to stingless bees (Hymenoptera: Apidae: Meliponini). Journal of Economic Entomology, 102, 1737-1742.
- Van der Steen, J.J.M. (2001) Review of methods to determine the hazard and toxicity of pesticides to bumblebees. Apidologie, 32, 399-406.
- Vaughn, M., Shepherd, M., Kremen, C., & Black, S.H. (2007) Farming for Bees. The Xerces Society, Portland, OR. 44 pp.
- Winston, M. 1987. The Biology of the Honey Bee. Harvard University Press, Cambridge, Massachusetts. ISBN 0-674-07409-2.
- Winston, M.L. & Fergusson, L.A. (1985) The effect of worker loss on temporal caste structure in colonies of the honey bee (*Apis mellifera* L.). Canadian Journal of Zoology, 63, 777-780.

CHAPTER 11 ECOLOGICAL MODELING FOR PESTICIDE RISK ASSESSMENT FOR HONEY BEES AND OTHER POLLINATORS

Grimm, V.¹, Becher, M.A., Matthias-B.^{2*} Kennedy, P.^{2*}, Thorbek, P.,^{3*} and, Osborne, J.^{2*}

Formatted: No underline, Font color: Auto, Superscript

* Was not a participant of the SETAC Pellston Workshop on Pesticide Risk Assessment
for Pollinators

¹ Helmholtz Centre for Environmental Research – UFZ, Leipzig, Germany

Formatted: No underline, Font color: Auto, Superscript

² Rothamsted Research, Harpenden, Hertfordshire, UK

³ Syngenta, Environmental Safety, Jealott's Hill International Research Centre, Bracknell,
UK

⁴ Currently at University of Exeter, Cornwall Campus, Penryn, Cornwall, UK

Formatted: No underline, Font color: Auto, Superscript

Introduction

Current pesticide risk assessment for honey bees is based on laboratory tests and on semi-field and field studies. Risk assessment schemes focus on quotients of the hazard imposed by a compound and the predicted exposure to this compound in the field. Depending on this quotient, in a tiered approach individual larvae and adults or entire experimental colonies are tested under confined or open field conditions. This scheme provides a wealth of important information for risk assessment. Test methods, experimental designs, standardization, and new and comprehensive endpoints are under continuous development and will help improve the efficiency and reliability of current risk assessment schemes.

There are, however, a number of questions relevant for ecological risk assessment that cannot be fully answered with laboratory and field studies. Ecological risk assessment tries to determine unacceptable risk on populations but it remains unclear how to

establish whether an effect is unacceptable or not (Hommen *et al.* 2010). Tests focusing on the individual organisms deliver information on mortality or sub-lethal effects under laboratory conditions, but leave uncertain what these effects mean at the population level, for example, whether or not they impair the ability of the entire colony to persist, to cope with other stressors, and to reliably provide services such as honey production and pollination.

Formatted: Font: Italic, No underline, Font color: Auto

To assess effects on natural populations in general, ecological factors such as adaptive behavior, population structure, density dependence, exposure patterns, landscape structure, and species interactions need to be taken into account (Forbes *et al.* 2009). Additionally, for social insects such as honey bees, it needs to be considered that the reproductive unit is not the individual worker bee but the entire colony and its queen. The colony and its functioning can be considered as a complex net of buffer mechanisms that has evolved to increase the fitness of the queen. The loss of individual worker honey bees might thus be less significant than in solitary species; ~~(B) beekeepers however, may see it differently if honey harvest is impaired.)~~ On the other hand, buffer mechanisms have only certain capacities. We cannot easily know these capacities and how they are affected by other stressors such as varroa mites (*Varroa destructor*), viruses, changes in landscape, or beekeeping practices.

Formatted: Font: Italic, No underline, Font color: Auto

Semi-field and field studies allow inclusion and manipulation of some ecological factors, but certainly not all of them in all possible combinations within experimentally controlled conditions. They are expensive, time-consuming, require interpretation by experts, and may still be inconclusive as sufficiently controlled conditions are rarely achievable under field conditions. In addition, behavioral responses of colonies and foraging bees show large variations that can make it difficult to obtain any identifiable effects of a certain factor on honey bee populations.

Ecological models provide a tool to overcome limitations of empirical studies. They are widely used in theoretical and applied ecology because ecological systems are usually too complex, develop too slowly, and cover areas that are too large to be studied solely via

controlled laboratory or field experiments. In the context of regulatory risk assessment, ecological models are often grouped with organism~~individual~~-level models addressing toxicokinetics and toxicodynamics (TK-TD) or dynamic energy budgets (DEB) to “mechanistic effect models” (Grimm *et al.* 2009). This terminology was introduced to distinguish these models, which simulate processes related to effects of pesticides on organisms and populations, from fate models which focus on the fate of pesticides in water and soil, and from statistical or empirical models, which establish correlative, but not causal, relationships between factors. Ecological models can address all levels of organization beyond the individual, but ecological risk assessment usually focuses on populations (Schmolke *et al.* 2010a, Galic *et al.* 2010). In this chapter we give a brief introduction into the rationale and approaches of ecological modeling of population dynamics. We present an example model to demonstrate the potential insights that can be gained from such ecological models, summarize current modeling practice and describe recent attempts to establish good modeling practice, which is needed to make mechanistic effect models applicable for regulatory risk assessment. We then provide an overview of existing models of honey bee colonies and give recommendations for the potential use of these models for pesticide risk assessment. Although this chapter focuses on honey bees, we will also briefly discuss how ecological modeling could support risk assessment of non-*Apis* pollinators. We will not discuss models addressing ecosystem services, which are important but belong to a different category of models and address different questions (Kevan *et al.* 1997, Williams *et al.* 2010).

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Example model: common shrew

The following example model demonstrates how well-tested population models can be used to extrapolate the effects of toxicants observed at the individual level to the population level while considering different exposure patterns and landscape structures. Since such a demonstration does not yet exist for honey bees or other pollinators, we use a model of the common shrew (*Sorex araneus* L.). Wang and Grimm (2007) developed an individual-based population model of this species, which is a common insectivore.

The purpose of the model was to explore the population-level consequences of acute mortality induced by pesticides.

The key behavior of the common shrew, which determines its response to heterogeneity in habitat quality and to the local density of conspecifics, is territoriality, *i.e.*, the aggressive defense of a certain area to secure resources and habitat. Therefore, the model is spatially explicit and represents each individual of the population, its life cycle, and its territorial behavior. The habitat consists of hexagonal units of 5 m diameter which are characterized by habitat type (*e.g.*, grassland or hedge) and level of food resources on a given calendar day. Individuals are characterized by the variables age, gender, developmental stage (lactating offspring, subadult, adult), fertility (fertile, infertile; applies to females only), pregnancy, and home range. Home ranges are a set of habitat units occupied by a certain individual.

The processes of the model comprise development, mortality, reproduction, home range dynamics, dispersal, and mating. The model proceeds in daily time steps and covers an area of 25 ha. A full description of the model is given in Wang and Grimm (2007) using the standard format for describing individual-based models, ODD (Overview, Design concepts, Details; Grimm *et al.* 2006, 2010). The model allows the fate of each individual and its territory to be followed, day by day, in heterogeneous landscapes consisting of different habitat types (Figure 11-1).

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto




Figure 11-1. Output of an individual-based model of the common shrew (Wang and Grimm 2007) on a certain day of the simulation. Black lines delineate home ranges of males, gray lines of females. Home ranges in cereal fields need to be larger than in grassland or hedges because of lower resource levels. Home ranges are drawn as minimum convex polygons by connecting the outmost cells occupied by their owners (from Wang and Grimm 2007).

Parameters affecting home range sizes were calibrated to match observations of a certain field study. Likewise, daily mortality was calibrated to obtain populations able to persist in good habitats. All other model parameters were taken from field studies. To make sure that the model captures important features of the internal organization of real populations of the common shrew, it was compared to multiple patterns observed in reality (pattern-oriented modeling; Grimm *et al.* 2005, Grimm and Railsback 2005, 2012).

Home range size and location varied with season, habitat type, and shrew density qualitatively similar to what is known from the field. Further patterns successfully tested were: proportion of pregnant and lactating females and the age distribution of juveniles and subadults. Thus, although the model certainly is not realistic in the sense that it takes into account all aspects of real populations, it is realistic enough to qualitatively predict the response of populations to additional mortality.

Formatted: Font: Italic, No underline, Font color: Auto

Accordingly, Wang and Grimm (2010) explore various hypothetical scenarios by applying pesticide-induced mortality on either April 1 or July 15: on that day, all individuals had an additional probability of 10 or 20% of dying. They contrasted orchards with and without 10% or 20% hedges, and compared different endpoints such as population size, daily population growth rate, recovery time, and extinction risk. They found that population size is more sensitive for detecting short-term effects than population growth rates and that landscape structure and timing of application had strong impacts on population recovery. For example, with 20% additional mortality on April 1, the population stabilized in orchards including 20% hedges, but continually declined in landscapes without hedges (Figure 11-2).




Figure 11-2. Population dynamics in orchards with and without 20% hedges with a yearly application of 20% additional mortality on April 1 (from Wang and Grimm 2010).

The model of Wang and Grimm (2007, 2010) can in principle be used for regulatory higher tier risk assessments of small mammals. Its main limitation is that only few empirical studies exist that can be used for parameterizing, testing, and validating the model. But it clearly demonstrates the potential of well-tested ecological models for risk assessment of pesticides. A further exemplary demonstration of this potential can be found in Topping et al. (2009), who analyze, using much more detailed models, scenarios including skylarks, beetles, spiders, and field voles. Galic *et al.* (2010) give an overview

Formatted: Font: Italic, No underline, Font color: Auto

of the types of insights for ecological risk assessment that can be gained from population models. Population models are all based on a models' ability to assess population status after integrating lethal and sublethal effects including behavioral changes, at the individual level.

Rationale and Approaches of Mechanistic Effect Modeling

Ecological models have to be based on conceptual models that reflect our current understanding of the system represented in the model. Conceptual models are usually formulated verbally or graphically, which by itself provides no means for testing whether they are consistent and complete. Modelers therefore use formal notations, based on mathematics and computer logics, to translate conceptual models into a framework that allow rigorous calculation of their consequences. Ecological models are thus, broadly speaking, tools for studying if-then scenarios: *if* we agree on a certain set of simplifying assumptions, *then* we have to accept the consequences predicted by the model. At the beginning of modeling projects, we are usually unhappy with their consequences because they do not match observations, so we revise our assumptions. Model development is therefore an iterative process (Figure 11-3).




Figure 11-3. Tasks of the “Modeling Cycle”, *i.e.*, of the iterative process of formulating, implementing, testing, and analyzing ecological models (after Schmolke *et al.* 2010b). Full cycles usually include a large number of subcycles, for example verification leading to further effort for parameterization or reformulation of the model. The elements of this cycle are used to structure a new standard format for documenting model development, testing, analysis, and application for environmental decision making, TRACE (Schmolke *et al.* 2010b).

The “Modeling Cycle” depicted in Figure 11-3 is relevant for any type of model, but many different types of model design and formulation exist (Schmolke *et al.* 2010a). Simple models, which are formulated via one or a few coupled differential equations, keep track of the processes causing changes in population size, such as mortality, reproduction, or disturbances. They are easy to communicate and understand but usually too poor in structure and mechanisms to be predictive and testable. Matrix models go beyond population size and consider the age, size, or stage structure of populations. They are frequently used to predict population growth rate and the sensitivity of growth rate to changes in mortality or reproduction of certain classes of individuals. Again, matrix models are easy to communicate but, once they are designed to include stochasticity, spatial effects, or density dependence, they have to be run on computers and are therefore

no longer very different from individual-based models (IBMs). Simple matrix models have a standard format and are relatively easy to parameterize and analyze. They project current average conditions into the future and can therefore be used for initial screening, corresponding to lower tier tests in risk assessment, with small or negative population growth rate indicating risk.

~~individual-based models~~ ~~IBMs~~ are computer simulation models in which each individual and its life cycle is represented explicitly (see the common shrew model presented above). Population dynamics and growth rates emerge from what individuals do and how they interact with each other and their environment. Individual-based models ~~IBMs~~ are harder to communicate, parameterize, test and understand than simpler mathematical models, but nevertheless used when one or more of the following factors are assumed to be essential for explaining population dynamics: local interactions, differences among individuals, and adaptive behavior (Grimm and Railsback 2005). Individual-based models ~~IBMs~~ are no longer new but routinely used not only in ecology but also in many other disciplines ranging from behavioral ecology to social sciences, where they are usually referred to as “agent-based” models (Railsback and Grimm 2012). Strategies exist to optimize model complexity (Grimm *et al.* 2005) and to formulate and communicate individual-based models ~~IBMs~~ according to a standard format, the ODD (“Overview, Design concepts, Details”) protocol (Grimm *et al.* 2006, 2010).

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

To use models for pesticide risk assessment, two conflicting criteria for assessing the suitability of models are critical: on the one hand, models need to be complex enough to deliver testable predictions which enable decisions about whether or not the model is a sufficiently good representation of the real world. On the other hand, models need to be simple enough to be thoroughly analyzed and fully understood. Modeling thus requires finding the optimal level of model complexity (Grimm *et al.* 2005, Grimm and Railsback 2012).

Formatted: Font: Italic, No underline, Font color: Auto

Understanding the main process within a model is decisive, otherwise we would be asking for blind faith in output from the equivalent of a black box. For some questions,

simpler models can be sufficient, correctly predicting trends and general mechanisms without making quantitative predictions. For other questions, more accurate predictions are required, which is possible if the models are driven by first principles, such as physiology, stoichiometry, or adaptive behavior, and if enough data are available to directly or indirectly estimate model parameters with sufficient certainty. Highly ecological predictive models have been developed (*e.g.*, Railsback and Harvey 2002, Stillman and Goss-Custard 2010, Topping *et al.* 2009), but all required more than five person years before first versions could be used to support decision making. However, once a predictive model exists, it pays off extremely well because it can then be used as a virtual laboratory to answer a wide range of questions regarding population dynamics under different and possibly new environmental conditions.

Modeling Practice for Risk Assessment

Claims about the high potential of ecological modeling for pesticide risk assessment are not new and have been made for at least 20 years (Barnthouse 1992). In fact, approximately one hundred academic publications exist that use population or other ecological models to explore the effects of pesticides at the population level (Schmolke *et al.* 2010a). Galic *et al.* (2010) summarize the scientific insights of these studies, which are certainly important and contribute to our understanding of the significance of individual-level effects at the population level. Nevertheless, the use of models is still limited ~~a in Europe population models have not yet been used, with very few recent exceptions, for regulatory risk assessment which is also the case in North America.~~ Why is this so? Schmolke *et al.* (2010a) found that most models in this field are not fit for being used for pesticide registrations. The main reason is that criteria for being accepted as a scientific publication, such as novelty, focusing on one main aspect, simplicity, or generality, are less relevant for making a model suitable for basing environmental decisions on their output. In most cases, choice of model structure and complexity was not justified, endpoints directly relevant for regulatory risk assessments were not considered, sources of parameter values were unclear, uncertainty of model output was not communicated, and most importantly, little effort was made to demonstrate that the model was a sufficiently good representation of the real population such that insights

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

gained in the model world could be transferred to the real world with sufficient confidence.

This situation is, however, changing in Europe. Two main challenges to make models fit to be used for regulatory risk assessment are (1) the establishment of Good Modeling Practice (GMoP), so that both industry and regulators have clear criteria for how to create and assess models, and (2) the lack of researchers who are well-trained both in ecological modeling and risk assessment (Thorbek *et al.* 2010). Therefore, *EFSA (Chemical Risk Assessment Models) project*, a large research and training network funded by the European Commission, was launched in 2009 (Grimm *et al.* 2009; [[HYPERLINK "http://cream-itn.eu"](http://cream-itn.eu)]), includes 13 academic institutions and 10 partners from industry, consulting firms, and regulatory authorities, will run until 2013, and will deliver both guidelines for GMoP and more than 20 young researchers trained in modeling and risk assessment. Moreover, models will be developed which, for indicator species and *risk assessment* questions, are good demonstrations for how models can be used for regulatory risk assessments.

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Elements of GMoP have long been identified but are still widely ignored. The real challenge is to get these elements accepted and used in practice. Schmolke *et al.* (2010b) found that for this, regulators or, more generally, decision makers need to be involved, direct benefits for modelers who follow GMoP (which usually requires extra effort) need to be identified, and a consistent terminology needs to be established. Therefore, the basic approach of CREAM in establishing GMoP is to define and use a standardized documentation framework, TRACE (TRANsparent and Comprehensive Ecological Modeling). Schmolke *et al.* (2010b) suggest the use of the structure of the iterative modeling cycle (Figure 3) as the basis for a general and standardized document structure. As a result, all models that are to be used to support pesticide registration and come with a TRACE documentation as a supplementary document, can be assessed in exactly the same way. Regulators will know that, for example, sensitivity analysis will be described in Section 2.2, the conceptual model underlying the model's design can be found in Section 1.2. Modelers, on the other hand, will know that regulators will expect to see, for

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

example, a documentation of sensitivity analysis, at some point, so they can use the TRACE format as a checklist. The direct benefit for the modeler is that the TRACE format helps keeping notes in the “modeling notebook”, which corresponds to “lab journals” in laboratories, in a format that later can directly be transferred to TRACE documents.

Once a critical number of example TRACE documents exist, by the end of the CREAM project, more specific assessment guidelines can be developed that help standardize the use of ecological models for regulatory risk assessment. This includes the agreement on standard scenarios, species, landscapes, ecoregions, and population-level endpoints. Honey bees and pollinators will play an important role in this context, due to their unique significance for biodiversity and ecosystem services.

Existing Models of Pollinators

Quite a few models exist that address various aspects of honey bee behavior and ecology (for an overview, see section 5.4. in Schmickl and Crailsheim 2007). However, there are surprisingly few sufficiently described models addressing dynamics of non-swarming, managed colonies which include the full life cycle of worker bees from a single hive over several years such that colony-level effects can be assessed (Table 11-1).

Table 11-1 Colony models that include the full life cycle of worker bees and run long enough, *i.e.*, two or more years, to assess status and survival of a model colony. The third column lists additional factors included in the model that can affect colony status and survival.

Reference	Purpose of model/Question addressed	Additional factors
Omholt (1986)	Explain brood-rearing peaks in non-swarming colonies	
DeGrandi-Hoffman <i>et al.</i> (1989)	Simulate honey bee population dynamics to support management	

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Martin (2001)	Explain the link between varroa mite infestation and honey bee colony failure, including the effects of virus diseases	Varroa and virus infections
Al Ghamdi and Hoopingarner (2004)	Develop a tool for research and management; interaction between varroa and honey bees	Varroa
Thompson <i>et al.</i> (2005), (2007)	Explore effect of an insecticide on colony dynamics	Pesticides
Schmickl and Crailsheim (2007)	Explore significance of important feedback loops, pollen supply, and brood cannibalism	Swarming
Becher <i>et al.</i> (2010)	Does temperature during development affect colony survival?	
Khoury <i>et al.</i> (2011)	Impact of increased forager mortality on colony growth and development	

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

7395

7396

7397 Two of these models are interesting from an academic point of view, but too simple to be
7398 tested against observed data (Omholt 1986, Khoury *et al.* 2011). Nevertheless, theoretical
7399 insights can guide the design and analysis of more complex models. For example,
7400 Khoury *et al.* (2011) implement two feedback mechanisms: between colony size and
7401 brood production and between the number of foragers and recruitment to foraging, which
7402 have been referred to as “social inhibition” (Leoncini *et al.* 2004). They found that if
7403 forager mortality exceeds a certain threshold, the colony can no longer maintain itself and
7404 will decline to extinction. These feedback mechanisms have been observed empirically
7405 and the results of Khoury *et al.* (2011) suggest that their significance should be further
7406 tested in more detailed models, containing a colony’s age structure, nectar and pollen
7407 stores, further feedback mechanisms, and variable environmental drivers.

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

7409 The model by Thompson *et al.* (2005, 2007) is also simple and considers the abundance
7410 of brood, in-hive and forager bees. This model was originally used in combination with a
7411 more detailed population model of varroa mites (Wilkinson and Smith 2002), but
7412 Thompson *et al.* left out the varroa part and added assumptions about the effects of a

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

certain type of pesticide (insect growth regulators), based on observations from their own experiments. Such re-use of models for new questions can be problematic, since the model's design may not be appropriate for the new questions. In this case, model resolution is likely to be too coarse to make robust predictions, still, the model serves as a demonstration of how, in principle, individual-level effects of pesticides can be included in colony models of honey bees.

The models presented by Martin (2001) and Al Ghamdi and Hoopingarner (2004) are modifications of BEEPOP (DeGrandi-Hoffman *et al.* 1989), a simulation model proceeding in time steps of one day and representing cohorts (or age classes) of eggs, brood, and adults of both worker bees and drones (Figure 4). BEEPOP distinguishes between in-hive and foraging bees, whereas the other two models do not. Colony dynamics are driven by the queen's egg-laying rate, which is mainly driven by weather, in particular temperature and photoperiod. Additionally, these models include feedbacks between egg-laying and colony size. Drones are mainly included because mites are more attracted by drone cells and mite reproduction is higher in drone cells, so that the proportion of drone cells has an important impact on the dynamics and effects of varroa infestation.

Formatted: Font: Italic, No underline, Font color: Auto

BEEPOP has been augmented by detailed modules for including effects of pesticides (Bromenshenk *et al.* 1991). The module BEETOX included a toxicity database for more than 400 chemicals and calculated lethal and sub-lethal effects for specific exposures; the module BEEKILL allowed the linkage these effects to exposure scenarios and feed the resulting changes in mortality, development and longevity into the colony model. Unfortunately, details of these modules were not published and the software implementing them, PC BEEPOP, is unlikely to run on modern computers. It also seems that it has never been used for regulatory risk assessment of pesticides, probably because it was very much ahead of its time. Nevertheless, the design of PC BEEPOP is interesting since it allows one to test effects of pesticides on honey bee colonies in a standardized way.

Formatted: Font: Italic, No underline, Font color: Auto

Becher *et al.* (2010) include the effect of colony size and structure on heating and the resulting temperature in the brood chamber. It had been observed that brood developed under higher temperatures proceeds faster from in-hive tasks to foraging. It turns out, however, that this has little effect on the dynamics and status of the colony. This is a good example of the role of models for relating individual-level effects to colony-level phenomena. Without the model, it would have been impossible to predict this relationship for the temperature effect, simply because colony structure, environmental drivers, and feedback mechanisms are too complex to be even qualitatively assessed just by reasoning. Negative results, as in this case, *i.e.*, the working hypothesis is shown to be false, are no less important than positive results.

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto




Figure 11-4. Conceptual diagram of the colony model of Martin (2001). Solid lines represent the flow of individuals between developmental stages and dotted lines represent influences (from Martin 2001).

The most complex colony model is HoPoMo (Schmickl and Crailsheim 2007). In contrast to all other colony models, HoPoMo is not entirely driven by demographic rates, such as egg-laying rate of the queen and age- and task-dependent mortalities. Rather, the

current number, stage, age, and task of bees are used to calculate the estimated requirements of the colony for nectar and pollen. Depending on current stocks of these two resources, the proportion of worker bees devoted to different tasks is dynamically reallocated every day. The three different tasks distinguished are nursing, food processing, and foraging. HoPoMo includes a large number of further feedbacks between the current state of the colony, or parts of it, and process rates. HoPoMo consists of 60 difference equations, which are all well documented and biologically justified. The model has been thoroughly tested, including sensitivity analyses and exploration of certain mechanisms. It reproduces several empirical patterns and correctly predicts at least one feature of real colonies that was not used to calibrate or design the model, but emerged during analysis of the full model: in smaller model colonies, with no more than 20,000 brood cells, the number of unsealed brood cells shows oscillations similar to what has been observed in real experimental hives. The model has, however, not yet been used to answer any specific question about how colonies respond to environmental stress, such as exposure to a pesticide.

Two of the colony models in Table 1 also consider infestation with varroa mites. Phoretic mites, i.e. mites attached to worker bees, enter brood cells about one day before they are sealed and reproduce within these brood cells. Emerging mites try to infest another brood cell or become phoretic, and thereby spread varroa infestation. During the interaction with brood and worker bees, mites transfer viruses, for example Deformed Wing Virus (DWV), or Acute Paralysis Virus (APV). The model of Martin (2001) integrates honey bee and mite population dynamics and the effects of viruses. It shows, for example, that the less virulent DWV will become more widely spread than APV, and that mite control measures need to be taken before the longer-lived overwintering bees emerge. Further varroa models, which focus on various aspects of varroa population dynamics, but are coupled to much simpler colony models than BEEPOP, include Omholt and Crailsheim (1991), Fries *et al.* (1994), Martin (1998), Calis *et al.* (1999), Wilkinson and Smith (2002), and DeGrandi-Hoffman and Curry (2005). For the purpose of pesticide registration, it seems necessary to use models that allow inclusion of varroa infestation because, at least in Europe and North America, varroa is a ubiquitous stressor. It

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

remains as an open question, the way in which varroa infestation could or should be taken into account for pesticide registration. Should decisions be made to ensure safety under a worst-case assumption of high infestation where colonies have high risk of collapsing even without exposure, under an assumption of effective varroa management by beekeepers, or should average infestation levels based on national or international surveys be used? These questions cannot be answered scientifically, but robust, well-tested, and predictive colony models which allow inclusion of varroa and possibly other stressors would support decisions by quantitative arguments.

Currently, only the model by Martin (2001) is suitable to consider different, but simultaneous stressors. On the other hand, HoPoMo is a more realistic model and includes feedback mechanisms which seem to be important for the functioning of a colony; in particular, HoPoMo is driven by pollen and nectar stores, demand, and availability in the landscape. If HoPoMo could include a module representing varroa infestation and virus effects, it would currently be the most suitable model for pesticide risk assessment. However, changes in landscape structure, crop plants and their rotation, and agricultural practice also affect honey bee colony performance so that, for registration purposes, a model should also allow such factors to be represented with sufficient detail regarding spatial structure, crop dynamics and rotation, and foraging behavior. Adding such a module to HoPoMo would make an already very complex model even more complex and therefore harder to test and understand. Therefore, a colony model that includes varroa, viruses, and foraging in heterogeneous landscapes should preferably be similar in design to the model of Martin (2001) but include the most important feedbacks included in HoPoMo.

A well-tested prototype of such a model, dubbed “BEEHAVE”, was developed by M. Becher and co-workers at Rothamsted Research, UK, in 2009-2013⁴. Its purpose is not pesticide registration per se, but to explore the possible reasons for honey bee decline and collapse as well as devising strategies for improving honeybee health. For this purpose, the model includes varroa, viruses, and explicit foraging in heterogeneous landscapes. The option to include pesticide effects, or other additional stressors subsequently shown

to be important, was considered from the beginning of this modeling project and a design developed to enable this to be relatively straightforward. The model and its computer code and user manual will be made available in the summer of 2012 (it is being completed, it is available), so that other researchers can test the model independently and use it or the model for various purposes.

As for non-*Apis* pollinators, fewer models exist than for honey bees. The population model of the solitary red mason bee, *Osmia rufa* (L.) (Ulbrich and Seidelmann 2000) shows, however, that if sufficient empirical knowledge of a species' ecology and behavior exists, developing a population model is straightforward and can lead to important insights. The purpose of the *Osmia* model was predicting the risk of extinction of this solitary species in different types of habitat, which are characterized by the amount and quality of food they provide. The model is individual-based and focuses on cell construction and maternal investment in brood cells. The life stages distinguished are eggs, larvae, imagines in cocoons, males, pre-nesting females, and nesting females. A key decision of nesting females is the sex determination of their brood. The first brood cells are always daughter cells but at some point the mother bee switches to construction of son cells. In the model it is assumed that this switching depends on the mother's weight, i.e. heavier bees produce more daughter cells. Likewise, size of progeny is related to their mother's weight. As a measure of habitat quality, time for cell construction was used as a proxy (Gathman 1998). In this way the model can be linked to habitat quality without explicitly representing habitat and foraging. As stressor, parasites were taken into account, with parasitism rates being higher for longer cell construction times. Mean population size and extinction risk were taken as population-level endpoints.

Mitesser *et al.* (2006) developed a colony model for the halictid bee *Lasioglossum malachurum* to explore the emergence of activity cycles, which are typical for some annual eusocial "sweat bees" (Halictidae). The model is very simple and includes only two state variables, the numbers of workers and of sexuals; the time horizon considered is so short that mortality of sexuals could be ignored. Still, there is no principle reason why it should not be possible to develop an age-structured model, similar to BEEPOP or BEEHAVE that includes the full life cycle.

Formatted: Font: Italic, No underline, Font color: Auto

A very interesting individual-based model of bumble bees was developed by Hogeweg and Hesper (1983). It includes the full life cycle of individuals and different types of behaviors, and is, like HoPoMo, to a large degree driven by food collection and consumption and time budgets for certain activities. Focus, though, is less on colony dynamics per se but on explaining division of labor within the colony and so-called “dominance interactions”, by which this division emerges. This model was about 20 years ahead of its time as individual-based models, which go beyond demographic rates and include behavior, have only become more widely used within the last 10 years. It would certainly be worthwhile to re-implement this model and try to adapt it to new questions. Whether or not it would be sufficient to just assume division of labor, or have mechanisms included that allow this division to emerge, remains an open question. In general, eusocial non-*Apis* pollinators have simpler and smaller colonies. This implies that, although they benefit from cooperative activities, they do not maintain buffer mechanisms and reserves which would be as powerful as in honey bee colonies. They also show greater foraging activity, to compensate for the lack of maintained reserves, potentially increasing risk of pesticide exposure.

A bottleneck for developing models for non-*Apis* pollinators might be the lack of data about their foraging behavior in real landscapes since exposure to pesticides to a large extent depends on foraging. Detailed foraging models need to be developed and parameterized and tested using corresponding field studies and experiments

2012, J Everaars and Dornmann 2013 *unpubl. manuscript*. Do we need a citation for this as well?

Discussion

Sophisticated tests and schemes exist to assess the risk that pesticides impose to honey bees. Current regulations and thresholds seem to be conservative but still leave many questions open. The difficulty problem is that to confirm whether or not the -without performing controlled, long-term experiments with colonies in real landscapes, exposed not only to pesticides but also other stressors (including beekeeping practices)-, we cannot

Formatted: No underline, Font color: Auto, Highlight

Formatted: No underline, Font color: Auto, Highlight

~~be certain whether or not a sublethal or lethal effect(s) of pesticides, observed in~~
~~laboratories or field experiments, translate into a significant risk to~~ ~~implies an~~
~~unacceptable risk to the functioning and/or survival of a colony.~~ ~~controlled, long-term~~
~~experiments are required to take into account the individual and combined effects of~~
~~pesticides and other stressors on colonies at the landscape scale.~~ For example, if on a
normal day an average of 100 dead bees is found around the hive, and during acute
pesticide exposure 300 dead bees are found, is this of any significance to the colony?
Likewise, if larvae develop more slowly, or worker bees have a shortened lifespan due to
pesticides, how does this affect colony functioning in terms of honey production and
pollination? Answering such questions with real experiments might be possible to some
degree, but would require enormous resources.

Ecological models could, in principle, compensate for this limitation of empirical
approaches. And there are, indeed, fields where models are used to support
environmental decision making. For example, recent regulations of wildlife diseases,
such as rabies or classical swine fever, are based on predictions of models which are quite
similar to the common shrew model presented earlier (Thulke and Grimm 2010). In some
federal states of Germany, forest management plans on the time scale of 10 – 20 years are
based on predictions of the individual-based forest model SILVA (Pretzsch *et al.* 2002).
Common features of these and other ecological models used for decision making is that
their development took at least five years, and their acceptance by the responsible
decision makers about 10 years.

Establishing the use of ecological models to assess risk of pollinators, in particular honey
bees, can nevertheless be achieved faster. Well-tested and documented models already
exist, which can at least be used, preferably in joint workshops, to discuss and learn the
use of such models for higher-tier risk assessments. BEEHAVE, the model currently
developed in the UK, holds further promise, in particular because it includes the main
potential stressors of colonies and foraging in heterogeneous landscapes. Ideally, to make
BEEHAVE fit for use with pesticide registrations, it would need to be used in one or
more workshops where researchers from all three sectors involved in pesticide risk

Formatted: Font: Italic, No underline, Font color: Auto

assessment, industry, regulators, and academia, agree on standard model scenarios, endpoints, and risk assessment schemes. BEEHAVE is described in a standard format (ODD, Grimm *et al.* 2006, 2010), its development and analysis will be available as a TRACE document, and it is implemented in a software platform, NetLogo (Wilensky 1999), that is freely available and easy to learn. BEEHAVE is thus designed to be tested, used, and developed not only by its developers but by the scientific and user community involved in honey bee research and management.

Formatted: Font: Italic, No underline, Font color: Auto

The good news is that honey bee models are less limited by data for parameterization than models of most other species. Experimental managed colonies are relatively easy to observe in the laboratory and field. Bee behavior has been investigated a lot, and beekeepers accumulated sound empirical knowledge on how colonies respond to environmental events and beekeeping practices. Foraging still is a bottleneck in empirical knowledge, but remote sensing techniques can be used now to follow the flight path of individual foragers (Riley *et al.* 1996, Osborne *et al.* 1999). Moreover, in response to the decline or collapse of honey bees in Europe and North America, large international networks such as COLOSS (Neumann and Carreck 2010) compile and analyze huge amounts of data, which can be used to test model predictions.

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Ecological models are no silver bullet to solve all problems of pollinator risk assessment, but they are a valuable and needed tool for extrapolating individual-level effects to the colony-level, to overcome important limitations of field studies, and to explore endpoints that quantify adverse effects not only on pollinators *per se* but also on biodiversity and ecosystem services.

Formatted: Font: Italic, No underline, Font color: Auto

References

- Al Ghamdi, A., Hoopingarner, R. 2004. Modeling of honey bee and varroa mite population dynamics. Saudi.J.Biol.Sci. 11:21-36.
- Barnthouse, L.W. 1992. The role of models in ecological risk assessment: A 1990's perspective. Environ. Toxicol. Chem. 11: 1751-1760

- Becher, M. A., H. Hildenbrandt, C. K. Hemelrijk, and R. F. A. Moritz. 2010. Brood temperature, task division and colony survival in honeybees: A model. *Ecological Modelling* 221:769-776.
- Bromenshenk, I.J., Daskocil, J., Olbu, G. J., DeGrandi-Hoffman, G., Roth, S. A. 1991. PC BEEPOP, an ecotoxicological simulation-model for honey-bee populations. *Environmental Toxicology and Chemistry* 10: 547-558.
- Calis, N.M., Fries, I., Ryrie, S. C. 1999. Population modelling of *Varroa jacobsoni* Oud. *Apidologie* 30 :111-124.
- DeGrandi-Hoffman, G., S. A. Roth, G. L. Loper, and E. H. Erickson. 1989. Beepop - A honeybee population-dynamics simulation-model. *Ecological Modelling* 45:133-150.
- DeGrandi-Hoffman, G., Curry, R. 2005. Simulated population dynamics of Varroa mites in honey bee colonies: Part II - What the VARROAPOP model reveals. *American Bee Journal* 145: 629-632.
- Eversmans, J. 2012. The response of solitary bees to landscape configuration with focus on body size and nest-site preference. PhD dissertation, Martin-Luther-University Halle-Wittenberg, Germany.
- Eversmans, J., and C.F. Dommann. 2013. A simulation model for non-Apis bees: solitary bees foraging and competing for pollen. In: Devillers, J. (ed.) In Silico Bees. CRC Press (in press).
- Forbes, V. E., U. Hommen, P. Thorbek, F. Heimbach, P. van den Brink, J. Wogram, H.-H. Thulke, and V. Grimm. 2009. Ecological models in support of regulatory risk assessments of pesticides: developing a strategy for the future. *Integrated Environmental Assessment and Management* 5:167-172.
- Fries, I., Camazine, S, Sneyd, J. 1994. Population dynamics of *Varroa jacobsoni* - a model and a review. *Bee World* 75: 5-28.
- Galic, N.G., Hommen, U.; Baveco, J.M.; Van den Brink, P.J. 2010. [HYPERLINK "http://edepot.wur.nl/143793" \t "_blank"]. *Integrated Environmental Assessment and Management* 6:338 - 360.
- Gathmann, A. 1998. Bienen, Wespen und ihre Gegenspieler in der Agrarlandschaft: Artenreichtum und Interaktionen in Nisthilfen, Aktionsradien und Habitatbewertung. – Cuvillier Verlag, Göttingen.
- Grimm V. & Railsback, S. F. 2005 Individual-based modeling and ecology. Princeton, NJ, USA: Princeton University Press.
- Grimm, V., E. Revilla, U. Berger, F. Jeltsch, W. M. Mooij, S. F. Railsback, H.-H. Thulke, J. Weiner, T. Wiegand, and D. L. DeAngelis. 2005. Pattern-oriented modeling of agent-based complex systems: lessons from ecology. *Science* 310:987-991.
- Grimm V, Berger U, Bastiansen F, Eliassen S, Ginot V, Giske J, Goss-Custard J, Grand T, Heinz SK, Huse G, Huth A, Jepsen JU, Jørgensen C, Mooij WM, Müller B, Pe'er G, Piou C, Railsback SF, Robbins AM, Robbins MM, Rossmanith E, Rüger N, Strand E, Souissi S, Stillman RA, Vabø R, Visser U, DeAngelis DL (2006) A standard protocol for describing individual-based and agent-based models. *Ecological Modelling* 198:115-126.
- Grimm, V., R. Ashauer, V. Forbes, U. Hommen, T. G. Preuss, A. Schmidt, P. J. van den Brink, J. Wogram, and P. Thorbek. 2009. CREAM: a European project on mechanistic effect models for ecological risk assessment of chemicals. *Environmental Science And Pollution Research* 16:614-617.
- Grimm V, Berger U, DeAngelis DL, Polhill G, Giske J, Railsback SF. 2010. The ODD protocol: a review and first update. *Ecological Modelling* 221: 2760-2768.

7708
7709 Grimm V, Railsback SF. 2012. Pattern-oriented modelling: a “multiscope” for predictive systems ecology.
7710 Philosophical Transactions Royal Society London B 367: 298-310.
7711
7712 Hogeweg, P., Hesper, B., 1983. The ontogeny of the interaction structure in bumble bee colonies: a
7713 MIRROR model. Behav. Ecol. Sociobiol. 12, 271–283.
7714
7715 Hommen, U.; Baveco, J.M.; Galic, N.G.; Van den Brink, P.J. 2010. [[HYPERLINK](http://edepot.wur.nl/144150)
7716 "http://edepot.wur.nl/144150" \t "_blank"] Integrated Environmental Assessment and
7717 Management: 325 - 337.
7718
7719 Kevan, Greco & Belaousoff (1997) Log-normality of biodiversity and abundance in diagnosis and
7720 measuring of ecosystem health: pesticide stress on pollinators in blueberry healths. J. Appl. Ecol. 34(5):
7721 1155-1136
7722
7723 Khoury DS, Myerscough MR, Barron AB (2011) A quantitative model of honey bee colony population
7724 dynamics. PLoS ONE 6(4): e18491. doi:10.1371/journal.pone.0018491
7725
7726 Leoncini I, Le Conte Y, Costagliola G, Plettner E, Toth AL, et al. (2004) Regulation of behavioral
7727 maturation by a primer pheromone produced by adult worker honey bees. Proceedings of the National
7728 Academy of Sciences of the United States of America 101: 17559–17564.
7729
7730 Martin, S. 1998. A population model for the ectoparasitic mite *Varroa jacobsoni* in honey bee (*Apis*
7731 *mellifera*) colonies. Ecological Modelling 109: 267-281.
7732
7733 Martin, S. J. 2001. The role of *Varroa* and viral pathogens in the collapse of honeybee colonies: a
7734 modelling approach. Journal of Applied Ecology 38:1082-1093.
7735
7736 Mitesser O, Weissel N, Strohm E, Poethke H-J (2006) The evolution of activity breaks in the nest cycle of
7737 annual eusocial bees: a model of delayed exponential growth. BMC Evol Biol 6:45. DOI 10.1186/1471-
7738 2148-6-45
7739
7740 Neumann, P. and Carreck, C. (2010) Honey bee colony losses: a global perspective. J. Apic. Res. 49, 1–6
7741 O’Neal, M.E., Landis, D.A., Rothwell, E., Kempel, L. & Reinhard, D. (2004) Tracking insects with
7742 harmonic radar: a case study. American Entomologist, 50, 212-218.
7743
7744 Omholt, S. W. 1986. A model for intracolony population dynamics of the honeybee in temperate zones.
7745 Journal of Agricultural Research 25: 9-21.
7746
7747 Omholt, S. W., Crailsheim, K. 1991. The possible prediction of the degree of infestation of honeybee
7748 colonies (*Apis mellifera*) by *Varroa jacobsoni* OUD: by means of its natural death-rate: a dynamic model
7749 approach. Norw. J. Agric. Sci. 5: 393-400.
7750
7751 Osborne, J. L., S. J. Clark, R. J. Morris, I. H. Williams, J.R. Riley, A. D. Smith, D. R. Reynolds, and A. S.
7752 Edwards.1999. A landscape-scale study of bumble bee foraging range and constancy, using harmonic radar.
7753 Journal of Applied Ecology 36:519–533.
7754
7755 Pretzsch H., P. Biber, and J. Dursky. 2002. The single tree-based stand simulator SILVA: construction,
7756 application and evaluation. Forest Ecology and Management, 162:3-21.
7757
7758 Railsback, S. F. and Harvey, B. C. 2002. Analysis of habitatselection rules using an individual-based
7759 model. Ecology 83: 1817–1830.
7760
7761 Railsback SF, Grimm V. 2012. Agent-based and Individual-based Modeling: A Practical Introduction.
7762 Princeton University Press, Princeton, N.J.

- Riley JR, Smith AD, Reynolds DR, Edwards AS, Osborne JL, et al. 1996. Tracking bees with harmonic radar. *Nature* 379:29–30
- Schmickl, T., and K. Crailsheim. 2007. HoPoMo: A model of honeybee intracolony population dynamics and resource management. *Ecological Modelling* 204:219-245.
- Schmolke V, Thorbek P, Chapman P, Grimm V. 2010a. Ecological modelling and pesticide risk assessment: a review of current modelling practice. *Environmental Toxicology and Chemistry* 29: 1006-1012.
- Schmolke, A., P. Thorbek, D. L. DeAngelis, and V. Grimm. 2010b. Ecological modelling supporting environmental decision making: a strategy for the future. *Trends in Ecology & Evolution* 25:479-486.
- Stillman, R. A. & Goss-Custard, J. D. 2010 Individual-based ecology of coastal birds. *Biol. Rev.* 85, 413–434.
- H. M. Thompson, S. Wilkins, A. H. Battersby, R. J. Waite, and D. Wilkinson. The effects of four insect growth-regulating (IGR) insecticides on honeybee (*Apis mellifera* L.) colony development, queen rearing and drone sperm production. *Ecotoxicology* 14(7):757-769, 2005.
- Thompson, H. M., S. Wilkins, A. H. Battersby, R. J. Waite, and D. Wilkinson. 2005. The effects of four insect growth-regulating (IGR) insecticides on honeybee (*Apis mellifera* L.) colony development, queen rearing and drone sperm production. *Ecotoxicology* 14:757-769.
- Thorbek P, Forbes V, Heimbach F, Hommen U, Thulke HH, van den Brink PJ, Wogram J, Grimm V (eds.). 2010. Ecological models for regulatory risk assessments of pesticides: developing a strategy for the future. Pensacola and Boca Raton (FL): Society of Environmental Toxicology and Chemistry (SETAC) and CRC Press.
- Thulke H-H, Grimm V. 2010. Ecological models supporting management of wildlife diseases. In: Thorbek P, Forbes V, Heimbach F, Hommen U, Thulke HH, van den Brink PJ, Wogram J, Grimm V (eds). Ecological models for regulatory risk assessments of pesticides: developing a strategy for the future. Pensacola and Boca Raton (FL): Society of Environmental Toxicology and Chemistry (SETAC) and CRC Press, pp. 67-76.
- Topping CJ, Dalkvist T, Forbes VE, Grimm V, Sibly RM. The potential for the use of agent-based models in ecotoxicology. 2009. In: Devillers, J. (ed.) *Ecotoxicology Modeling*, Springer, pp. 205-237.
- Ulbrich, K., and K. Seidelmann. 2000. Modeling population dynamics of solitary bees in relation to habitat quality. *Web Ecology* 2:57-64.
- Wang M, Grimm V (2007) Home range dynamics and population regulation: an individual-based model of the common shrew. *Ecological Modelling* 205: 397-409.
- Wang M, Grimm V. 2010. Population models in pesticide risk assessment: lessons for assessing population-level effects, recovery, and alternative exposure scenarios from modelling a small mammal. *Environmental Toxicology and Chemistry* 29: 1292-1300
- Wilensky, U. (1999) NetLogo. [[HYPERLINK "http://ccl.northwestern.edu/netlogo/"](http://ccl.northwestern.edu/netlogo/)]. Center for connected learning and computer-based modeling, Northwestern University, Evanston, IL.
- Wilkinson, D., and G. C. Smith (2002) A model of the mite parasite, *Varroa destructor*, on honeybees (*Apis mellifera*) to investigate parameters important to mite population growth. *Ecological Modelling* 148:263-275.

7818 Williams *et al.* (2010) Ecological and life history traits predict bee species responses to environmental
7819 disturbances. Biol. Cons. 143: 2280-2291
7820
7821

Formatted: Font: Italic, No underline, Font color: Auto

CHAPTER 12: DATA ANALYSIS ISSUES

Warren-Hicks, W.

This chapter discusses recommendations from the Workshop participants on existing methods and approaches for statistically assessing exposure and effects to pollinators using both laboratory and field tests. In a few cases, broad suggestions are discussed on how to examine, present, and evaluate data from these tests. Participants identified a need for additional statistical analysis tools for evaluating data from existing study designs and results to aid in the design and conduct of future study protocols. However, neither the discussions of the Workshop nor established guidance documents (*e.g.*, EU's Dir 91/414 and EPA Part 158 Test Guidelines) provide suggestions or case study illustrations detailing appropriate approaches for statistically examining data from both short- and long-term laboratory and field tests. An exploration of analytical methods most appropriate for evaluating data would serve to inform regulatory authorities, agrochemical registrants, and researchers engaged in such studies. The following provides a brief overview of the types of statistical issues relevant to evaluating the potential effects of pesticides on pollinators, that will be addressed by attendees of the Workshop through a subsequent effort, at a later date (note: details will be provided in a separate document through SETAC publications). The intent is to highlight issues of interest to risk assessors during the data analysis and risk characterization phases specifically with data generated on bees for use in an ecological risk assessment.

Study Duration

Decisions regarding study duration and dosing time will impact any statistical model applied to the data, including dose-response models, and can have a large impact on the statistical inferences drawn from the data. The duration of some of the proposed laboratory-based chronic studies is 10 days. However, the implications of both longer and shorter durations have not been tested either in terms of their ability to detect subacute/chronic effects or the relevancy of laboratory-based studies to field-based studies of longer duration.

7853

7854 *Replicates and Dosing*

7855 Questions around the number of bees per replicate, the number of replicates per dose, is
7856 an element in both laboratory and field studies that requires consideration. In laboratory-
7857 based studies, key issues include the clear definition of treatment units, estimation and
7858 interpretation of between-treatment variance, and temporal variation over the course of
7859 the test. In semi-field and field studies, the concept of a replicate and whether
7860 information from multiple hives on the same field can be considered true replication
7861 versus pseudoreplication is critical to the calculation of variation in these tests.

7862

7863 Dosing in laboratory-based studies is more standardized than in field studies. Dose levels
7864 in a laboratory-based studies are carefully selected to cover the range of possible effects
7865 to allow the estimation of a dose-response function. Whereas individual bees may be
7866 “dosed” in laboratory-based study, in field studies there can be uncertainty regarding the
7867 extent to which bees are actually exposed to test material. Examination of raw data from
7868 tests of such a design can result in a visual non-monotonic dose-response relationship.
7869 Methods for interpreting this information, and the implications for selection of dose
7870 levels, are of interest to the development of subsequently applied statistical models.

7871

7872 *Long-Term Tests*

7873 In chronic tests (10/14-day test, semi-field and field), the test is generally designed to be
7874 sensitive to sub-lethal effects, and consequently treatment levels and duration may be
7875 different from lethality tests. The length of the test and its influence on calculation of
7876 statistical endpoints and uncertainty in the model-based endpoints should be examined.
7877 However, high variability in measurement endpoints and low replication can confound
7878 efforts to detect statistically significant effects. Field studies have the advantage of
7879 extending for longer periods than other tests, but the length of these tests should be
7880 examined with respect to bee life stage and the extent of an effect that would be
7881 necessary to impair the colony as a whole. Consideration may need to be given to
7882 cumulative dosing effects in longer-term studies. In addition, how issues of temporal
7883 variation, temporal correlation, and trends are assessed for multiple endpoints are areas

which should be more standardized to ensure greater consistency and comparability between studies.

Statistical Models

Many methods are available for dealing with dose-response information. Selection of the model structure is important and mathematical approaches for treating study data and resulting curves are issues. Classic probit and logit models are typically chosen, but given biological and experimental variation, choice of model or experimental design can result in differing LC₅₀ and EC₅₀ estimates. Methods and approaches for dealing with differing results will be addressed in the anticipated analysis.

In brood tests, mortality is expressed as a percentage of the reference population after an adjustment according to the Abbott formula. However, other statistical methods and variance calculations are available, although no sensitivity studies on the test results have been conducted to date to determine the appropriateness of the models used to fit the data. Statistical methods for estimating the probability of survival at a specific age may be appropriate for these data, depending on the experimental design established for the test. In semi-field and field tests, which are typically hypothesis-based as opposed to regression-based study designs, questions include whether there are appropriate time-series models for testing for long-term trends in multiple endpoints, and how non-linear or episodic time-series data are treated. Use of specific statistical models may be more appropriate to evaluate long-term survival and hazard. Examination of survival functions for semi-field tests is an area of future research.

Through the review of several existing data sets, additional areas of analysis may be addressed, including treatment of controls or baseline effects. The anticipated work will examine approaches and interpretation of uncertainty in examining endpoints and output from tests. In addition to examining variability, an evaluation of uncertainty will include examples and case studies for interpreting results in light of the uncertainty estimates.

CHAPTER 13 RISK MITIGATION AND PERFORMANCE CRITERIA

Johansen, E., Fry, M., and, Moriarty, T.

The Role of Risk Management in Pollinator Protection

The risk assessment paradigm discussed at the SETAC Pellston Workshop articulates a process to measure the effects of a compound against the protection goals of a regulatory authority. When sufficient data are available to reasonably predict that the intended use of a plant protection product is inconsistent with protection goals of a regulatory authority, and the use of that product remains beneficial and desirable to stakeholders, then risk managers may seek to either continue to refine the estimate of risk, through higher tier testing/analyses (if this remains an option), or to bring the estimated risks into line with the protection goals through specific mitigation measures affecting the proposed use of that compound. Regulatory agencies rely upon mitigation to balance environmental protection goals with other (stakeholder) demands and incorporate mitigation into their management decisions. Consequently, the role of mitigation is central to the process for pesticide regulation. With the exception of few scenarios²⁷, most mitigation includes reducing potential exposure. The regulatory agency may mitigate the potential risk by denying use on a particular crop or use site. However, in most cases, mitigation actions are those which modify the manner in which a product is used.

Stakeholders in the process of risk management include regulatory agencies (national and local), chemical producers, distributors, field advisors, and practitioners (including growers and applicators). At the national level, regulatory authorities are charged with registering pesticide products in a manner consistent with their statutory responsibilities.

²⁷ Certain inert ingredients have been shown to [indirectly] increase the potency of a compound; in addition, specific environmental conditions may also modify the behavior, and therefore the potency of a compound.

At the local level, *e.g.*, state governments in the US, have their own pesticide registration process, which is equally or more protective than the national level. In other scenarios, in France for example, specific restrictions can be implemented based on specific cropping or pedo-climatic conditions that may be associated with increased potential risk. At the field level, (additional) mitigation actions can be developed, promoted and implemented by industry experts, crop specialists, beekeepers, growers and/or pesticide applicators that extend beyond what is legally required by the regulatory authorities (such as through different management programs).

Mitigation language should be specified in a way that allows for consistent (spatial and temporal) implementation. If mitigation language fails to be clear enough for proper, consistent implementation, then inconsistent protection scenarios may result, and the relationship between the regulatory decision and the protection goals may be lost. Clarity and consistent interpretation are also important because the use of a pesticide product inconsistent with the label directions is in many countries considered a violation of the law that may carry with it prosecutorial action. Insofar that the adjudication of the label violation involves investigation by a third party (usually a local regulatory authority such as in the US) and arbitration by a civil official, the clarity of the intended use and restrictions associated with a product label is necessary in order to establish misuse. Misuse of a pesticide can also result in severe adverse effects on either human health or the environment.

Regulatory authorities directly or indirectly rely upon feedback information to understand whether assessments and decisions actually support stated protection goals. Feedback information may come in different forms, such as research studies, reports of bee poisoning incidents, or targeted monitoring programs. Feedback information can provide insight into how a product is actually used, unforeseen variables that affect the use of a compound, unforeseen effects of a mitigation action, and/or simply whether the mitigation measures are sufficient to ensure the protection goal(s). Targeted programs (*i.e.*, investigation designs that time information collection with the actual use of the products) can be expensive but provide high quality data. Investigations such as eco-

epidemiological analyses such as those described by Susser (2004)²⁸ may not be as valuable as targeted monitoring programs, but can provide information on one or several co-variables. Information gained through bee poisoning incident reports may lack some information (such as timing of application, application rate, or analytical analysis) that may be useful in establishing that a particular chemical use resulted in an incident, but may provide information on a specific type of product or use scenario that may be anecdotally linked to an incident. In addition, because incident reports frequently rely upon volunteer reporting, it is difficult to know the degree to which incident reports reflect real world conditions. Therefore, a lack of incident reports may or may not be indicative that the intended (directed) use of a product is safe. Conversely, the lack of incident may not represent the extent of events related to a product, *i.e.*, the absence of incident reports cannot be reasonably construed as the absence of incidents. Conversely, the presence of limited incidents may not necessarily indicate whether a risk exists with a product. However, a pattern of incidents related to a specific compound, application method, or crop for example, may be a clear indication of a risk issue. Nonetheless, information from these feedback sources provides multiple lines of evidence that can be used to inform and modify existing or future assessment or management decisions.

Additional discussion may be found in a recent European “OPERA” review (Alix *et. al.*, 2011).

Formatted: Font: Italic, No underline, Font color: Auto

It is worth noting that when honey bee workers are killed in the field, the loss of these workers may, to a certain extent, be compensated by the growth of the colony, which may continue to grow and reproduce with little or no impact from the kill(s). Because most non-*Apis* bees are solitary species, where single females build their nests, lay eggs, and forage for pollen and nectar to feed their offspring, the death of a foraging female or even the incapacity to provision her cells results in the cessation of her reproduction (Taséi 2002). Below is a brief discussion of considerations with respect to pesticide risk mitigation for *Apis* and non-*Apis* bees.

²⁸ [REDACTED]

Regulatory Risk Mitigation Methods

The risk assessment should provide a clear description of the risk (*i.e.*, the likelihood and magnitude of an adverse effect) that needs to be mitigated. Knowledge of the chemical physical properties, environmental fate and ecological effects of a compound are integrated with an understanding of the use of a compound to provide the information necessary to develop potential mitigation options. Specific characteristics of the risk(s) to be mitigated may include the following.

- Whether the risk is related to acute effects on adult bees, chronic effects on adult bees, adverse effects on larval development, or other effects (such as interactive effects of tank-mixes containing insecticides and fungicides).
- Whether the risk is related to honey bees, other species of bees, or both.
- Whether the risk is related to a particular crop or site being treated, to off-target movement of the pesticide to adjacent crops or blooming weeds where bees may be foraging on nectar and/or pollen, or to other concerns (such as contamination of nesting materials used by non-*Apis* bees).
- Whether the risk is related to a particular application mode (systemic or topical) or method (such as spray, or irrigation)
- Whether or how long the pesticide exhibits hazard to bees following application (referred to as extended residual toxicity (RT) in the US).

- a) Crops Requiring Pollination by Bees: Central to managing risk of pesticides to bees is controlling potential exposure at the time, or under conditions when bees are [likely to be] present in an agricultural setting. One of the most critical issues for risk mitigation is when bees are present at a site for pollination of the crop (Riedl *et al.*, 2006), which may also include bees foraging on understory bloom or in an adjacent or border area. For crops that require pollination by bees, the primary consideration should be to protect bees from pesticide residues that represent a hazard potential. While every attempt should be made to avoid applications of insecticides and fungicides during the pollination period, use of a plant protection product may be needed (or designed for use) when the crop may

be most attractive to bees. When developing risk mitigation statements, there are several mitigation options that could be considered:

- Product Formulation: Typically there may be several formulations that could be used to treat a crop/pest combination. To the extent possible, formulations should be those that pose the least threat to bees. Formulations that approximate pollen grains (*e.g.*, some microencapsulated products) in terms of particle size can lead to greater exposure as bees may accumulate the product through their normal foraging activity. However, addition of a sticking agent to a foliar application can potentially reduce transfer from the plant to the bee. Granular formulations are typically considered the least hazardous to bees. Seed treatments also provide limited exposure (similar to granular formulations) provided that dust emission (from abrasion during planting) emission is properly managed. However, dust particles from seed treatments were responsible for a large number of bee poisoning incidents in Germany during 2008 (Pistorius *et al.* 2009). Soluble and emulsifiable (liquid) formulations are usually safer to bees than wettable powders. Dust and micro-encapsulated formulations may be more hazardous to bees than other formulations, (or routes). For more information on the relative hazard of different formulations, see Johansen and Mayer (1990).
- Method of Application: The application method may also be examined to reduce potential environmental exposure. Generally, ground applications result in less off-target drift to both adjacent areas and the understory than aerial applications. Soil incorporated application methods provide limited environmental exposure (via drift); however, since the compound is available to all the growth material, this method may lead to pesticide residues to be expressed in understory bloom. With respect to aerial application, droplet size can have a marked effect on the extent of drift; in general, larger droplets are less likely to drift compared to finer droplets.

- Application Parameters: Limiting the use rate and frequency of application to the minimum required to effectively control the pest or disease organism. Increased application intervals or reduced application rates may lower potential exposure. Application intervals may be related to residue levels in the field that may represent a potential route of exposure (via uptake by the plant or by contact). Products that have demonstrated synergism may be identified or prohibited by a product label.
 - Understory and Adjacent Areas: Understory can be a source of either foliar (*e.g.*, from aerial drift) or systemic (when pesticide residues in the soil are taken up by understory flora) exposure to pesticides applied on field. Note that the understory may represent an attractive source of nutrition for the bees separate from, or in addition to, the cultivated crop. Potential methods of controlling weed bloom include mowing, disking, flailing, or through use of an herbicide. However, it is important to note by eliminating understory forage (as a source of exposure) also forfeits this material as a source of forage or habitat for both pollinators and arthropod fauna. And consequently not considered a sustainable mitigation measure in some European countries.
 - Equally important is control of off-site movement of a pesticide. Bufferzones between application and adjacent areas, particularly if they are attractive to pollinators will reduce potential exposure. Use of low drift spray nozzles, not allow application when wind conditions favor drift onto adjacent crops or weeds that are attractive to bees
- Windbreaks may also be employed to reduce drift. Avoid seed dust at sowing (low wind conditions, equip drillers with dust reducing devices).

- Timing of Application and Environmental Conditions: Applications may be restricted to times when bee activity is expected to be at a minimum. Honey bees do not forage at night (in temperate regions), and do not begin actively foraging until the temperature reaches at least 55°F (12.8°C). In addition, some flowers close at night, consequently, spray is less likely to land on this portion of the plant, further reducing potential exposure to the bee the following day when foraging begins. This risk mitigation technique is only effective if the pesticide has an intermediate residual hazard to bees of 8 hours or less (evening applications only), has a short residual hazard of less than 4 hours (evening or morning applications), or if flowers are closed during applications.
- It should be noted though, that other bee species have slightly different activity times, and high temperatures encourage bees to forage earlier in the day or continue to forage later into the evening than usual. Late evening applications are generally less hazardous to bees than early morning applications; environmental conditions such as temperature and dew point may affect the dissipation of a compound (*e.g.*, slow down), thereby extending a compounds residual toxicity. This mitigation option is likely to be of very limited benefit in tropical regions, since the non-foraging period for honey bees in the tropics is very short when compared with temperate regions. For more information on application timing and environmental conditions, see Johansen and Mayer (1990).
- Tank-Mixes: Tank-mixing may represent an economical option in pest control. However, care should be taken to understand if there are unforeseen effects to non-target organisms from mixing different compounds in a single application. Tank-mixing certain types of compounds may result in interactive effects that can enhance to toxicity of the mixture to bees. (France has recently prohibited tank mixes of triazole fungicides and pyrethroids (JORF, 2010).)
- Notification: Growers may notify beekeepers of anticipated pest control needs. This allows the parties involved to discuss variables and options to reduce

potential exposure to bees. While beekeepers may try to protect their stock from an application by covering colonies, doing so for an extended period of time may be damaging to the colonies, particularly in warm weather. Further, it may be difficult to move managed bees “on demand” since the configuration of the colonies, number of colonies, and the bee activity level effect how quickly stock can be relocated (or protected). (Also, while moving or protecting may be an option for managed bees, it will not protect non-managed bees.)

- b) Crops Not Requiring Pollination by Bees: Pesticide applications to blooming crops, crops with extra-floral nectaries, and pollen shedding crops not requiring pollination that are attractive to bees have also been documented as an important cause of bee poisoning (Riedl *et al.* 2006). The mitigation options listed above should be considered, but the mitigation statements may need to be modified to address the specific circumstances involved with crops that do not require pollination.

Non-Regulatory Risk Mitigation Methods

Where limitations exist with regard to the level of risk management that can be reliably and effectively implemented through a national-scale label (regulatory method), implementation of risk management may be possible at the *landscape*, or field level through best management practices (BMPs) employed by the user (non-regulatory). Alternative or additional methods to mitigate risk to pollinating bees may be used in conjunction with measures identified through the product registration and captured on the product label. Beekeepers, growers, and applicators together with IPM agents, agricultural extension agents, crop advisors and pesticide product representatives can exercise field-level knowledge (*i.e.*, practical experience) to achieve maximum protection for both the grower and the beekeeper. Measures that go beyond the product label reflect local knowledge, and relationships which foster cooperation that are often the most effective way to manage potential risks.

8155

8156 Among regulatory and non-regulatory methods to mitigate potential risks,
8157 communication and cooperation between growers, applicators, and beekeepers is perhaps
8158 the most important tool to reduce risk, and ensure that the needs of all of the stakeholders
8159 are met. Growers and beekeepers engage in reciprocal, mutually beneficial endeavors and
8160 it is to the advantage of each to anticipate/respect the concerns/needs of the other.
8161 Growers can learn the pollination requirements of the crops they grow and plan pest
8162 control operations with pollination needs in mind. Growers and advisors can proactively
8163 manage routine insect pests by developing and monitoring for economic thresholds to
8164 initiate appropriate treatment early to reduce pest population and prevent, avoid or lessen
8165 loss without having to rely on higher application rates/intervals that may represent a risk
8166 to bees. Such a program is often less hazardous to pollinators and other beneficial insects
8167 as well. Applicators can use their knowledge of local weather patterns to time
8168 applications in a way that responds to pest pressure and accounts for bee activity, and/or
8169 chemical physical properties of the pesticide product. Through communication with
8170 growers and applicators, beekeepers should be familiar with pest control problems and
8171 programs, in order to develop mutually beneficial agreements that better ensure the
8172 prudent use of insecticides and fungicides. Beekeepers, growers, crop advisors and
8173 applicators should be aware of the toxicity of product(s) being used, and any residual
8174 toxicity characteristics. As discussed previously, depending on the size and location of
8175 apiaries and weather conditions, some beekeepers can protect honey bee colonies by
8176 covering them with wet burlap the night before a crop is treated with an insecticide that
8177 has an extended residual hazard. These covers are typically maintained wet and in place
8178 for enough time to provide protection from initial hazards. Honey bee colonies should be
8179 clearly marked with identification as this facilitates communication.

8180

8181 Apiaries can be situated to isolate them from intensive pesticide application area and to
8182 protect them from insecticide and fungicide drift. Establish holding yards for honey bee
8183 colonies at least four miles from blooming crops being treated with insecticides that are
8184 highly toxic to bees.

Ridge tops are preferable to canyon bottoms, as insecticide fines drift down into the canyons and flow with morning wind currents.

Suggested Techniques to Mitigate Risks to Other Species of Bees

Nesting and Moving Bees

While shelters for certain species, such as alfalfa leafcutting and bumble bees can be built to be covered, closed or removed during insecticide applications to reduce the threat of insecticide drift, most non-*Apis* bees, especially soil-nesting species, cannot be relocated as a protection measure. Many non-*Apis* bees will nest in the ground in orchards and even within row crops (Kim *et al.* 2006). Squash bees (genus *Peponapis*), for example, frequently nest underground at the base of squash and pumpkin plants within production fields (Shuler *et al.* 2005), as do *Melissodes* bees in cotton fields (Vaissière *et al.* 1985). Therefore, recommendations made to protect honey bees by closing up or moving hive boxes are of little value for economically important wild bees living in and around crop fields and orchards. Similarly, some alfalfa seed producers in western U.S. states rely on artificially constructed salt flats to aggregate large numbers of ground-nesting alkali bees (*Nomia melanderi*) for pollination (Cane 2008). The large size of such nesting areas, the long distance these bees can fly (up to 3.2 km [2 miles]), and their potential location away from seed production fields makes it impossible to close off nest entrances to prevent them from foraging in recently sprayed fields.

Blooms of any type, including weedy species that may be available in adjacent areas on in fence rows, may serve as nesting sites or as a nutritional source for native pollinators (as it is for managed pollinators as well). To the extent that growers can leave such plants undisturbed and manage pesticide drift, they contribute to the conservation of these native pollinators and the diversity of the farm ecosystem. Approximately 70% of native bees are ground nesters, burrowing into areas of well-drained, bare or partially vegetated

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

soil. Growers and beekeepers can provide resources for nesting sites for many non-*Apis* species. More information on improving habitat for non-*Apis* pollinators may be found in Vaughn *et al.* (2007) and Vaughn and Skinner (2008).

Formatted: Font: Italic, No underline, Font color: Auto

Timing of Application

Mitigation of potential exposure through restricting applications to the evening or during periods of cool temperatures was discussed earlier, based upon the premise that honey bees usually do not forage when temperatures are below 13°C (55°F) or between late evening and early morning (Johansen and Mayer 1990), thus giving pesticides with a short residual hazard more time to become inactive or less biologically available. For example, alfalfa leafcutting bees (*Megachile rotundata*) are nearly inactive at 70°F (21.1°C) and completely inactive at 60°F (15.6°C). Both managed alfalfa leafcutting and bumble bees (*Bombus* spp.) can be safeguarded from potential exposures by removing nests prior to pesticide applications. However, this does not reflect the cooler weather tolerance of some temperate species of non-*Apis* bees, such as *Bombus* spp. and *Osmia* spp., both of which are frequently noted for their ability to forage during cool, inclement weather, as well as earlier and later in the day (Thompson and Hunt 1999, Bosch and Kemp 2001). Furthermore, the peak foraging times for bumble bees are very early and late in the day, whereas peak honey bee foraging typically occurs at different periods. Similarly, squash bees (genus *Peponapis*) have been documented to perform a significant amount of pollination in the pre-dawn hours when honey bees are inactive (Sampson *et al.* 2007). Hence, application of pesticides during the evening, while still preferable, may in fact disproportionately affect certain non-*Apis* species (Thompson 2001). In some instances, spraying crops that are soon to bloom (*e.g.*, those at budburst) may have a disproportionately higher impact on male solitary bees that emerge before the females and often spend the night in flowers or attached to bud stems.

Formatted: Font: Italic, No underline, Font color: Auto

Formatted: Font: Italic, No underline, Font color: Auto

Pesticide Application Technologies to Mitigate Exposure to Bees

For compounds that are acutely toxic to bees by contact exposure and a screening-level risk assessment indicates a potential risk to bees via contact exposure, data from a higher-

tier test, such as U.S. EPA's Tier 2 study to evaluate the toxicity of a pesticide on foliage (e.g., alfalfa) should be used to determine when products should not be applied (e.g., Do not apply when bees are actively foraging). To minimize exposure of bees to pesticides, it is important to be aware of weather conditions, particularly wind speed and direction, and avoid applying during those times. Applications at dusk or late evening or early morning prior to dawn when the majority of honey bees are not actively foraging could help minimize contact exposure, depending on the residual time and bioavailability of the pesticide.

Mitigation for exposure to seed treatment dust

In order to minimize the emission of abraded seed treatment dust during sowing, particularly when seeds dressed with insecticides that are toxic to bees, the following parameters are considered to be particularly relevant:

Seed coating quality

Prior to seed treatment, seeds need to be properly cleaned to remove extraneous debris. Thereafter care should be taken to minimize loose dust in the seed bag. The use of optimized seed treatment recipes is a key parameter to guarantee a high abrasion resistance of the treated seed, while for some treated seeds (e.g., corn), the use of appropriate stickers and film-coatings will further enhance the resistance of treated seeds to abrasion.

Seeding technology

When seeds are sown using vacuum pneumatic sowing equipment, the use of deflectors, which direct dust downward into the field being planted, has been demonstrated to reduce off-site dust emission. However, even with deflectors, caution should be taken when using this type of sowing equipment in no-till fields, if blooming weeds are present in the field. In this scenario, dust could be deflected directly onto the flowering weeds. Mechanically operated sowing equipment, as well as those using compressed air, are less prone to emit dust into the environment.

8277

8278 **Soil applied uses**

8279 Crops that are not in bloom often harbor blooming weeds or have blooming cover crops.
8280 These blooming plants may represent a potential source of pesticide exposure for both
8281 honey bees and non-*Apis* bees if the plants are exposed to soil-applied systemic
8282 pesticides. Chemigation systems should be maintained in proper working order to ensure
8283 pesticides will not spray, leak or run-off into areas where potential contamination of
8284 blooming plants or water sources for bees could occur. Care should also be taken when
8285 making granular applications for the same reasons. These potential routes of exposure
8286 are probably best addressed through product stewardship, that requires applicator
8287 education and post registration monitoring.

8288

8289 **IPM / crop rotation**

8290

8291 IPM techniques can contribute to the natural reduction of pests by simply employing
8292 techniques that reduce the reliance on the broad application of pesticides. When IPM
8293 techniques are used, populations of pests can be more easily maintained below
8294 detrimental thresholds, thus reducing the need for pesticide treatments, and thus reducing
8295 potential exposures to bees.

8296

8297 **Landscape management**

8298 Preserved habitats, refuges, food resource, and the like may reduce the dependence of
8299 non-target species on commercially cropped areas (Vaughn *et al.*, 2007). Variables such
8300 as the nature of the refuge, the proportion or density, location and management of such
8301 areas contribute to the effectiveness of the protected area. Initiatives have been
8302 undertaken that illustrate the effect of the implementation of flowering strips on
8303 pollinating species (*e.g.*, Operation Pollinator developed by Syngenta, [HYPERLINK
8304 "http://www.operationpollinator.com"]) which could provide a useful basis for further
8305 recommendations in the future. Further work is needed to actually quantify the benefit

in terms of exposure (drift reduction) and impact of the implementation of habitat for non-*Apis* pollinator species. Eventually landscape-level modeling may be used in support of the design of the landscape elements that may be recommended as mitigation measures.

References

- A. Alix, L. Adams, M. Brown, P. Campbell, E. Capri, A. Kafka, K. Kasiotis, K. Machera, C. Maus, M. Miles, P. Moraru, L. Navarro, J. Pistorius, H. Thompson & A. Marchis. Bee health in Europe: facts and figures. [HYPERLINK "http://www.opera-indicators.eu/eng/info/Documents-on-CAP/Farming-Bee-good-Bee-health.html"]
- Johansen, C.A. and D.F. Mayer. Pollinator Protection – A Bee & Pesticide Handbook. Wicwas Press, 1990.
- Pistorius, J., Bischoff, G., Heimbach, U., and M. Stähler. Bee poisoning incidents in Germany in spring 2008 caused by abrasion of active substance from treated seeds during sowing of maize. Hazards of pesticides to bees – 10th International Symposium of the ICP-Bee Protection Group. Julius-Kühn-Archiv 423 (118-126), 2009.
- Riedl, H., E. Johansen, L. Brewer, and J. Barbour. How to Reduce Bee Poisoning from Pesticides, PNW 591. Oregon State University, 2006.
- Sasser, E. 2004. Eco-Epidemiology: Thinking Outside the Black Box. Epidemiology 15(5): 519 – 520. doi: 10.1097/01.ede.0000013591.42782.b4 [HYPERLINK "http://journals.lww.com/epidem/Fulltext/2004/09000/Eco_Epidemiology__Thinking_Outside_the_Black_Box.4.aspx"]
- Thompson, H.M. and D. Thorbahn. Review of honeybee pesticide poisoning incidents in Europe – evaluation of the hazard quotient approach for risk assessment. Hazards of pesticides to bees – 10th International Symposium of the ICP-Bee Protection Group. Julius-Kühn-Archiv 423 (103-108), 2009.
- Vaughn, M., M. Shepherd, C. Kremen, and S.H. Black. Farming for Bees: Guidelines for Providing Native Bee Habitat on Farms. The Xerces Society, 2007.
- Vaughn, M. and M. Skinner. Using Farm Bill Programs for Pollinator Conservation, Technical Note No. 78. United

[PAGE * MERGEFORMAT]

8349

8350


Chapter 14 Recommendations for Future Research in Pesticide Risk Assessment for Pollinators

From the ~~discussions in the preceding chapters~~ discussion above, the following recommendations are proposed which aim at further improving the risk assessment scheme that could be developed in these proceedings.

Exposure

Consumption of guttation water as a source of exposure: Various investigations of residues in guttation droplets collected from seed-treated crop plants revealed the potential for high residue levels to be present in guttation droplets (Girolami *et al.*, 2009; Joachimsmeier *et al.*, 2010; Pistorius and Joachimsmeier, 2010; Schenke *et al.*, 2010). Highest residues in guttation water occur immediately after seedling emergence and have been shown to decline with time. Current data suggests that monocotyledons tend to show guttation on a more frequent basis than dicotyledons. Some plants such as sugar beets produce practically negligible guttation. If bee hives are located in the immediate proximity to treated crops (field margin), some individual honey bees have been observed collecting guttation droplets. (Girolami *et. al*, 2009) If highly toxic systemic seed treatments or soil applications have been used, some individual forager bees could be potentially exposed to lethal levels of residues in guttation water. However, in currently available colony-level studies, neither adverse effects on colonies, nor impact on beekeeping practices have been associated with pesticides in guttation water. Further studies are currently under evaluation, and more research is required to clarify if exposure of systemic pesticides through guttation water needs to be included in the pesticide risk assessment process.

8380
8381
8382
8383



8384
8385
8386
8387
8388
8389

Guttation water on a strawberry leaf. Photograph by Mace Vaughan, Xerces Society for Invertebrate Conservation, all rights reserved, used by SETAC with permission.

Formatted: No underline, Font color: Auto

Formatted: Font: 9 pt, No underline, Font color: Auto

Formatted: Font: 9 pt, Italic, No underline, Font color: Auto

Formatted: Font: 9 pt, No underline, Font color: Auto

Formatted: Font: 9 pt, No underline, Font color: Auto

Formatted: Font: 9 pt

8390
8391
8392
8393
8394
8395
8396
8397
8398
8399
8400
8401
8402

Quantify in-hive exposure to larval, queens, and other hive members for use in screening assessments: Data on actual exposure of larvae or other hive members could be established by chemical analysis of larval jelly, royal jelly, and beebread following a field application (such as in a semi-field or field scenario). Spraying a surrogate crop (*e.g.*, *Phacelia* or buckwheat), enclosed in a tunnel containing a hive with minimal pollen and nectar stores would provide an optimal test system to measure in-hive exposure. Larval jelly and bee bread could be sampled from larval cells and analyzed for the appropriate pesticide residues. Data from a series of such tests that capture a range of mode of actions, application methods could be averaged to provide a generalized value to represent in-hive “pesticide” exposure (*e.g.*, in larval food) for use in screening level analyses. Analysis could include both foliarly applied and systemic compounds. For systemic compounds, representative crops could be selected and treated using different delivery routes. Residues in leaves, pollen and nectar could be sampled over time, and

Formatted: Font: Italic, No underline, Font color: Auto

particularly during flowering to determine uptake and decline rates of the pesticide. These data could help refine the default exposure calculation for systemic compounds and would also be helpful in determining the number of samples (e.g., beebread, larval jelly) that should be analyzed to obtain a robust and repeatable measurement of residue levels, and would also provide information to compare residue levels in pollen to that in other in-hive products, such as beebread.

Effects

Role of inerts and co-formulants: Although pesticide effects testing typically focuses on the technical grade active ingredient in a relatively pure form (e.g., greater than 95% pure), these compounds are often applied as formulations that contain other products (e.g., adjuvants and/or surfactants). The potential effects of the formulated products may differ from the active ingredient. Also, given that the constituent elements of formulated products have different chemical/physical properties whereby they dissipate at different rates than the active, methods for studying these products in an environmentally realistic way can be challenging. Since there can be many formulated products associated with an active, methods are needed for determining which if any formulation should be tested.

Formatted: Font: Not Bold, Italic, No underline, Font color: Auto

Formatted: Font: Not Bold, No underline, Font color: Auto

Formatted: Font: Not Bold, Italic, No underline, Font color: Auto

Formatted: Font: Not Bold, No underline, Font color: Auto

Formatted: Font: Not Bold, Italic, No underline, Font color: Auto

Formatted: Font: Not Bold, No underline, Font color: Auto

Formatted: Font: Not Bold, Italic

*Comparisons between *Apis* and non-*Apis* species:* An obvious knowledge gap identified by the participants of the Workshop is data to compare effects between *Apis* and non-*Apis* species. This includes effects in laboratory-based studies and semi-field and full-field studies (exploring both differences in sensitivity and susceptibility). One way to address this uncertainty is to include non-*Apis* bees in semi-field and field studies.

Reliable test for sub-lethal effects: There is a real need for reliable (field-level) tests for sub-lethal effects and a means to translate these effects into meaningful measures at the hive level, i.e., to establish quantitative linkages between sub-lethal measurement endpoints on individual bees and more traditional colony-level assessment endpoints. Sub-lethal effects are most often made at the individual level but even when effects are noted it is difficult to extrapolate these effects to the whole colony. Research is needed to

develop reliable test measurements to consistently document sub-lethal effects on bee behavior. Equally important is a means to translate these effects at the individual level to effects at the colony level. Suggestions for sub-lethal tests include: a standard test for foraging disorientation that might include a “time back to the hive” or a maze at the hive entrance.

Determining the degree of adult or brood loss that affects colony productivity and survival: Losses of adult bees in dead bee traps and brood are often noted but the impact of these losses is hard to determine, especially if the losses are transitory. A series of experiments are needed to determine the rate of adult and brood loss necessary to impact colony productivity and pollination and ultimately colony survival. *Apis* colonies have a reserve of worker bees that serve to buffer the effects of temporary losses. However, there remains a fundamental uncertainty regarding the point at which the hive buffer becomes exhausted, and the colony is impaired.

Extrapolating from semi-field or field scale to protection goals: Currently, if any significant effects are observed or measured in semi-field or field studies, then it is predicted that protection goals will unlikely to be met. This is due to inability to confidently extrapolate from effects seen in a semi-field or field study to what may, or may not occur under field conditions. It would be extremely valuable if research could be carried out to link measurement endpoints, derived from a semi-field or field study, with protection goals. This may include not only well designed testing, but well designed post-monitoring as well.

There is a need for cost-effective reporting schemes that provide incentives to all parties involved, *e.g.*, beekeepers, applicators, and growers, to help increase accurate representation of use and effects of pesticide use in the field. This information would be an important input to the pesticide regulatory framework (*i.e.*, risk assessment and risk management). Furthermore, a common platform for incident reporting between regulatory authorities would facilitate the sharing of incident data and management strategies.

Modeling has been identified as a promising tool for the purpose of risk assessment and risk management. Further research and work on model development for use in pesticide risk assessment for pollinators would help to document and refine modeled biological realism, sensitivity, robustness, parameterization and calibration. Models could be used to explore potential linkages between measurement endpoints and assessment endpoints or protection goals. Models could also be used in support of extrapolation in time and space of the outcome of a risk assessment based on laboratory studies. Models could also be developed as a support in the design of higher tier studies and landscape management. Collaboration between modelers and others such as regulators or entomologists would help direct model development and refinement.

The role that landscape management and alternative foraging and habitat resources may play in limiting the impact of pesticides and agronomic practices on pollinators calls for further research in this area. Typically monitoring studies undertaken in agronomic systems proposing diverse options for landscape management would provide feedback and support appropriate recommendations. Such approaches include population ecology, landscape ecology and exposure characterization. It is noteworthy that the data generated may also feed model development and could thus be generated with the advice of modelers.

Efficacy of Mitigation Techniques. Research is needed to inform whether different risk mitigation techniques are efficacious in reducing the frequency or severity of bee poisoning incidents. For example, research could be carried out that investigates drift reduction technologies or the impact of vegetated buffers in mitigating spray drift or their effectiveness as a refuge and habitat for pollinators.

Data on Interactive Effects (e.g., synergism): More research is needed to to inform the understanding of interactive effects between crop protection products, particularly between insecticides and fungicides. Evidence of interactions have been observed under laboratory conditions, however the extent of these interactions in the field remains poorly described. Information on this, including research involving residues occurring in hives

is needed to improve our understanding of whether label directions should be revised to restrict or prohibit tank-mixtures of certain pesticides/adjuvants/surfactants that are applied in conjunction with the pesticide and may be available as an exposure source to bees, ~~and to flowering crops, such as in France for example JORF, 2010.~~

Formatted: Strikethrough

Of critical importance is information on the interaction between in-hive mite control chemicals (acaricides), applied by beekeepers for control of varroa mites, and insecticides or fungicides applied to pollinated crops. Understanding linkages or relationships between these exposure mixtures and honey bee diseases is very important. Research in this area, in addition to that conducted by the US Department of Agriculture would improve the understanding of whether label use directions for in-hive acaricide applications and/or pesticide applications to flowering crops should be revised.

References

Formatted: Font: Bold, No underline, Font color: Auto

Formatted: Font: Bold

Girolami VM, Grooti M, Di Bernardo A, Tapparo A, Giorio C, Squartini A, Mazzon L, Mazaro M, Mori N. 2009. Translocation of neonicotinoid insecticides from coated seeds to seedling guttation drops: a novel way of intoxication for bees. Journal of Economic Entomology. 102(5): 1808-1815.

Joachimsthaler L, Heinbach U, Schenke D, Pistorius J. 2010. Residues of different systemic neonicotinoids in guttation droplets of oil seed rape in a field study. Julius Kühn-Archiv. 428: 468-469.

Schenke D, Joachimsthaler L, Pistorius J, Heinbach U. 2010. Pesticides in guttation droplets following seed treatment – Preliminary results from greenhouse experiments. Presented at the 20th Annual Meeting of SETAC Europe, Seville (abstract book ET05P-TU155, p. 259).

[PAGE * MERGEFORMAT]

8523

8524 **APPENDIX**

8525

APPENDIX 1 ELEMENTS FOR A CHRONIC ADULT ORAL TOXICITY STUDY

Below are elements of a chronic oral toxicity test proposed by Workshop participants:

- The lifespan of adult honey bees isolated from their colony in laboratory test cages is generally only 2-3 weeks. Control mortality is likely to be unacceptably high before the test ends if you begin with older bees.
- Cages should be well ventilated and sufficiently large to allow the bees to move around freely.
- Minimally, three replicates per dose and 10 bees per cage should be used; however, it is important to note that statistical power is based on the number of replicates (treatment units or cages) and not the number of bees within the treatment unit.
- There should be a minimum of 5 dose rates (treatment levels) to achieve a dose-response curve for the test item and to allow generation of the lethal concentration to 50% of the bees tested, *i.e.*, LC₅₀, a no-observed-effect-concentration (NOEC), and sufficient doses to verify the LC₅₀ of a toxic reference chemical (*e.g.*, dimethoate is used as a reference toxin in other toxicity tests).
- The test substance should be dissolved in the aqueous sucrose solution (using a maximum of 1% solvent (*e.g.*, acetone) if required).
- If a solvent is required to dissolve the test substance, then a suitable solvent control should be run in addition to a negative control concurrent with the treatments. Therefore, both an untreated sucrose (50% w/v) control and, if a solvent has been used to suspend the test item in sucrose, a sucrose-solvent control containing the same maximum concentration of solvent as the test item should be used.
- A protein supplement may be used in the 50% w/v sucrose if this ensures control mortality is acceptable at 10 days.
- As a chronic toxicity test, concentrations/levels should be selected to minimize mortality and facilitate measurement of sublethal effects. A median effect

concentration (EC₅₀) based on sublethal effects (*e.g.*, impaired behaviour, growth) should be a primary focus of the study.

- Two dosing methods should be considered:
 1. The volume of treated sucrose should be sufficient to allow *ad libitum* feeding for a 24 hr period (continuous dosing).
 2. A small volume of treated sucrose (*e.g.*, 20µL/bee) should be offered for 2-4 hours each day and then replaced with untreated sucrose (daily dosing). It may be necessary however, to starve (fast) the bees before providing the treated sucrose solution to ensure that the dosed test solution will be completely consumed by the test organisms).
- The amount of treated sucrose offered to the bees and the amount remaining each day should be recorded. The dose consumed should be determined by comparing the weight of the dose remaining in the glass feeders with the weight of a known volume of the test solutions. The composition of the feeders is an important consideration since, depending on the test chemical, material other than glass can interfere with the availability of the test substance.
- During the test period, the bees are kept in the dark (except during observations) in an incubator at 25±2°C and 60-80% relative humidity.
- Mortality and sublethal effects should be assessed at 24-hour intervals after the start of the test for up to 10 days. Sublethal effects should be assessed according to appropriate categories. Control mortality should be not greater than 15%.
- As with any toxicity test protocol, the stability of the test material must be considered when determining the exact methods used in the study. Ideally, nominal concentrations/levels of the test chemical should be verified through analytical measurements.
- The source of the test bees must be recorded, and to the extent possible, disease/parasite loads should be minimized. Any treatments (*e.g.*, antibiotics) other than the chemical of interest must be documented and must be consistent across treatments/controls. To the extent possible, the bees should be from a

[PAGE * MERGEFORMAT]

8586 single colony and/or derived from colonies with sister queens. As with all studies,
8587 bees should be assigned to treatment groups randomly.
8588

APPENDIX 2 ELEMENTS OF A LARVAL STUDY

Proposed Elements for a Larval Study

- Larvae at the L1 (first instar) stage are fed standardized amounts of a semi-artificial diet. Test items (pesticides or other products of interest) are incorporated into the food at different concentrations within an appropriate range in order to compute the following end points for larvae (L1 to L5), pupae (L5 to adult emergence) and adults (emergence to day 22 post-emergence): LC₅₀, LD₅₀ and NOEC (the NOEC will be the principle target endpoint).
- The reference product is typically dimethoate.

Larvae termination and collection

- For one replicate, larvae are collected from a unique colony. Test colonies have to be healthy and must not show any visible clinical symptoms of pests, pathogens, and/or toxin stress. Tests should be conducted with summer larvae during a period from the middle of spring to the middle of autumn (the exact time of year varies by location). No varroa treatment with the exception brood removal should be applied within the 8 weeks preceding the beginning of experiments.
- At Day -3 (prior grafting, Fig. 4), the queen of the chosen colony is confined in its own colony onto a comb. This can be done using an excluder cage into which a comb (dark preferred) containing empty cells is placed or by using a smaller push-in cage (~10 × 10 cm) which can be used to confine a queen on a given section of comb containing empty cells. In both cases, the comb is placed close to other combs containing brood (Fig. 1).
- At Day -2, with the verification that there are eggs, the queen is removed from the cage 22-26 hours after she was encaged. To ensure that larvae are available at Day 1 of the study it is recommended to cage the queens of 2 or 3 colonies in the event a queen is laying few or no eggs. Based on queen vigour, the queen's isolation time can be reduced in order to minimize variability in larval size (age).

- The comb containing the eggs is left caged to prohibit the queen from ovipositing further on the comb on the same position near the brood frames. The eggs develop until the hatching larvae at Day 1.
- At Day 1 (Fig. 3), the comb containing first instar larvae is transferred from the hive to the laboratory for grafting. As L1 larvae are subject to desiccation a wetted towel should be placed around the comb.

Preparation of rearing material

Rearing Cells

- Larvae (≤ 1 day old) are reared in polystyrene grafting cups (common among beekeeping equipment supply companies. Cells with rounded bottoms are best) having an internal diameter of approximately 9 mm. Before use, the cells are washed and sterilized in 0.4% MBC (methyl benzethonium chloride) water solution, or ethanol and rinsed in sterile water then dried in a laminar-flow hood. Each larva is placed into a well of a 48-well tissue culture plate.
- Larvae plates with lids closed, are placed into a larval chamber such as a hermetic chamber (*e.g.*, Plexiglas desiccator, a plastic container, *etc.*) into which a dish having a potassium sulphate (K_2SO_4) saturated solution is placed to maintain a water saturated atmosphere ($>90\%$ relative humidity). The larval chamber is placed into an incubator at $34,5^\circ C$. It is important that this temperature is maintained within a small range since temperature can affect the toxicity of pesticides to immature bees (Medrzycki *et al.* 2010).

Larval Food

- The food is composed of three diets for different days of the study with Diet A following the recipe of Vandenberg and Shimanuki (1987) and subsequent diets modified from this basic diet.
 - Diet A (Day 1): 50% fresh royal jelly + 50% aqueous solution containing 2% yeast extract, 12% glucose and 12% fructose. A recipe for 20 g diet contains 10 g

- 8649 royal jelly, 1.2 g glucose, 1.2 g fructose, and 0.2 g yeast extract mixed in 7 mL
8650 H₂O.
- 8651 ○ Diet B (Day 3): 50% fresh royal jelly + 50% aqueous solution containing 3%
8652 yeast extract, 15% glucose and 15% fructose. A recipe for 20 g diet contains 10 g
8653 royal jelly, 1.5 g glucose, 1.5 g fructose, and 0.3 g yeast extract mixed in 7 mL
8654 H₂O.
- 8655 ○ Diet C (from Days 4 to 6): 50% fresh royal jelly + 50% aqueous solution
8656 containing 4% yeast extract, 18% glucose and 18% fructose. A recipe for 21 g
8657 diet contains 10 g royal jelly, 1.8 g glucose, 1.8 g fructose, and 0.4 g yeast extract
8658 mixed in 7 mL H₂O.

8659

8660 **General Information Regarding Diet Preparation**

8661

8662 Royal jelly can be stored frozen at -20°C in small aliquots to avoid multiple freezing
8663 which causes a change in the sugar crystals. It should be thawed by placing it at 4°C
8664 overnight, or at room temperature for 1-2 hrs. Reverse osmosis water or distilled water
8665 should be used, boiled for 10 min, and cooled to 45-55 °C (cool enough for hands to
8666 touch) prior to using it for mixing. Water, sugars and yeast should be mixed thoroughly
8667 (all solid materials should be broken up with a sterile spatula) in lab ware (preferably
8668 glass lab ware such as a beaker) that has been autoclaved. The mixture should be
8669 vortexed for 30 seconds. Once the bubbles have settled, the total volume should be
8670 adjusted to 10 mL with the prepared water. Finally when the mixture has room
8671 temperature, 10 g of royal jelly should be added to the mixture and the mixture vortexed
8672 for 30 seconds. The diets prepared for a test should be stored in a refrigerator at ~5-10°C
8673 during the test.

8674 **Pupation and emergence**

8675

- 8676 • At Day 7 (prepupal stage), the plates with open lids are transferred into a pupal
8677 chamber (*i.e.*, a hermetic Plexiglas desiccator, a plastic container, *etc.*). The
8678 chamber should be maintained with a saturated atmosphere (~75% relative

humidity) this can be achieved by placing a dish with a NaCl saturated solution into the chamber.

- The container is then placed into an incubator at 34,5°C.
- At Day 15, each plate is transferred into an emergence box (~11 × 15 × 12cm) with a cover that is aerated with wire gauze. The emergence chamber should contain a piece of comb (~3 × 5 cm) which attracts the emerging bees. Emerging bees are fed *ad libitum* with a sucrose syrup solution (50% sucrose/distilled water by volume) that is supplied in an 2ml eppendorf tube with a hole below. The emergence box is returned to the pupal chamber.

Grafting and feeding of larvae

- The rearing cells in the well plate are prepared by pipetting 20 µl of Diet A into each cell. The comb is placed angular on a clean table and a cold light or LED light is used for illumination to prevent larvae from drying.
- The grafting of the L1 larvae is performed by quick transfer from the comb to each plastic cell cup and placed on the surface of the diet using a grafting instrument of choice (a grafting spoon, paint brush size 00, Chinese grafting tool, etc.).
- If grafting is performed from several combs or a comb is not use for a moment it should be covered by the wetted towel. The grafting should be performed randomly to maintain treatment heterogeneity.
- When a plate is completed with 48 larvae, it is placed into the larval chamber and then into the incubator immediately.
- The larvae are fed once a day (except at Day 2) at the same time of day (+/- 1 hour) 3 different diets in different amounts using a stepwise pipette with sterile tips (see Fig. 4 for feeding timeline) following the scheme given in Figure 4. Prior to administration to the larvae, the diet is warmed to 34,5°C by placing in the incubator 1 hour prior feeding. The diet should be pipetted on the inner side wall of the cell to slide slowly down in order to avoid the larvae from drowning. It

8709 must be avoided that diet is placed on the larvae to prevent the blocking of the
8710 spiracles.

8711

8712 **Experimental Groups**

8713

- 8714 • The experimental unit is a single larvae in a cell and a treatment group consists of
8715 minimum 24 larvae (half of a 48 tissue culture plate). For each test, the following
8716 treatment groups should be used:
 - 8717 - 1 control diet without solvent (24 larvae)
 - 8718 - 1 control diet with solvent (24 larvae).
 - 8719 - 5 test item concentrations (24 larvae each)
 - 8720 - 1 reference treatment with dimethoate (24 larvae)

8721 Each test (all 8 groups of test larvae) should be replicated across 3 independent colonies
8722 (unrelated queens).

8723

8724 **Preparation of the pesticide solutions**

8725

- 8726 • The test pesticide is dissolved in water (the preferred solvent) or acetone if the
8727 pesticide is not water soluble. If a solvent other than water is used, a second
8728 solvent control group must be used consisting of control larvae fed with diet
8729 containing the solvent at the same concentration as the treated samples.
- 8730 • Dilutions of the stock solutions are made with non-chlorinate, sterile drinking
8731 water using disposable pipette tips equipped with a filter. The amount of test
8732 solution administered must not exceed 10% of the final volume. In all cases, one
8733 must include the same final volume of water or solvent in all treatments and
8734 controls.

8735

8736 **Treatments**

8737

- 8738 • In acute toxicity tests, larvae are treated at Day 4 with Diet C containing the test
8739 item solutions at their respective test concentrations.

8740

- 8741 • For chronic toxicity tests, larvae are treated daily (except Day 2) with the diets
8742 containing the test item solutions at test concentrations. In order to assess the
8743 adequate endpoints (NOEC and LC₅₀), it is recommended to run a preliminary
8744 experiment where the appropriate concentrations of the test preparation, vary
8745 geometrically at 5 to 10 different concentrations, can be determined.

8746 **Toxic Reference**

8747

- 8748 • The toxic reference is typically the organophosphate dimethoate:
- 8749 - in acute toxicity tests: 3 µg/larva is mixed with Diet C and provided at Day 4,
8750 - in chronic toxicity tests: it is mixed with the three diets at test concentrations
8751 of 20 µg / kg diet.

8752

8753 **Definition of Mortality**

8754

- 8755 • LARVA: An immobile larva (not breathing or moving when viewed under a
8756 dissecting scope) is recorded as dead. If a larva's mortality is in doubt, examine
8757 the larva the following day.
- 8758 • PUPA: A non-emerged individual at Day 22 is considered as dead during the pupal
8759 stage.
- 8760 • ADULT: An immobile adult which does not react to a tactile stimulation is
8761 recorded as dead.

8762

8763 **Mortality Assessments**

8764

8765 LARVA: Daily (except Day 2) when larvae are fed, all dead larvae are removed for
8766 sanitary reasons. Specific mortality checks are made according to the type of test (acute
8767 or chronic). In the acute test where exposure is at Day 4, a first mortality check is made at
8768 Day 4 in order to replace the dead larvae before they have started consuming the diet
8769 containing the insecticide. Mortality must also be recorded at Days 5, 6 and 7. In the test
8770 with chronic exposure mortality is noted at Day 7.

8771 PUPA: Non-emerged bees are counted at Day 22.

8772

8773 ADULT: short-term survival: living [emerged] adult bees and dead adults which left their
8774 cell and show a normal development are counted at Day 22.

8775

8776 Long-term survival: living adult bees and dead adults are assessed daily through 10 days
8777 post-emergence. Typically, control mortality increases from day 12 to 14.

8778

8779 **Validity range of data**

8780 • For the test to be considered valid, bees fed the control diet must adhere to the
8781 following:

- 8782 ○ Larvae - $\leq 10\%$ mortality (number of dead larvae/24)
- 8783 ○ Pupae - $\leq 20\%$ mortality (number of dead pupae at Day 22/24)
- 8784 ○ Adult- $\leq 10\%$ mortality (number of dead adults at Day 10 post-emergence/total
8785 number of emerged adults)

8786 If the mortality in the control groups is higher than that outlined above, the test is
8787 invalidated.

8788 The mortality rate within the dimethoate control should be:

- 8789 • Acute test: $\geq 50\%$ mortality at Day 6 for larvae exposed to 3 μg dimethoate / larva
8790 at D4

- Chronic test: $\geq 50\%$ cumulative mortality at Day 7 after exposure to 20 mg dimethoate/kg diet.

The calculated LC_{50} must be in each case between the concentrations tested; the LC_{50} must not be extrapolated outside of the tested concentration.

LD_{50} and LC_{50} Calculation

- Mortalities are expressed in percentage of the reference populations after an adjustment according to the Abbott formula (1925):

$$M = \frac{(P - T)}{S} \times 100 \text{ EQ1: raw mortalities}$$

$$M = \frac{(\%P - \%T)}{100 - \%T} \times 100 \text{ EQ2: percent mortalities}$$

- M is the adjusted mortality expressed in percent of the initial population, initial number of larvae (24) for a larval mortality, number of living pre pupae at Day 7 for pupal mortality, number of emerged [adult] bees at Day 22 for an adult mortality

- P: mortality due to the treatment

- T: control mortality

- S: surviving number in control

- %P: mortality percentage due to the treatment

- %T: control mortality percentage

The results will be analysed using regression and/or probit modelling. All raw and adjusted data must appear in the study report. The lethality graphs and their equations must be reported. The results should include LC_{50} values for 24 and 48h expressed in terms of μg per individual (for the acute test), and for a LC_{50} in μg per litre of solution

8816 (ppb) for the chronic test. These calculated variables should include their respective 95%
8817 confidence intervals.

8818 **Determination of the NOEC**

8819

8820 The NOEC is the highest concentration which does not induce mortality significantly
8821 higher than that observed in controls. This analysis is typically performed using a Chi2
8822 test (1 tail test, at an alpha of 0.05).

8823

APPENDIX 3 ELEMENTS OF ARTIFICIAL FLOWER TEST

Artificial flower experiments are performed with a nucleus (“nuc”) colony (about 4000 workers and a fertile queen) placed in an outdoor flight cage. Three feeding periods are typically included in the test design. The initial feeding is with an untreated (blank) sucrose solution (500 g.kg⁻¹) delivered in both the artificial flower feeder and a standard feeder placed in the flight cage; the second feeding is treated sucrose solutions; and, the third feeding is again, an untreated (blank) sucrose solution. The foraging activity and the learning performances are evaluated using an artificial flower feeder adapted from the experimental device described by Pham and Masson (1985). The feeder consists of six feeding sites arrayed on a circular tray (50 cm diameter). Each artificial flower feeder is a plastic Petri dish containing glass balls (allowing landing of foragers on the feeding sites) and filled with a sucrose solution that is, or is not treated with the test compound. The sucrose solution in each Petri dish is maintained at a constant level, and on each side of the feeding sites an odorant (*e.g.*, pure linalool) is allowed to diffuse. To limit the influence of visual or spatial cues, the artificial feeder is rotated slowly (*e.g.*, 1/3 rpm). The device is placed in front of the hive entrance.

The conditioning (pairing odor/sucrose reward) is conducted for 2 hours on the first day. Testing is then carried out on the following days. The testing device is set with 3 scented devices with food reward alternating with 3 unscented devices, without any food reward. The testing device is presented for 5 minutes and then replaced by the conditioning device for 15 minutes, with the odor being again associated with a sucrose solution (treated or untreated). For each observation (every 30 seconds over the 5-min observation period), the number of forager visits on either the scented sites or the unscented artificial flowers is recorded. After each test, the tray is cleaned with ethanol and the Petri dishes are changed to avoid the deposition of marking scent by the forager bees. The volume of sucrose solution up taken by the foragers is measured.

References

[PAGE * MERGEFORMAT]

8855 Pham, M.H., Masson, C., 1985, Analyse par conditionnement associative du mecanisme
8856 de la reconnaissance de sources alimentaires par l'abeille. Bu. Soc. Entomol. Fr. 90, 1216-
8857 1223.
8858
8859

8860

8861 APPENDIX 4 ELEMENTS OF THE VISUAL LEARNING TEST

8862

8863

8864 Experimental maze tests have been developed to test whether a pesticide compound can
8865 disorientate foragers. Orientation performance of bees in a complex maze relies on
8866 associative learning between a visual mark and a reward of sugar solution.

8867


8868 The colony is maintained in an outdoor flight cage covered with an insect-proof cloth.
8869 The maze consisted of a matrix of 4 rows \times 5 columns of identical cubic boxes, each side
8870 of the box measuring 30 cm; each wall has a 4-cm diameter hole in its centre through
8871 which bees can move to the adjacent box (Zhang *et al.* 1996). The boxes are made of
8872 white opaque plexiglass, and a metallic screen (3 mm \times 3 mm mesh) covers the maze.

8873

8874 Bees fly through a sequence of boxes to reach a feeder containing a reward of sugar
8875 solution. The path through the maze spans 9 boxes, including 3 decision boxes and 6
8876 non-decision boxes. A non-decision box has two holes, each in a different wall; one hole
8877 where the bee is to enter and another hole and through which the bee is expected to leave.
8878 A decision box has three holes, each in a different wall. One hole is where the bee enters
8879 and the bee then is expected to choose between the other two holes.

8880

8881 During conditioning, bees are collectively trained to associate a mark (designating the
8882 correct hole/path) with food. To achieve this, a mark is fixed in front of the correct
8883 hole/path as well as the sucrose solution feeder outside the maze for one hour. For an
8884 additional hour, the feeder is placed in the first box of the path for about 30 min, then in
8885 the second box of the path the next 30 min, then in the third box during for 30 min and so
8886 on. The feeder is then moved to the fifth box for about 20 min. Finally, the feeder is
8887 placed at the end of the path (Figure A4-1) in the reward box. Several conditioning
8888 periods (3-5) are necessary to train a sufficient number of bees. After the bees have found
8889 the food (reward) and have fed, the bees are captured on the sugar syrup feeder and are
8890 then placed in rearing cages equipped with a water supply and a sugar syrup feeder (50 %



After conditioning, the capacity of an individual bee to negotiate a path through the maze is tested. An observer notes the number of correct and incorrect decisions, and then number of turns back. During retrieval tests, several different paths are used. During a test, only one bee is allowed into the maze at a time and is tested for one of the five path configurations.

Four categories of performances are defined and one of categories is assigned to each of them:

1. bee moves through the maze and arrives directly at the goal (reward box);
2. bee moves through the maze and arrives to the goal with one or more turns back (bee leaves the box through the hole from which it entered);
3. bee moves through the maze with mistake(s) (bee making one or more wrong turns at the decision boxes) but arrives to the goal;
4. bee does not arrive to the goal within 5 min after entering the maze.

Performances of control and treated bees are evaluated as the mean of the categories assigned to bees in each group. The time required to reach the goal from the instant of entering the maze is measured for each bee. Flight time is considered only for bees flying through the whole path within 5 minutes.

Strengths/Weaknesses

Menzel *et al.* (1974) have demonstrated that honey bees in flight can associate a visual mark to a reward and, this associative learning is used by bees to negotiate a path in a complex maze (Zhang *et al.* 1996). After treatment with a sublethal dose of a chemical, the ability of bees to perform the task can be impaired compared to untreated control bees (Decourtye *et al.* 2009). Work with this type of experimental test has indicated that orientation capacities of foragers in a complex maze can be affected by a pesticide. The maze test relies on the visual learning of foragers in relation to navigation. However, while the maze test has demonstrated effects with pesticides which are neurotoxic, there are insufficient data at this time to determine whether the test will provide useful

information for chemicals with other modes of action. Additionally, bee navigation in the field relies upon several guidance mechanisms, (*e.g.*, position of sun, magnetism, *etc.*), unlike in the maze where performance is based on the use of a limited number of pertinent cues. Additional experiments are needed to establish whether effects on maze performance reflect what may actually occur when foragers exposed to pesticides in the field and are then confronted with complex environmental cues.

References

- Decourtye A., Lefort, S., Devillers J., Gauthier M., Aupinel P., Tisseur M., Sublethal effects of fipronil on the ability of honeybees (*Apis mellifera* L.) to orientate in a complex maze. In: Oomen PA, Thompson HM., editors. Hazards of pesticides to bees. Belin. Orno Brynda GmbH; 2009. p.75-83.
- Menzel R., Erber, J., Masuhr, T., (1974) Learning and memory in the honey bee. Experimental Analysis of Insect Behavior (BartonBrowne L.,ed) Springer, Berlin.
- Ibid.*, Zhang *et al.* 1996
- Zhang SW, Bartsch K and Srinivasan MV (1996) Maze Learning by Honeybees. Neurobiol Learn Mem; 66:267-282.

APPENDIX 5 FORAGING BEHAVIOR WITH RADIO FREQUENCY IDENTIFICATION

Experimental test situations have been designed to explore feeding behavior and social communication (Schricker and Stephen 1970; Cox and Wilson 1984; Bortolotti *et al.* 2003; Yang *et al.* 2008). These studies generate information on trips between a feeder and a hive, with the variable of pesticide exposure is explored. Most test techniques (in this area of exploration) are limited by the number of individuals that can be simultaneously monitored, and by the time devoted to recording individuals. To address these limitations, automated tracking and identification systems have been developed using radio frequency (RF) transponder technology. The use of transponders has the potential to revolutionize the study of insect life-history traits, especially in behavioral ecotoxicology.

Different transponder devices have been employed on the honey bees, including: harmonic radar (*e.g.*, Riley and Smith 2002) and radio frequency identification (RFID; Streit *et al.* 2003). Currently, the RFID tags seem to offer unique advantages. Advantages of the RFID technology include the large number of individual insects that can be tracked, the number of detections which can be monitored rapidly and simultaneously (milliseconds) without interference from a variety of matrices (*e.g.*, propolis, glue, plastic, wood, *etc.*) which frequently encumber visual observations. RFID is also less disruptive on bee behavior given the small size of the tags compared to what is needed for harmonic radar tracking.

The tag itself is not equipped with a power source (passive function); rather, it obtains its signal power from the detector (transponder) and causes the tag to emit a unique identification code. The detector (reader) can recognize a virtually unlimited number (18×10^{18} possible identification codes) of individually tagged insects. The RFID technology allows detecting each time a tag-equipped bee is passing in close proximity to the reader (working distance of approximately 3 m) in a study to determine the error rate, Streit *et al.* 2003, demonstrated that 1 out of 300 tagged bees was not recorded by the RFID readers.

8999

9000 Experimental Procedure

9001

9002 The experimental colony is maintained in an outdoor tunnel (8 m × 20 m, 3.5 m high)
 9003 covered with an insect-proof cloth and the ground covered with a double layer of plastic.
 9004 Bees are fed with pollen which is renewed daily. A sucrose solution (50% w/w) is
 9005 delivered by a feeder positioned 18 m from the hive entrance, in a wooden box (26 cm ×
 9006 26 cm, 30 cm high).

9007

9008 RFID tags (64-bit, 13.56 MHz system, 1.0 mm × 1.6 mm × 0.5 mm), weighing about 3
 9009 mg (3% of bees' weight), represent a relatively low weight given that the honey
 9010 bee is able to carry up 70 mg of nectar (Ribbands 1953) and 10 mg of pollen (Hodges
 9011 1952). A tag-equipped bee passing underneath the reader is identified by the reader that
 9012 sends the data along with real-time recording to a database. Readers are placed at the
 9013 entrance of the hive and at the artificial feeder. By passing underneath the reader both at
 9014 the hive and at the feeder, the foraging bee is monitored twice, thus determining the
 9015 direction of travel and the travel time between the two recording points. The reader
 9016 software records the identification code and the exact time of the detection automatically
 9017 for 6 days in a database for later analysis of spatial and temporal information. Analyses
 9018 of the data may provide information on the time spent within the hive; time spent at the
 9019 feeder; time spent between the feeder and the hive, number of entries into and exits from
 9020 the hive, and the number of entries into and exits from the feeder.

9021

9022 RFID devices allow the study of both the behavioral traits and the lifespan of bees,
 9023 especially under biotic and/or abiotic stress. However, the large quantity of data obtained
 9024 with this technique requires an interface for analyzing the data and providing the life-
 9025 history traits of individual bees. Under semi-field conditions, RFID microchips have
 9026 provided detectable effects due to exposure to an insecticide (Decourtye *et al.* 2011).

9027

9028 **References**

9029

9030 Bortolotti L, Montanari R, Marcelino J, Medrzycki P, Maini S, Porrini C (2003) Effects
9031 of sub-lethal imidacloprid doses on the homing rate and foraging activity of honey bees.
9032 Bull Insectol; 56:63-67.
9033
9034 Cox R. .L and W. T Wilson (1984) Effects of permethrin on the behavior of individually
9035 tagged honey bees, *Apis mellifera* L. (Hymenoptera: Apidae). Environ Entomol; 13:375-
9036 378.
9037
9038 Decourtye A., Devillers J., Aupinel P., Brun F., Bagnis C., et. al. (2011) Honeybee
9039 tracking with microchips: a new methodology to measure the effects of pesticides.
9040 Ecotoxicology London England 20: 429-437.
9041
9042 Hodges D (1952) The pollen load of the honeybee. London Bee Research Association,
9043 London.
9044
9045
9046 Ribbands CR (1953) The behaviour and social life of honeybees. London Bee Research
9047 Association, London.
9048
9049 Schricker B, Stephen WP (1970) The effects of sublethal doses of parathion on honeybee
9050 behaviour. I. Oral administration and the communication dance. J Apicult Res 9:141–
9051 153.
9052
9053 Streit S, Bock F, Pirk CWW, Tautz J (2003) Automatic life-long monitoring of individual
9054 insect behaviour now possible. Zoology 106:169–171.
9055
9056 Yang, E.C., Chuang, Y.C., Chen, Y.L., and Chang, L.H., Abnormal Foraging Behavior
9057 Induced by Sublethal Dosage of Imidacloprid in the Honey Bee (Hymenoptera: Apidae).
9058 Journal of Economic Entomology, Entomological Society of America, 101(6): 1743-
9059 1748, 2008
9060
9061

APPENDIX 6 DETAILED DESCRIPTION OF THE PROPOSED OVERALL RISK ASSESSMENT SCHEME

Sprayed Treatments

1. Details of the product and its pattern of use

The most important route of exposure of honey bees to plant protection products for spray applications is by direct exposure to field sprays. In some cases, exposure of bees is not possible and there is no need for a detailed assessment of risks, such as in the case of products used during winter when bees are not foraging, pre-emergent herbicides where plants may not be present to forage on, indoor residential uses and uses in glasshouses where bees are not used for pollination. However, in any scenario where, irrespective of the timing of application, the presence of residues in flowers cannot be excluded the potential for bee exposure should be considered.

The attractiveness of the crop to honey bees may be considered as an entry point for this risk assessment. Useful guidance in this respect may be found in the MRL Working Group (EC, 2009) publication which includes additional criteria to consider, such as the presence of other sources of nectar/pollen in the foraging area. In general, a crop can be considered as unattractive to bees when it is harvested before flowering. Some plants that are intrinsically unattractive to bees may be visited by bees because of extra floral nectaries (*e.g.*, in field beans) or honeydew produced by aphids.

As a basis for applying the assessment scheme depicted in **Figure 2**, full details of the product and the intended use must be available. (→ **2.**)

2a & 2b. Is exposure of adult/immature stages of bees possible?

Based on the information from the product and the intended application it has to be decided whether exposure of adult bees and immature stages (larvae and pupae; brood) can be excluded. The justification has to take into account all routes of exposure that may be relevant to the intended use, *e.g.*, through residues on flowers or in flower matrices (*e.g.*, pollen, nectar), and as for non-*Apis* bees in leaves, soil, *etc.* (**Table 3**).

The screening step has to be initiated if exposure of adult bees (→ **3a.**) or immature stages (→ **3b.**) to the active ingredient cannot be excluded. Further risk assessment is not required in cases where exposure can be ruled out for both adults and immature stages of bees (→ **6.**).

3a. Assess the toxicity of a. i. to *Apis mellifera* adults:

Establish acute oral and contact LD₅₀, calculate HQ (Appl. Rate/LD₅₀). Is HQ below the trigger value, (e.g., HQ <50?)

Acute oral and contact toxicity of the active ingredient to adult honey bees should be determined in appropriate laboratory tests generating median lethal doses (LD₅₀) for both routes of exposure (*cf.* Chapter 7). The highest intended field application rate is used to estimate possible exposure in comparison to the most sensitive of these LD₅₀ endpoints. A hazard quotient (HQ) is calculated by dividing the application rate (g a.i./ha) by the most sensitive acute toxicity endpoint (µg/bee).

The resulting HQ does not directly specify the relation of exposure level and toxicity since the numerator (application rate in terms of g a.i./ha) and denominator (LD₅₀ in terms of µg/bee) of the HQ are in different units of measurement. Rather, it is used as a preliminary screen to indicate whether a level of exposure may lead to adverse effects (*i.e.*, that a presumption of minimal risk cannot be made) based on empirical incident data. This initial HQ calculation is used as an indicator of risks in the European regulatory process and has been compared to EU incident data. Comparisons of screening-level HQ values with incident data have indicated that adverse effects in the field are not observed when HQ values are greater than 50 (see Mineau *et al.* 2008). In this flow chart, the screening-level HQ trigger of 50 is given as an example of value that is used in Europe for screening purposes (EC, 2010); however, regulatory authorities must develop their own triggers for moving to more refined assessments. The intent here is to demonstrate that at a screening level, relatively coarse measures of exposure are used in combination with relatively simple measures of effects to determine whether risk can be presumed low.

Where HQ exceeds the trigger value a higher-tier risk assessment or consideration of risk mitigation measures is required (→ **7**). Otherwise the risk to adult honey bees (*Apis*-bees)

may be assessed to be low and consideration of possible effects on non-*Apis* bees is the next step of the screening procedure (→ 4a.).

3b. Assess the toxicity of a. i. to *Apis mellifera* larvae:

Establish NOEL, Calculate TER, is TER > 1?

Chronic toxicity of the active ingredient to honey bee larvae should be determined in an appropriate laboratory test generating a NOEC for the brood development including adult emergence weight (*cf.* Chapter 8). For the risk assessment, this toxicity endpoint is compared to the exposure of honey bee larvae via contaminated food items. If chemical/crop specific exposure data are not available, then default exposure estimates may be determined through information from residue analysis data (see Chapter 7 for more details.).

Toxicity and exposure data (expressed in same measurement units of ug/kg) are related in a TER calculation (TER = NOEC divided by predicted exposure. The resulting TER is compared to an appropriate trigger and any value above that trigger indicates a presumption of minimal risks. In the flow chart, a trigger of 1 is used based on the presumption that maximum residues measured in pollen have not exceeded 100 ug/kg and that using a value of 1000 ug/kg would likely be considered protective. Again, appropriate exposure values and triggers must be determined by the regulatory authority; however, at this level of refinement, potential risks are determined from toxicity data on bee brood and rely on the no observed effect concentration.

4a. Assess possible impacts to non-*Apis* adults using NTA data as surrogate: If HQ for *Apis* is between 5 and 50, consider NTA: calculate HQ, is HQ < 2?

When specific data on the toxicity of the compound to adult non-*Apis* bee species are lacking, potential risk may be estimated from the data available on the honey bee and if available in the dossier, the use of data on other non-target arthropods (NTA).

A possible tiered approach using these data, to screen for the need of a risk assessment specific to non-*Apis* bees that would use dedicated data is presented thereafter.

Initially the HQ calculated under point 3a. using the honey bee LD₅₀ could be used as a trigger of concern for possible effects on non-*Apis* bees. This HQ value would then be compared to a trigger value lower by an order of magnitude to account for inter-species

variability of toxicity data. Thus the HQ calculated under point 3a shall be lower than 5 for acceptable risks to be concluded for adult honey bees and adult non-*Apis*. The order of magnitude increase in the trigger is intended to account for inter-species variability. In the case of $5 < \text{HQ} < 50$, data on NTA species would be considered in order to conclude about the level of concern of the product for non-*Apis* bees, taking into consideration the level of risk for NTA species and how representative the test species are of non-*Apis* bees expected to frequent the crop *etc.*. As an example, in the risk assessment scheme for NTA performed in the EU, the laboratory toxicity endpoint for the most sensitive NTA species is compared to the maximum application rate in an HQ calculation (where the toxicity endpoint is also expressed as a rate [g a.i./ha]) (Candolfi *et al.* 2001). This HQ is assessed against a trigger value of 2. Where the HQ value for NTA exceeds this trigger value, it is concluded that risk to non-*Apis* cannot be excluded and that risk estimates should be further refined. This refinement could consider the generation of specific adult toxicity data with a non-*Apis* species before a higher tier risk assessment or consideration of risk mitigation measures (\rightarrow 5a.). If mitigation measures are considered, then the effect of these measures on potential exposure should be considered using the same process as just described from the point where potential risk could not be presumed low/minimal.

If this HQ for NTA is below the trigger value, the risk to adult non-*Apis* bees may be considered minimal (\rightarrow 6).

5a. Establish adult oral and contact LD₅₀ for a non-*Apis* bee species: Calculate HQ, is HQ < 50?

The screening step 3a. may be repeated using specific toxicity data generated in tests with a non-*Apis* bee species. For further details on laboratory studies on non-*Apis* bees see Chapter 8.

Where the HQ exceeds the trigger value of 50, a higher-tier risk assessment or consideration of risk mitigation measures is required (\rightarrow 7.). For HQ values below the trigger, risk to larvae of non-*Apis* bees is considered minimal (\rightarrow 6.).

5b. Establish larval NOEL for relevant non-*Apis* bee species. Calculate TER, is TER > 10?

The screening step **3b.** may be repeated using specific toxicity data generated in tests with a non-*Apis* bee species. For further details on laboratory studies on non-*Apis* bees see Chapter 8.

Where TER is below the trigger value of 10, a higher-tier risk assessment or consideration of risk mitigation measures is required (→ 7.). For TER values above 10, the risk to larvae of non-*Apis* bees is considered minimal (→ 6.).

6. Presumption of minimal risk.

If exposure can be excluded or the criteria in the screening step are met for both adult bees and larvae, then a minimal risk to honey bees and/or non-*Apis* bees can be presumed.

A minimal risk for honey bees and/or non-*Apis* bees can also be presumed if treatments in higher-tier semi-field and field tests result in no significant difference compared to the untreated control when evaluated against the protection goals. Further risk mitigation measures are not required.

7. Continue with higher tier risk assessment or consider risk mitigation measures and reassess.

If in the screening step the criteria for adult bees or larvae are not met, a higher-tier risk assessment (depicted in **Figure 3**) should to be performed (→ 8.). The screening step may be repeated to consider specific risk mitigation measures that exclude or mitigate exposure (*e.g.*, by reducing the application rate, avoiding the exposure to residues during flowering *etc.*) (→ 2.). For further considerations of risk mitigation measures see Chapter 11.

8. Is higher tier risk assessment triggered by failing the screening step with non-*Apis* bees?

Concerns identified in the screening procedure(s) and which are not addressed through mitigation, may then be further refined through semi-field or field tests (→ 9.). If in the

screening step(s) potential risks were identified for non-*Apis* species (adults or larvae) that will be further refined in a higher tier study, then the assessor should consider whether a higher-tier study with honey bees would also be representative of the concerns identified for non-*Apis* bees in the screening step (→ **13.**).

9. Is higher tier risk assessment triggered by failing the screening step with regard to honey bees?

If in the screening step the criteria for *Apis* (adult bees or larvae) are not met, a semi-field or field test should be performed to further refine potential concerns. (→ **10.** or **11.**). In transitioning from the use laboratory-based studies on individual bees to semi-field and field toxicity studies typically conducted at the colony level, test conditions are intended to reflect more realistic exposure conditions. Unlike the lower tier studies though, exposure is incorporated into the results of the semi-field and field studies such that the question being asked is whether there is an adverse effect under the conditions tested. Since measurement endpoints are selected in higher tier studies to directly reflect assessment endpoints which are in turn intended to address protection goals, these studies simply answer a yes/no question and do not require risk estimates, *i.e.*, no HQ or TER is calculated..

10 and 11. Assess the effects of the a. i. to *Apis mellifera* in a semi-field or a field test: Do results indicate minimal risk (no significant difference to control)?

Concerns raised in the screening procedure may be investigated through a semi-field test where possible effects are assessed against the criteria related to the protection goals. This is to say that measurement endpoints should be readily related to assessment endpoints which in turn reflect protection goals. For example, if a protection goal is to ensure pollination services, then having sufficient forage strength in a colony is important. Therefore, adult and larval bee survival is a reasonable assessment endpoint and the number of dead bees in traps and/or brood termination rates may be reasonable measurement endpoints to reflect that assessment endpoint.

The choice between semi-field and field- testing depends on the profile of the product as for example the expected duration of exposure, the possibility of occurrence of effects,

9245 the nature of the anticipated effects, *etc.* This choice is a case by case decision, but the
 9246 design of semi-field and field studies should be informed by the information deduced
 9247 from lower tier testing and other relevant lines of evidence, *e.g.*, incident data.
 9248 Semi-field testing (cage, tunnel or tent tests) is a suitable option before full field testing.
 9249 The advantage of semi-field testing is that mortality is easier to assess and exposure of
 9250 bees to the test compound is more readily ensured since bees are confined within a tent
 9251 and cannot forage elsewhere. In addition, if an accurate quantification of exposure is
 9252 needed, semi-field studies may provide more reproducible residue levels due to the
 9253 relative protection from weather conditions.
 9254 Semi-field as well as full field tests aim at evaluating the level of effects that may be
 9255 expected on bees exposed to the product under realistic conditions, *i.e.*, through the crop
 9256 having been treated at proposed application rates. Because the conditions of exposure of
 9257 bees are more reflective of actual use conditions, the results of these trials may be directly
 9258 used in the risk assessment (see Chapter 9).
 9259 The design of semi-field / field testing may also follow a tiered approach. In first
 9260 instance semi-field tests should be designed in order to maximize the exposure of bees to
 9261 residues resulting from an application. For sprayed products, the demonstration of
 9262 acceptable effects in a semi-field or field test performed on a 'standard crop' (*e.g.*, wheat)
 9263 made artificially attractive through a sugar solution and treated at the maximum
 9264 application rate at flowering may be considered as protective for any crop that may be
 9265 further treated with the product. Further steps may consider bee attractive crops treated
 9266 at flowering (*e.g.*, phacelia), and then the specific crops on which the compound will
 9267 actually be applied as a highest tier when a treatment at flowering cannot be excluded.
 9268 Further on, the possibility of an exposure outside the flowering period of the crop through
 9269 for example spray drift onto flowers in vegetated areas or onto flowering weeds within
 9270 the crop (*e.g.*, understory of orchards) should also be considered in the trials, if triggered
 9271 by the lower tiers.
 9272 In the case of soil/ seed treatments, it may be more difficult to identify a surrogate (worst
 9273 case) crop as the exposure results from systemic properties and the attractiveness of the
 9274 crop to bees.

For both sprayed and soil/seed treatments, in the case of systemic activity, if the substance or its residues are persistent and the product may be used on several crops in a rotation, the potential accumulation in soil and subsequent effect on in-plant residues should be considered in the study protocol.

For both semi-field and field trials, it should be demonstrated that the test bees were actually exposed under the environmental conditions (especially weather conditions in case of field trials) of the study. The use of a toxic standard (semi-field trials) or pollen collection and residue analysis, may also help to document exposure. A quantified assessment of the exposure is particularly important for systemic products, as reference substances for systemic products are difficult to define since they too would be dependent on crop properties. There should always be a comparable untreated control in order to provide a reference point against which to compare the test treatment(s). While positive controls (toxic reference chemicals) are frequently used in laboratory and semi-field studies, they are not typically used in full field studies. Therefore, it is not possible to demonstrate definitively that the study design is sufficient to detect treatment effects and it is important to document exposure through residue analyses.

For honey bees, suitable methods for semi-field and field trials are discussed in OEPP/EPPO (2010) (see Chapter 9) which have been defined for sprayed treatment and can be adapted to soil/seed treatments (systemic activity). These studies may also be modified for specific assessments with honey bees, *e.g.*, repellency and other behavioural effects, effects of aged residues or for specific testing of brood effects. Possible adaptations for non-*Apis* species are discussed in chapter 9.

The interpretation of semi- and full-field study results is further detailed in Chapter 9. It should rely on a comparison of effects in the test chemical treatments and in the concurrent negative control. If the semi-field test treatment results in no significant difference from untreated controls in lethal and sublethal effects (*i.e.*, survival, growth, reproduction and foraging behaviour), a minimal risk is indicated (→ 6.). Otherwise a higher-tier evaluation using a field test has to be performed (→ 11.).

12. Risk mitigation measures specific to *Apis mellifera* possible?

Where the results of higher-tier semi-field and field tests indicate that the protection goals are not met, the assessment scheme may be reiterated considering specific risk mitigation measures mitigating the exposure of honey bees (→ 2.) Note in this respect that semi-field and field test may be appropriately adapted in order to check for the efficiency of risk mitigation measures to reduce exposure to and subsequent impact from treatment residues on bees.

13. Are there significant routes of exposure for non-*Apis* bees that are not covered by the honey bee risk assessment and/or risk assessment for other non-target arthropods?

In any case when a risk assessment for non-*Apis* bees is triggered and a refined risk assessment is available for honey bees and NTAs, it may be interesting to discuss the extent these risk assessments address part of the risk issues relative to non-*Apis* species. As an example, concerns with effects on non-*Apis* bees identified at the lower level(s) may in some cases be addressed by semi-field or field tests with honey bees as for example where no additional significant routes of exposure for non-*Apis* bees have to be taken into account. Furthermore, higher-tier field data generated with NTA species may also address these concerns provided the routes of exposure are comparable to those for non-*Apis* bees (Table 3, see Chapter 9). If these data are considered suitable surrogates and if the examination of these data results in no significant risk with regard to the protection goals, then a minimal risk to non-*Apis* bees is indicated (→ 6.). Otherwise semi-field or field tests with non-*Apis* bees should be considered to address the concern (→14).

14 and 15. Assess the effects of the a.i. to a non-*Apis* bee species relevant to the identified route of exposure in a semi-field or a field test: Do results indicate minimal risk (no significant difference to control)?

Potential risks identified in the screening-level assessment may be addressed by appropriately designed semi-field tests where possible effects are assessed against the evaluation criteria related to the protection goals. The derivation of evaluation criteria for specific protection goals is discussed in Chapter 4. For further details on semi-field

studies on non-*Apis* bees see Chapter 9. As previously developed in the case of honey bees, the choice between a semi-field test or a full field study depends on the outcome of lower tier studies and should also consider choices made for honey bees. If the results of semi-field or field test, in conjunction with information from lower tier studies and other relevant data indicate no significant difference in relevant lethal and sublethal effects compared to untreated controls, minimal risk is indicated (→ 6.). Otherwise, further risk mitigation may be considered or the risk has to be presumed as significant (→ 16.).

16. Risk mitigation measures specific to non-*Apis* bee species possible?

Where the results of higher-tier semi-field and field tests on non-*Apis* indicate that the protection goals are not met, the assessment scheme may be reiterated considering specific measures designed to mitigating the exposure of non-*Apis* bees (→ 2.). Note in this respect that semi-field and field test may be appropriately adapted in order to check for the efficiency of risk mitigation measures to limit the exposure and potential impact of treatment residues on non-*Apis* bees.

17. Presumption of significant risk

If there are no measures available to sufficiently mitigate the risk to honey bees and/or non-*Apis* bees indicated by the evaluation of the results of higher-tier semi-field and field tests against the protection goals, then a significant risk has to be presumed.

2. Soil or Seed Treatment With a Systemic Active Substances

1. Details of the product and its pattern of use

As a basis for applying the assessment scheme, details of the product and the intended use must be available, especially the crop, the formulation type, type and timing of application as well as the application rate (g a.i./ha). In addition it has to be determined whether the active ingredient has systemic properties, *i.e.*, significant portions of the compound are translocated in the plant resulting in residues of concern in plant matrices like nectar, pollen and leaves that might lead to exposure of bees (→ 2.). Where persistent soil residues may give rise to uptake of the substance by succeeding (rotational) crops the same considerations with regard to attractiveness of these crops to bees apply as discussed in the description of the risk assessment scheme for spray applications. Restrictions concerning the choice of succeeding crops may be considered as risk mitigation measures.

2a & 2b. Is exposure of adult/immature stages of bees possible?

Based on the information on the product and its intended application it has to be decided whether exposure of adult bees and immature stages (larvae and pupae; brood) can be excluded. The justification has to take into account all routes of exposure that may be relevant to the intended use, *e.g.*, through residues on flowers or in flower matrices (*e.g.*, pollen, nectar), and as for non-*Apis* bees in leaves, soil, *etc.* (Table 3).

The screening step should be initiated if exposure of adult bees (→ 3a.) or immature stages (→ 3b.) to the active ingredient cannot be excluded. Further risk assessment is not required in cases where exposure can be ruled out for both adults and immature stages of bees (→ 6.).

Special routes of exposure of bees as a result of soil or seed treatment application of active substances with systemic properties may not be covered by the risk assessment scheme for spray application. The exposure of bees to residues of a systemic product may occur through transfer of residues taken up by the roots from the seed coating or soil and distributed to the upper (apical) parts of the plant and in particular in matrices of interest to bees (pollen, nectar and honeydew) if the crop is visited by bees. The resulting

residue of concern may comprise the active substance and/or systemic soil degradation products or metabolites formed in the plants.

Honeydew might not be considered a relevant route because the concentration of a systemic compound translocated in the phloem and reaching honeydew without harming aphids should in principle not be capable of harming bees foraging on the honeydew, unless the compound is highly selective towards non-aphid insects. If there is uncertainty regarding potential residues in honeydew because there is insufficient information on selectivity available in the registration dossier, a dedicated evaluation according to the present risk assessment scheme would be triggered.

Information derived from residue studies and plant metabolism studies is in general sufficient to identify if the substance is internally distributed within the plant during its growth, and if it is further degraded into major degradation products. Similarly, possible uptake and distribution in plants of major soil degradation products could be identified in these residue studies as well. The sensitivity (*i. e.*, limits of quantification and detection) of the analytical methods that are used in the residue studies must be checked in order to ensure that they are low enough to detect residue levels that exert toxic effects to bees. If it is uncertain whether the detection methods are sufficiently sensitive, additional investigations have to be considered to demonstrate the absence of residue translocation at potentially toxic levels. Studies that specifically investigate the presence of residues in flowers, nectar or pollen may be considered as an option for the generation of data to refine the predicted exposure of bees.

Other routes of exposure as a consequence of soil or seed treatment application (*e.g.*, drift of abraded treated seed coating dust into adjacent areas attractive to bees) are not specific to systemic active substances and therefore not addressed in this risk assessment scheme. It should be noted that the emission and dispersion of dusts at sowing is considered as reflecting a poor quality sowing and/or formulation practices that could be mitigated to reduce potential exposure to a minimum level. Therefore measures aiming at reducing the emission and dispersion of dusts at sowing should be considered.

3a. Assess the toxicity of a. i. to *Apis mellifera* adults (oral exposure): Establish oral LD₅₀, calculate TER, compare TER to an appropriate trigger value

9422 The acute oral toxicity of the active ingredient to adult honey bees should be determined
9423 in appropriate laboratory tests generating median lethal doses (LD₅₀) (Chapter 8). The
9424 highest intended field application rate is used to estimate possible exposure in
9425 comparison to the most sensitive of acute contact and acute oral LD₅₀ endpoints.

9426 For the risk assessment, the LD₅₀ is set into relation to the exposure of adult honey bees.
9427 For this purpose, a default dietary residue level may be used, as for example the value of
9428 1 mg a.i./kg proposed by the EPPO (EPPO, 2010). Measured residue levels may also be
9429 used as a refinement of exposure estimates. As exposure estimates should reflect the
9430 maximum expected residue levels for a “worst-case” assessment, the measured residue in
9431 plant matrices to be used as a refinement of exposure estimates for TER calculation could
9432 for example be based on the upper 90th percentile of residue data for the relevant crop for
9433 comparison to the most sensitive acute LD₅₀.

9434 Toxicity and exposure data expressed in same units are related in a TER calculation (TER
9435 = LD₅₀ divided by predicted exposure) where residue concentrations have to be expressed
9436 in terms of daily uptake per bee (ug/kg).

9437 The calculated TER is assessed against an appropriate trigger value. A trigger value of 10
9438 may for example be applied indicating that the predicted exposure is lower than the acute
9439 toxicity by at least one order of magnitude and the margin of safety achieved can be
9440 regarded as sufficient to cover the uncertainty related to longer exposure periods and
9441 possible related increased sensitivity (EPPO 2010).

9442 Where the TER is below the trigger value, a higher-tier risk assessment or consideration
9443 of risk mitigation measures is required (→ 8). As a refinement option a prolonged
9444 toxicity test in the laboratory may be considered (→ 4a.). Otherwise the risk to adult
9445 honey bees is assessed to be low an evaluation of possible effects on non-*Apis* bees is the
9446 next step of the screening procedure (→ 5a.).

9447

9448 **3b. Assess the toxicity of a. i. to *Apis mellifera* larvae: Establish NOEL, Calculate**
9449 **TER, compare TER to an appropriate trigger value**

9450 Chronic toxicity of the active ingredient to honey bee larvae should be determined in an
9451 appropriate laboratory test generating a NOEC for the brood development including adult
9452 emergence weight (Chapter 8). For the risk assessment, this toxicity endpoint is

compared to the exposure of honey bee larvae via contaminated food items. If chemical /crop specific exposure data are not available, then default exposure estimates may be determined through information from residue analysis data (see Chapter 7 for more details.).

Toxicity and exposure data (expressed in same measurement units of ug/kg) are related in a TER calculation (TER = NOEC divided by predicted exposure. The resulting TER is compared to an appropriate trigger and any value above that trigger indicates a presumption of minimal risks. In the flow chart, a trigger of 1 is used based on the presumption that maximum residues measured in pollen do not exceed 100 ug/kg and that using a value of 1000 ug/kg would likely be considered protective. Again, appropriate exposure values and triggers must be determined by the regulatory authority; however, at this level of refinement, potential risks are determined from toxicity data on bee brood and rely on the no observed effect concentration.

4a. Assess the oral toxicity of a. i. to *Apis mellifera* adults in a prolonged (10 d) test: establish oral NOEL, calculate TER, compare and compare TER to an appropriate trigger value

As a refinement option the NOEL derived from a 10-d toxicity test with oral exposure may be taken into account before embarking on a higher tier risk assessment. The NOEL is related to the potential exposure of adult honey bees via consumption of contaminated food items (default value as for example 1 mg a.i./kg or measured residue data). A TER value is calculated by dividing NOEL by predicted exposure expressed in the same units of measurement. In this case, since the effects are monitored over a 10-d period, the average (or time-weighted average) of residue levels is a more appropriate exposure estimate in a TER calculation. The calculated TER is assessed against an appropriate trigger value. A trigger value of 1 may be applied since the toxicity endpoint is related to the NOEL.

Where the TER is below the trigger value, a higher-tier risk assessment or consideration of risk mitigation measures is required (→ 8). Otherwise the risk to adult honey bees is assessed to be low and consideration of possible effects on non-*Apis* bees is the next step of the screening procedure (→ 5a.).

9484

9485 **5a. Assess possible impacts on non-*Apis* adults using NTA data as surrogate: If TER**
 9486 **for *Apis* is between 10 and 100, consider NTA data**

9487 When specific data on the toxicity of the compound to adult non-*Apis* bee species are
 9488 lacking, potential risk may be estimated from the data available on the honey bee and if
 9489 available in the dossier, the use of data on other non-target arthropods (NTA).

9490 Explore the NTA data package to ascertain whether there is likely to be a significant risk
 9491 to non-*Apis* bees by considering the characteristics of each species tested, *e.g.* *Aleochara*
 9492 *bilineata* may give some evidence concerning soil-dwelling species and *Aphidius* sp. on
 9493 nectar feeding species. Where a risk to non-*Apis* bees [as estimated using NTA] cannot
 9494 be excluded, more refinement is considered necessary. This refinement could consider
 9495 the generation of specific adult toxicity data with a non-*Apis* species before a higher tier
 9496 risk assessment or consideration of risk mitigation measures (→ 6a.). If mitigation
 9497 measures are considered, then the effect of these measures on potential exposure should
 9498 be considered using the same process as just described from the point where potential risk
 9499 could not be presumed low/minimal.

9500 If the risk to NTA is considered to be minimal, the risk to adult non-*Apis* bees may be
 9501 considered minimal (→ 7).

9502

9503 **6a. Establish adult oral LD₅₀ for a non-*Apis* bee species: calculate TER, compare**
 9504 **TER to an appropriate trigger value**

9505 The screening step 3a. may be repeated using specific toxicity data generated in tests with
 9506 a non-*Apis* bee species. For further details on laboratory studies on non-*Apis* bees see
 9507 Chapter 8.

9508 For the risk assessment, the LD₅₀ endpoint is set into relation to the exposure of adult
 9509 non-*Apis* bees. For this purpose a worst case default dietary residue level of 1 mg a.i./kg
 9510 (EPPO 2010) or measured residue data in relevant food items may be used. Toxicity and
 9511 exposure data expressed in same units are expressed as a ratio in a TER calculation (TER
 9512 = LD₅₀ divided by predicted exposure) where residue concentrations have to be expressed
 9513 in similar terms, *i.e.*, -daily uptake per bee. The calculated TER is assessed against an
 9514 appropriate trigger value. A trigger value of 10 indicating that the predicted exposure is

lower than the acute toxicity by at least one order of magnitude may be considered to be appropriate also for non-*Apis* bees.

Where TER is lower than the trigger value, a higher-tier risk assessment or consideration of risk mitigation measures is required (→ 8.). Otherwise the risk to adults of non-*Apis* bees is considered minimal (→ 7.).

4b. Assess possible impacts on non-*Apis* immature stages: If TER for *Apis* is between 1 and 10, establish larval NOEL for relevant non-*Apis* bee species (→ 5b.).

Otherwise the risk to immature non-*Apis* bees is considered minimal (→ 7.).

Lacking specific data on the toxicity of the compound on immature stages of non-*Apis* bee species, the assessment of possible effects on this group in the screening procedure can utilize data on honey bees. As a trigger of concern for possible effects on non-*Apis* bees the TER calculated under point 3b. using a honey bee larval NOEC is compared to a value higher by an order of magnitude to account for inter-species variability of toxicity data. Where this TER is below a trigger value of 10 a refinement of the screening step may be considered generating specific toxicity data with immature stages of non-*Apis* bee species before a higher-tier risk assessment or consideration of risk mitigation measures is required.

5b. Establish larval NOEL for a non-*Apis* bee species. Calculate TER, compare TER to an appropriate trigger value

The screening step 3b. may be repeated using specific toxicity data generated in tests with a non-*Apis* bee species. For further details on laboratory studies on immature stages of non-*Apis* bees see Chapter 8. Toxicity and exposure data expressed in same units are expressed as a ration in a TER calculation (TER = NOEC divided by predicted exposure concentration). The calculated TER is assessed against an appropriate trigger value. A trigger value of 10 indicating that the predicted exposure is lower than the acute toxicity by at least one order of magnitude may be considered to be appropriate also for non-*Apis* bees.

Where TER is below the trigger value, a higher-tier risk assessment or consideration of risk mitigation measures is required (→ 8.). For TER values that are higher than the trigger, the risk to larvae of non-*Apis* bees is considered minimal (→ 7.).

7. Presumption of minimal risk.

If exposure can be excluded or the assessment criteria in the screening step are met for both adult bees and larvae a minimal risk to honey bees and non-*Apis* bees can be presumed.

A minimal risk for honey bees and non-*Apis* bees can also be presumed if treatments in appropriate higher-tier semi-field and field tests result in no significant difference compared to the untreated control when evaluated against the protection goals. Further risk mitigation measures are not required.

8. Continue with higher tier risk assessment or consider risk mitigation measures and reassess.

If in the screening step the assessment criteria for adult bees or larvae are not met, a higher-tier risk assessment should be performed (→ 9.). Alternatively the screening step may be repeated considering specific risk measures excluding or mitigating exposure (→ 2.). For further considerations on risk mitigation measures see Chapter 12.

9. Is higher tier risk assessment triggered by failing the screening step with regard to non-*Apis* bees?

Concerns identified in the screening procedure have to be addressed in semi-field or field tests with honey bees (→ 10.). If in the screening step the criteria for adult bees or larvae are not met with regard to non-*Apis* bees, it must be determined whether a higher-tier study with honey bees are sufficient to cover concerns identified for non-*Apis* bees in the screening step (→ 14.).

10. Is higher tier risk assessment triggered by failing the screening step with regard to *Apis mellifera*?

If in the screening step the criteria for adult bees or larvae are not met only with respect to honey bees, a semi-field or field test should be performed to address the concern (→ 11. or 12.).

(Note: Higher tier part of the risk assessment schemes is identical for both spray and soil/seed treatment application. Note: Due to an additional step in the screening procedure, the numbering of the steps in the higher tier risk assessment scheme for soil/seed treatment application is different [+1])

11. and 12. Assess the effects of the a. i. to *Apis mellifera* in a semi-field or a field test: do results indicate minimal risk (no significant difference to control)?

See 10 and 11 in the risk assessment flowchart for sprayed treatments

Where in the semi-field test or in the field test treatment results in no significant difference in lethal and sublethal effects on survival, growth, reproduction and foraging behaviour compared to untreated control, a minimal risk is indicated (→ 7.). Otherwise a higher-tier evaluation a field test has to be performed (→ 12.).

13. Risk mitigation measures specific to *Apis mellifera* possible?

Where the results of higher-tier semi-field and field tests indicate that the protection goals are not met, the assessment scheme may be reiterated considering specific measures to mitigate the exposure of honey bees (→ 2.). Note in this respect that semi-field and field test may be appropriately adapted in order to check for the efficacy of risk mitigation measures to limit the exposure and subsequent impact on bees.

14. Are there significant routes of exposure for non-*Apis* bees that are not covered by the honey bee risk assessment and/or risk assessment for other non-target arthropods?

In any case when a risk assessment for non-*Apis* bees is triggered and a refined risk assessment is available for honey bees and NTAs, it may be interesting to discuss the extent to which these risk assessments address part of the risk issues relative to non-*Apis* species. As an example, concerns with effects on non-*Apis* bees identified at the lower level(s) may in some cases be addressed by semi-field or field tests with honey bees as

for example where no additional significant routes of exposure for non-*Apis* bees have to be taken into account. Furthermore, higher-tier field data generated with NTA species may also address these concerns provided the routes of exposure are comparable to those for non-*Apis* bees (Table 3, see Chapter 9). If these data can serve as surrogates and if the examination of these data results in no significant risk with regard to the protection goals, then a minimal risk to non-*Apis* bees is indicated (→ 7.). Otherwise semi-field or field tests with non-*Apis* bees have to be performed to address the concern (→15. or 16.).

15. Assess the effects of the a. i. to a non-*Apis* bee species relevant to the identified route of exposure in a semi-field test: Do results indicate minimal risk (no significant difference to control)?

Concerns raised in the screening procedure may be addressed by appropriately designed semi-field / field tests where possible effects are assessed against the criteria intended to reflect the protection goals. The derivation of assessment criteria for specific protection goals is discussed in Chapter 4. For further details on semi-field studies on non-*Apis* bees see Chapter 9.

Where in the semi-field test treatment results in no significant difference in relevant lethal and sublethal effects compared to untreated control, a minimal risk is indicated (→ 7.). Otherwise in a higher-tier evaluation a field test should be performed (→ 16.).

16. Assess the effects of the a.i. to a non-*Apis* bee species relevant to the identified route of exposure in a semi-field or a field test: Do results indicate minimal risk (no significant difference to control)?

Concerns raised in the screening-level assessment may be addressed by appropriately designed semi-field tests where possible effects are assessed against the evaluation criteria related to reflect the protection goals. The derivation of evaluation criteria for specific protection goals is discussed in Chapter 4. For further details on semi-field studies on non-*Apis* bees see Chapter 9.- As for honey bees, the choice between a semi-field test or a full field study depends on the outcome of lower tier studies and should also consider decisions for honey bees. If the results of semi-field or field test, in conjunction with information from lower tier studies and other relevant data indicate no

significant difference in relevant lethal and sublethal effects compared to untreated controls, minimal risk is indicated (→ 7.) Otherwise, further risk mitigation may be considered or the risk has to be presumed as significant (→ 17.).

17. Risk mitigation measures specific to non-*Apis* bee species possible?

Where the results of higher-tier semi-field and field tests on *non-Apis* bees indicate that the protection goals are not met, the assessment scheme may be reiterated considering specific measures designed to mitigating the exposure of non-*Apis* bees (→ 2.).

Note in this respect that semi-field and field test may be adapted in order to determine whether risk mitigation measures actually limit the exposure and potential impact on *non-Apis* bees.

18. Presumption of significant risk

If there are no measures available to mitigate the risk to honey bees and/or non-*Apis* bees indicated by the evaluation of the results of higher-tier semi-field and field tests against the protection goals, then a significant risk has to be presumed.

References

Alix A., Lewis G. 2010. Guidance for the assessment of risks to bees from the use of plant protection products under the framework of Council Directive 91/414 and Regulation 1107/2009. OEPP/EPPO, Bulletin OEPP/EPPO Bulletin 40, 196–203.

Candolfi M.P., Barrett K.L., Campbell P.J., Forster R., Grandy N., Huet M.C., Lewis G., Oomen P.A., Schmuck R., Vogt H. 2001. Guidance document on regulatory testing and risk assessment procedures for plant protection products with non-target arthropods, in ESCORT 2 workshop (European Standard Characteristics of non-target arthropod Regulatory Testing), Wageningen, The Netherlands. SETAC Publication, 46 pp.

9665 EPPO, 2010. Environmental risk assessment scheme for plant protection products,
9666 Chapter 10. Risk assessment to honey bees, PP 3/10 (3), OEPP/EPPO, Bulletin
9667 OEPP/EPPO Bulletin 40, 1–9.
9668 Mineau P, Harding, KM, Whiteside, M, Fletcher, MR, Garthwaite, D, Knopper, LD
9669 (2008) Using reports of honey bee mortality in the field to calibrate laboratory derived
9670 pesticide risk indices Environ. Entomol. 37(2): 546-554
9671

9672 **GLOSSARY OF TERMS**

9673

9674	µg/kg	Symbol for “micrograms per kilogram”
9675	µg·L ⁻¹	Symbol for “micrograms per liter”
9676	a.i.	Active Ingredient
9677	Bw	Body Weight
9678	CCD	Colony Collapse Disorder
9679	CFR	Code of Federal Regulations
9680	Colony	
9681	Cw	Concentration in water (µg/L)
9682	EC25	25% Effect Concentration
9683	EC50	50% (or Median) Effect Concentration
9684	ECOTOX	EPA managed database of ECOTOXicology data
9685	EEC	Estimated Environmental Concentration
9686	EFSA	European Food Safety Authority
9687	e.g.	Latin exempli gratia (“for example”)
9688	EPPO	European and Mediterranean Organization for Plant Protection
9689	et al.	Latin et alii (“and others”)
9690	Etc.	Latin et cetera (“and the rest” or “and so forth”)
9691	EU	European Union
9692	FAO	Food and Agricultural Organization (United Nations)
9693	FIFRA	Federal Insecticide Fungicide and Rodenticide Act
9694	Forager	
9695	g a.i./ha	grams of active ingredient per hectare
9696	GENEEC	GENeric Estimated Environmental Concentration
9697	Ha	hectare
9698	Hive	
9699	HQ	Hazard Quotient
9700	IAPV	Israeli Acute Paralysis Virus
9701	ICP-BR	International Commission for Plant-Bee Relationships
9702	i.e.	Latin for id est (“that is”)
9703	Kg	Kilogram(s)
9704	km	Kilometer(s)
9705	L	Liter
9706	lb a.i./A	Pound(s) of active ingredient per acre
9707	LC50	50% (or Median) Lethal Concentration
9708	LD50	50% (or Median) Lethal Dose
9709	LOC	Level of Concern
9710	Log	Logarithm
9711	LOQ	Level of Quantitation

9712	m	meter(s)
9713	mg	Milligram(s)
9714	mg/kg	Milligrams per kilogram (equivalent to ppm)
9715	mg/L	Milligrams per liter (equivalent to ppm)
9716	mi	mile(s)
9717	mL	milliliter
9718	n/a	Not applicable
9719	NASS	National Agricultural Statistics Service
9720	NOAEC	No Observable Adverse Effect Concentration.
9721	Nuc	
9722	OECD	Organization for Economic Cooperation and Development
9723	OEPP	Organisation Européenne et Méditerranéenne pour la Protection des
9724	Plantes (EPPO)	
9725	OPP	Office of Pesticide Programs, US Environmental Protection Agency
9726	PEIP	Pesticide Effects on Insect Pollinators (OECD)
9727	PMRA	Pest Management Regulatory Agency (Canada)
9728	ppb	Parts per Billion (equivalent to µg/L or µg/kg)
9729	ppm	Parts per Million (equivalent to mg/L or mg/kg)
9730	PPR	Plant Protection Products and the Residues (EPPO)
9731	PRZM	Pesticide Root Zone Model
9732	RQ	Risk Quotient
9733	SETAC	Society of Environmental Toxicology and Chemistry
9734	T-REX	Terrestrial Residue Exposure model
9735	USDA	United States Department of Agriculture
9736	USEPA	United States Environmental Protection Agency
9737	Worker bee	
9738		

9739

9740 **Acknowledgments**

9741

9742

9743 **SETAC Pellston Workshop on Pesticide Risk Assessment for Pollinators**

9744

9745 **Steering Committee**

9746

9747 Mike Coulson, Syngenta Ltd., UK

9748 Thomas Steeger, U.S. Environmental Protection Agency

9749 Joseph Wisk, BASF Corporation, Crop Solutions, US

9750 Dave Fischer, Bayer CropScience, US

9751 Thomas Moriarty, U.S. Environmental Protection Agency

9752 Mace Vaughan, Xerces Society for Invertebrate Conservation, US

9753 Franz Streissl, European Food Safety Authority

9754 Peter Delorme, Health Canada, Pest Management Regulatory Agency, Canada

9755 Jim Frazier, Pennsylvania State University, US

9756 Jochen Pflugfelder, Swiss Bee Research Center, Switzerland

9757 Christopher Lee-Steere, Australian Environment Agency Pty Ltd., Australia

9758 Jeff Pettis, U.S. Department of Agriculture

9759 Anne Alix, Ministry of Agriculture, Food, Fisheries, Rural Affairs and Spatial
9760 Planning, France

9761

9762

9763 **Workgroups**

9764

9765 **Exposure**

9766 Joseph Wisk, co-chair BASF Corporation, Crop Solutions, US

9767 Jens Pistorius, Julius Kühn-Institut, Institute for Plant Protection in Field Crops
9768 and Grassland, Germany, co-chair

9769 Mike Beevers, California Agricultural Research, Inc., US

9770 Richard Bireley, California Department of Pesticide Regulation, US

9771 Zak Browning, Browning's Honey Company, Inc., US

9772 Marie-Pierre Chauzat, French Agency for Food, Environmental and Occupational
9773 Health Safety, Sophia-Antipolis, France

9774 Jay Overmyer, Syngenta Crop Protection, LLC, US

9775 Alexander Nikolakis, Bayer CropScience AG, Development – Environmental
9776 Safety – Ecotoxicology – Bees, Germany

9777 Robyn Rose, U.S. Department of Agriculture Animal and Plant Health Inspection
9778 Service

9779 Robert Sebastien, Health Canada, Pest Management Regulatory Agency, Canada

9780 Bernard Vaissière, French National Institute for Agricultural Research, France

9781 Mace Vaughan, Xerces Society for Invertebrate Conservation, US

9782

9783 **Hazard, Laboratory**

9784 Jim Frazier, co-chair, Pennsylvania State University, US

9785 Jochen Pflugfelder, co-chair

9786 Pierrick Aupinel, INRA, Centre Poitou-Charentes, UE d'entomologie, France

9787 Axel Decourtye, ACTA, UMT PrADE, Germany

9788 Jamie Ellis, Honey Bee Research and Extension Laboratory, University of Florida,
9789 US

9790 Cynthia Scott-Dupree, School of Environmental Sciences, University of Guelph,
9791 Canada

9792 Zachary Huang, Michigan State University, US

9793 Volker Grimm, Helmholtz Center for Environmental Research – UFZ, Leipzig,
9794 Germany

9795 Helen Thompson, Food and Environment Research Agency, UK

9796 William Warren-Hicks, EcoStat, Inc., US

9797 Pamela Bachman, Monsanto Company, US

9798 Axel Dinter, DuPont de Nemours (Deutschland) GmbH, Germany

9799 Roberta C. F. Nocelli, Center for Agricultural Science – UFSCar – Araras – SP,
9800 Brazil

9801

9802 **Hazard, Semi field and Field**

9803 Jeff Pettis, co-chair

9804 Ingo Tornier, Eurofins Agrosience, Germany, co-chair

9805 Klaus Wallner, University of Hohenheim, Apiculture Institute, Germany

9806 Benard Vaissiere, Institut National de la Recherche Agronomique, Avignon,
9807 France

9808 Teodoro Stadler, Laboratorio de Toxicologia Ambiental, Instituto de Medicina y
9809 Biologia Experimental de Cuyo (IMBECU), Centro Cientifico Teconologico
9810 CONICET, Argentina

9811 Mark Clook, Chemicals Regulation Directorate, Health and Safety Executive, UK

9812 Wayne Hou, Health Canada, Pest Management Regulatory Agency, Canada

9813 Glynn Maynard, Office of the Chief Plant Protection Officer, Department of
9814 Agriculture, Fisheries and Forestry, Australia

- 9815 Roland Becker, BASF Aktiengesellschaft, Germany
- 9816 Mike Coulson, Syngenta Ltd, UK
- 9817 Dick Rogers, Bayer CropScience, US
- 9818 Pascal Jourdan, ITSAP – Institut de l’abeille, France
- 9819 Muo Kasina, Kenya Agricultural Research Institute, Kenya
- 9820
- 9821 **Risk Assessment**
- 9822 Anne Alix, co-chair, Ministry of Agriculture, Food, Fisheries, Rural Affairs and
- 9823 Spatial Planning, France
- 9824 Thomas Steeger, co-chair, U.S. Environmental Protection Agency
- 9825 Claire Brittain, Leuphana Univeristy of Lüneburg, Germany
- 9826 Dave Fischer, Bayer CropScience, US
- 9827 Reed Johnson, University of Nebraska- - Lincoln, US
- 9828 Erik Johansen, Washington State Department of Agriculture, US
- 9829 Thomas Moriarty, U.S. Environmental Protection Agency
- 9830 Franz Streissl, European Food Safety Authority
- 9831 Rolf Fischer, Federal Office of Consumer Protection and Food Safety, Germany
- 9832 Mark Miles, Dow AgroSciences, UK
- 9833 Christopher Lee-Steere, Australian Environment Agency Party Ltd., Australia
- 9834 Michael Fry, American Bird Conservancy, US
- 9835
- 9836
- 9837
- 9838
- 9839